TOWN OF MILTON

SARATOGA COUNTY, NEW YORK

New Highway Facility — Cold Storage Pre-Engineered Metal Building (PEMB)

CONTRACT SPECIFICATIONS AND BID DOCUMENTS

SUPERVISOR SCOTT OSTRANDER

<u>COUNCILMAN</u> RYAN ISACHESEN

JOHN FROLISH

FRANK BLAISDELL

COUNCILWOMAN BARBRA KERR

PREPARED BY:




DELAWARE ENGINEERING, D.P.C.

28 Madison Avenue Extension Albany, New York 12203 (518) 452-1290

May 2023





SECTION 000110 TABLE OF CONTENTS

VOLUME 1 OF 1

PROCUREMENT AND CONTRACTING REQUIREMENTS GROUP

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

INTRODUCTORY INFORMATION

Document 000110 Table of Contents

PROCUREMENT REQUIREMENTS

| Document 001113 | Notice to Bidders |
|--------------------|---------------------------------------|
| Document 002113 | Instructions to Bidders |
| Document 002113.10 | Instructions to Bidders Information |
| Document 002213 | Supplementary Instructions to Bidders |
| Document 002513 | Prebid Meetings |
| Document 002600 | Procurement Substitution Procedures |
| Document 003113 | Preliminary Schedules |

PROCUREMENT FORMS AND SUPPLEMENTS

Document 004113 Bid Form – AIA Stipulated Sum – Cold Storage PEMB

Document 004313 Bid Security Form

Additional Documentation

- 1. Non-collusive bidding certification
- 2. Certification of non-segregated facilities
- 3. Equal Employment Opportunity
- 4. Iranian Energy Sector Divestment Certification

CONTRACTING REQUIREMENTS

Section 006000

Project Forms

- 1. Standard Form of Agreement AIA A151
- 2. General Conditions AIA A201
- 3. Performance and Payment Bonds AIA A312
- 4. Request For Information AIA G716
- 5. Insurance Requirements
- 6. Partial Waiver of Lien
- 7. Prevailing Wage Requirements

SECTION 000110 TABLE OF CONTENTS

SPECIFICATIONS GROUP

GENERAL REQUIREMENTS SUBGROUP

DIVISION 01 – GENERAL REQUIREMENTS

| Section 011000 | Summary |
|----------------|---|
| Section 011000 | Contract Summary |
| Section 012500 | Substitution Procedures |
| Section 012600 | Contract Modification Procedures |
| Section 012900 | Payment Procedures |
| Section 013100 | Project Management and Coordination |
| Section 013200 | Construction Progress Documentation |
| Section 013300 | Submittal Procedures |
| Section 014000 | Quality Requirements |
| Section 016000 | Product Requirements |
| Section 017300 | Execution |
| Section 017700 | Closeout Procedures |
| Section 017823 | Operation and Maintenance Data |
| Section 017839 | Project Record Documents |

DIVISION 07 – THERMAL AND MOISTURE PROTECTION

| Section 074116 | Insulated Metal Roof Panels |
|-------------------|-----------------------------|
| Section 074213.19 | Insulated Metal Wall Panels |

Section 077253 Snow Guards

DIVISION 13 – SPECIAL CONSTRUCTION

Section 133419 Metal Building Systems



INVITATION TO BID

Notice is hereby given that sealed bids will be received until **1:00 P.M.**, **June 23, 2023**, at the Town of Milton Offices Attention: Town Clerk, located at 503 Geyser Road, Ballston Spa, NY 12020; at which time bids will be publicly opened and read aloud for the Rowland Street Highway Facility – Cold Storage PEMB.

A pre-bid conference will be held for this project on Thursday, June 8, 2023 at 1:00 PM via zoom at the following link:

https://us02web.zoom.us/j/87110767969

Bidding contractors are strongly encouraged to have an authorized representative of their firm attend the pre-bid conference.

Bids will be received for the Single Prime Contract Project consisting of the following prime contract which covers the Rowland Street Highway Facility – Cold Storage PEMB:

Pre-Engineered Metal Building Design, Fabrication, & Delivery

Fabrication and Delivery of PEMB must be completed by December 26, 2023.

Contract Documents, including Advertisement For Bids, Information For Bidders, Labor and Employment, Additional Instructions, Bid Documents, Agreement, General Conditions, General Requirements, Specifications, Contract Drawings and any Addenda, may be examined at no expense on-line at the following website: https://de.biddyhq.com or at the office of Delaware Engineering, D.P.C., 28 Madison Ave Extension Albany NY, 12203.

Digital copies of the Contract Documents may be obtained online as a download for a non-refundable fee of One Hundred Dollars (\$100.00) from the website: https://de.biddyhq.com. Complete hardcopy sets of bidding documents may be obtained from REV, 330 Route 17A, Suite #2, Goshen, NY 10924, Tel: 1-877-272-0216, upon depositing the sum of 100.00 Dollars (\$100.00) for each combined set of documents. Checks or money orders shall be made payable to Delaware Engineering, D.P.C. Cash deposits will not be accepted. Any Bidder requiring documents to be shipped shall make arrangements with REV and pay for all packaging and shipping costs.

Any Bidder who submitted completed Bid Forms to the Town of Milton, upon returning such set in good condition within thirty days following the award of the contract or rejection of the bids, will be refunded his full payment. Deposits will not be refunded to any non-bidder (including material suppliers, subcontractors, or those that provide quotes to Bidders). Questions should be sent to Cody Messier, PE via email at cmessier@delawareengineering.com.

Please note that https://de.biddyhq.com is the designated location and means for distributing and obtaining all bid package information. All Bidders are urged to register to ensure receipt of all necessary information including bid addenda. All bid addenda will be transmitted to registered plan holders via email and will be available at https://de.biddyhq.com. Plan holders who have paid for hard copies of the bid documents will need to make the determination if hard copies of the addenda are required for their use, and coordinate directly with REV for hard copies of addenda to be issued. There will be no charge for registered plan holders to obtain hard copies of the bid addenda.

Each bid must be accompanied by security in an amount not less than five percent (5%) of the amount of the bid in the form and subject to the conditions provided in the Information for Bidders. No Bidder may withdraw his bid within forty-five (45) days after the actual date of opening thereof.

This is an exempt capital improvement project, and Bidders shall not include taxes in the cost of materials which are to be incorporated into the work, and which are to be separately sold by the Contractor to the Town of Milton prior to incorporation into the work of the Contract.

Bids may be held by the Owner for a period not to exceed forty-five (45) days from the date of the opening of Bid for the purpose of reviewing the bids and investigating the qualifications of the bidder(s) and the subsequent approval of the bids and related documents by the Owner. The Owner reserves the right to reject any and all bids, or waive any informalities in the bidding, without explanation, and to select the Bid, the acceptance of which, in its judgement, will best assure the efficient performance of the work.

The contractors must also be aware that they must comply with the most recent State wage rates under New York State Department of Labor (www.labor.state.ny.us). In addition, the contractor must comply, if applicable, with Labor Law 220, section 220-h, which requires that on all public work projects of at least \$250,000.00, all laborers, workers and mechanics on the site be certified as having successfully completed the OSHA 10-hour construction safety and health course.

The right is reserved to waive any informalities in the Bid and to reject any or all Bids.

DOCUMENT 002113

INSTRUCTIONS TO BIDDERS

1.1 INSTRUCTIONS TO BIDDERS

- A. AIA Document A701, "Instructions to Bidders," is hereby incorporated into the Procurement and Contracting Requirements by reference.
 - 1. A copy of AIA Document A701, "Instructions to Bidders," is bound in this Project Manual.

END OF DOCUMENT 002113

Instructions to Bidders

for the following Project: (Name, location, and detailed description)

Town of Milton Rowland Street Highway Facility - Cold Storage PEMB

THE OWNER:

(Name, legal status, address, and other information)

Town of Milton 503 Geyser Road, Ballston Spa, NY 12020

THE ARCHITECT:

(Name, legal status, address, and other information)

Delaware Engineering, DPC 28 Madison Ave Ext., Albany, NY 12203

TABLE OF ARTICLES

- 1 DEFINITIONS
- 2 BIDDER'S REPRESENTATIONS
- **3 BIDDING DOCUMENTS**
- 4 BIDDING PROCEDURES
- 5 CONSIDERATION OF BIDS
- 6 POST-BID INFORMATION
- 7 PERFORMANCE BOND AND PAYMENT BOND
- 8 ENUMERATION OF THE PROPOSED CONTRACT DOCUMENTS

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An Additions and Deletions Report that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

FEDERAL, STATE, AND LOCAL LAWS MAY IMPOSE REQUIREMENTS ON PUBLIC PROCUREMENT CONTRACTS. CONSULT LOCAL AUTHORITIES OR AN ATTORNEY TO VERIFY REQUIREMENTS APPLICABLE TO THIS PROCUREMENT BEFORE COMPLETING THIS FORM.

It is intended that AIA Document G612[™]–2017, Owner's Instructions to the Architect, Parts A and B will be completed prior to using this document.

ARTICLE 1 DEFINITIONS

- § 1.1 Bidding Documents include the Bidding Requirements and the Proposed Contract Documents. The Bidding Requirements consist of the advertisement or invitation to bid, Instructions to Bidders, supplementary instructions to bidders, the bid form, and any other bidding forms. The Proposed Contract Documents consist of the unexecuted form of Agreement between the Owner and Contractor and that Agreement's Exhibits, Conditions of the Contract (General, Supplementary and other Conditions), Drawings, Specifications, all Addenda, and all other documents enumerated in Article 8 of these Instructions.
- § 1.2 Definitions set forth in the General Conditions of the Contract for Construction, or in other Proposed Contract Documents apply to the Bidding Documents.
- § 1.3 Addenda are written or graphic instruments issued by the Architect, which, by additions, deletions, clarifications, or corrections, modify or interpret the Bidding Documents.
- § 1.4 A Bid is a complete and properly executed proposal to do the Work for the sums stipulated therein, submitted in accordance with the Bidding Documents.
- § 1.5 The Base Bid is the sum stated in the Bid for which the Bidder offers to perform the Work described in the Bidding Documents, to which Work may be added or deleted by sums stated in Alternate Bids.
- § 1.6 An Alternate Bid (or Alternate) is an amount stated in the Bid to be added to or deducted from, or that does not change, the Base Bid if the corresponding change in the Work, as described in the Bidding Documents, is accepted.
- § 1.7 A Unit Price is an amount stated in the Bid as a price per unit of measurement for materials, equipment, or services, or a portion of the Work, as described in the Bidding Documents.
- § 1.8 A Bidder is a person or entity who submits a Bid and who meets the requirements set forth in the Bidding Documents.
- § 1.9 A Sub-bidder is a person or entity who submits a bid to a Bidder for materials, equipment, or labor for a portion of the Work.

ARTICLE 2 BIDDER'S REPRESENTATIONS

- § 2.1 By submitting a Bid, the Bidder represents that:
 - .1 the Bidder has read and understands the Bidding Documents;
 - .2 the Bidder understands how the Bidding Documents relate to other portions of the Project, if any, being bid concurrently or presently under construction;
 - .3 the Bid complies with the Bidding Documents;
 - the Bidder has visited the site, become familiar with local conditions under which the Work is to be performed, and has correlated the Bidder's observations with the requirements of the Proposed Contract Documents;
 - .5 the Bid is based upon the materials, equipment, and systems required by the Bidding Documents without exception; and
 - .6 the Bidder has read and understands the provisions for liquidated damages, if any, set forth in the form of Agreement between the Owner and Contractor.

ARTICLE 3 BIDDING DOCUMENTS

§ 3.1 Distribution

§ 3.1.1 Bidders shall obtain complete Bidding Documents, as indicated below, from the issuing office designated in the advertisement or invitation to bid, for the deposit sum, if any, stated therein.

(Indicate how, such as by email, website, host site/platform, paper copy, or other method Bidders shall obtain Bidding Documents.)

Refer to Document 001113 - "Notice To Bidders"

2

- § 3.1.2 Any required deposit shall be refunded to Bidders who submit a bona fide Bid and return the paper Bidding Documents in good condition within ten days after receipt of Bids. The cost to replace missing or damaged paper documents will be deducted from the deposit. A Bidder receiving a Contract award may retain the paper Bidding Documents, and the Bidder's deposit will be refunded.
- § 3.1.3 Bidding Documents will not be issued directly to Sub-bidders unless specifically offered in the advertisement or invitation to bid, or in supplementary instructions to bidders.
- § 3.1.4 Bidders shall use complete Bidding Documents in preparing Bids. Neither the Owner nor Architect assumes responsibility for errors or misinterpretations resulting from the use of incomplete Bidding Documents.
- § 3.1.5 The Bidding Documents will be available for the sole purpose of obtaining Bids on the Work. No license or grant of use is conferred by distribution of the Bidding Documents.

§ 3.2 Modification or Interpretation of Bidding Documents

- § 3.2.1 The Bidder shall carefully study the Bidding Documents, shall examine the site and local conditions, and shall notify the Architect of errors, inconsistencies, or ambiguities discovered and request clarification or interpretation pursuant to Section 3.2.2.
- § 3.2.2 Requests for clarification or interpretation of the Bidding Documents shall be submitted by the Bidder in writing and shall be received by the Architect at least seven days prior to the date for receipt of Bids. (Indicate how, such as by email, website, host site/platform, paper copy, or other method Bidders shall submit requests for clarification and interpretation.)

Refer to Document 002213 - "Supplementary Instructions to Bidders"

§ 3.2.3 Modifications and interpretations of the Bidding Documents shall be made by Addendum. Modifications and interpretations of the Bidding Documents made in any other manner shall not be binding, and Bidders shall not rely upon them.

§ 3.3 Substitutions

§ 3.3.1 The materials, products, and equipment described in the Bidding Documents establish a standard of required function, dimension, appearance, and quality to be met by any proposed substitution.

§ 3.3.2 Substitution Process

- § 3.3.2.1 Written requests for substitutions shall be received by the Architect at least ten days prior to the date for receipt of Bids. Requests shall be submitted in the same manner as that established for submitting clarifications and interpretations in Section 3.2.2.
- § 3.3.2.2 Bidders shall submit substitution requests on a Substitution Request Form if one is provided in the Bidding Documents.
- § 3.3.2.3 If a Substitution Request Form is not provided, requests shall include (1) the name of the material or equipment specified in the Bidding Documents; (2) the reason for the requested substitution; (3) a complete description of the proposed substitution including the name of the material or equipment proposed as the substitute, performance and test data, and relevant drawings; and (4) any other information necessary for an evaluation. The request shall include a statement setting forth changes in other materials, equipment, or other portions of the Work, including changes in the work of other contracts or the impact on any Project Certifications (such as LEED), that will result from incorporation of the proposed substitution.
- § 3.3.3 The burden of proof of the merit of the proposed substitution is upon the proposer. The Architect's decision of approval or disapproval of a proposed substitution shall be final.
- § 3.3.4 If the Architect approves a proposed substitution prior to receipt of Bids, such approval shall be set forth in an Addendum. Approvals made in any other manner shall not be binding, and Bidders shall not rely upon them.

§ 3.3.5 No substitutions will be considered after the Contract award unless specifically provided for in the Contract Documents.

§ 3.4 Addenda

§ 3.4.1 Addenda will be transmitted to Bidders known by the issuing office to have received complete Bidding Documents.

(Indicate how, such as by email, website, host site/platform, paper copy, or other method Addenda will be transmitted.)

Addenda will be distributed to bidders via email

- § 3.4.2 Addenda will be available where Bidding Documents are on file.
- § 3.4.3 Addenda will be issued no later than four days prior to the date for receipt of Bids, except an Addendum withdrawing the request for Bids or one which includes postponement of the date for receipt of Bids.
- § 3.4.4 Prior to submitting a Bid, each Bidder shall ascertain that the Bidder has received all Addenda issued, and the Bidder shall acknowledge their receipt in the Bid.

ARTICLE 4 BIDDING PROCEDURES

§ 4.1 Preparation of Bids

- § 4.1.1 Bids shall be submitted on the forms included with or identified in the Bidding Documents.
- § 4.1.2 All blanks on the bid form shall be legibly executed. Paper bid forms shall be executed in a non-erasable medium.
- § 4.1.3 Sums shall be expressed in both words and numbers, unless noted otherwise on the bid form. In case of discrepancy, the amount entered in words shall govern.
- § 4.1.4 Edits to entries made on paper bid forms must be initialed by the signer of the Bid.
- § 4.1.5 All requested Alternates shall be bid. If no change in the Base Bid is required, enter "No Change" or as required by the bid form.
- § 4.1.6 Where two or more Bids for designated portions of the Work have been requested, the Bidder may, without forfeiture of the bid security, state the Bidder's refusal to accept award of less than the combination of Bids stipulated by the Bidder. The Bidder shall neither make additional stipulations on the bid form nor qualify the Bid in any other manner.
- § 4.1.7 Each copy of the Bid shall state the legal name and legal status of the Bidder. As part of the documentation submitted with the Bid, the Bidder shall provide evidence of its legal authority to perform the Work in the jurisdiction where the Project is located. Each copy of the Bid shall be signed by the person or persons legally authorized to bind the Bidder to a contract. A Bid by a corporation shall further name the state of incorporation and have the corporate seal affixed. A Bid submitted by an agent shall have a current power of attorney attached, certifying the agent's authority to bind the Bidder.
- § 4.1.8 A Bidder shall incur all costs associated with the preparation of its Bid.

§ 4.2 Bid Security

§ 4.2.1 Each Bid shall be accompanied by the following bid security: (*Insert the form and amount of bid security.*)

Refer to Document 001113 - "Notice To Bidders"

§ 4.2.2 The Bidder pledges to enter into a Contract with the Owner on the terms stated in the Bid and shall, if required, furnish bonds covering the faithful performance of the Contract and payment of all obligations arising thereunder. Should the Bidder refuse to enter into such Contract or fail to furnish such bonds if required, the amount

of the bid security shall be forfeited to the Owner as liquidated damages, not as a penalty. In the event the Owner fails to comply with Section 6.2, the amount of the bid security shall not be forfeited to the Owner.

- § 4.2.3 If a surety bond is required as bid security, it shall be written on AIA Document A310™. Bid Bond, unless otherwise provided in the Bidding Documents. The attorney-in-fact who executes the bond on behalf of the surety shall affix to the bond a certified and current copy of an acceptable power of attorney. The Bidder shall provide surety bonds from a company or companies lawfully authorized to issue surety bonds in the jurisdiction where the Project is located.
- § 4.2.4 The Owner will have the right to retain the bid security of Bidders to whom an award is being considered until (a) the Contract has been executed and bonds, if required, have been furnished; (b) the specified time has elapsed so that Bids may be withdrawn; or (c) all Bids have been rejected. However, if no Contract has been awarded or a Bidder has not been notified of the acceptance of its Bid, a Bidder may, beginning days after the opening of Bids, withdraw its Bid and request the return of its bid security.

§ 4.3 Submission of Bids

§ 4.3.1 A Bidder shall submit its Bid as indicated below:

(Indicate how, such as by website, host site/platform, paper copy, or other method Bidders shall submit their Bid.)

Refer to Document 001113 - "Notice To Bidders"

- § 4.3.2 Paper copies of the Bid, the bid security, and any other documents required to be submitted with the Bid shall be enclosed in a sealed opaque envelope. The envelope shall be addressed to the party receiving the Bids and shall be identified with the Project name, the Bidder's name and address, and, if applicable, the designated portion of the Work for which the Bid is submitted. If the Bid is sent by mail, the sealed envelope shall be enclosed in a separate mailing envelope with the notation "SEALED BID ENCLOSED" on the face thereof.
- § 4.3.3 Bids shall be submitted by the date and time and at the place indicated in the invitation to bid. Bids submitted after the date and time for receipt of Bids, or at an incorrect place, will not be accepted.
- § 4.3.4 The Bidder shall assume full responsibility for timely delivery at the location designated for receipt of Bids.
- § 4.3.5 A Bid submitted by any method other than as provided in this Section 4.3 will not be accepted.

§ 4.4 Modification or Withdrawal of Bid

- § 4.4.1 Prior to the date and time designated for receipt of Bids, a Bidder may submit a new Bid to replace a Bid previously submitted, or withdraw its Bid entirely, by notice to the party designated to receive the Bids. Such notice shall be received and duly recorded by the receiving party on or before the date and time set for receipt of Bids. The receiving party shall verify that replaced or withdrawn Bids are removed from the other submitted Bids and not considered. Notice of submission of a replacement Bid or withdrawal of a Bid shall be worded so as not to reveal the amount of the original Bid.
- § 4.4.2 Withdrawn Bids may be resubmitted up to the date and time designated for the receipt of Bids in the same format as that established in Section 4.3, provided they fully conform with these Instructions to Bidders. Bid security shall be in an amount sufficient for the Bid as resubmitted.
- § 4.4.3 After the date and time designated for receipt of Bids, a Bidder who discovers that it made a clerical error in its Bid shall notify the Architect of such error within two days, or pursuant to a timeframe specified by the law of the jurisdiction where the Project is located, requesting withdrawal of its Bid. Upon providing evidence of such error to the reasonable satisfaction of the Architect, the Bid shall be withdrawn and not resubmitted. If a Bid is withdrawn pursuant to this Section 4.4.3, the bid security will be attended to as follows:

(State the terms and conditions, such as Bid rank, for returning or retaining the bid security.)

In the event of withdrawl, the Owneer may declare the amount of bid security forfeited.

ARTICLE 5 CONSIDERATION OF BIDS

§ 5.1 Opening of Bids

If stipulated in an advertisement or invitation to bid, or when otherwise required by law, Bids properly identified and received within the specified time limits will be publicly opened and read aloud. A summary of the Bids may be made available to Bidders.

§ 5.2 Rejection of Bids

Unless otherwise prohibited by law, the Owner shall have the right to reject any or all Bids.

§ 5.3 Acceptance of Bid (Award)

§ 5.3.1 It is the intent of the Owner to award a Contract to the lowest responsive and responsible Bidder, provided the Bid has been submitted in accordance with the requirements of the Bidding Documents. Unless otherwise prohibited by law, the Owner shall have the right to waive informalities and irregularities in a Bid received and to accept the Bid which, in the Owner's judgment, is in the Owner's best interests.

§ 5.3.2 Unless otherwise prohibited by law, the Owner shall have the right to accept Alternates in any order or combination, unless otherwise specifically provided in the Bidding Documents, and to determine the lowest responsive and responsible Bidder on the basis of the sum of the Base Bid and Alternates accepted.

ARTICLE 6 POST-BID INFORMATION

§ 6.1 Contractor's Qualification Statement

Bidders to whom award of a Contract is under consideration shall submit to the Architect, upon request and within the timeframe specified by the Architect, a properly executed AIA Document A305™, Contractor's Qualification Statement, unless such a Statement has been previously required and submitted for this Bid.

§ 6.2 Owner's Financial Capability

A Bidder to whom award of a Contract is under consideration may request in writing, fourteen days prior to the expiration of the time for withdrawal of Bids, that the Owner furnish to the Bidder reasonable evidence that financial arrangements have been made to fulfill the Owner's obligations under the Contract. The Owner shall then furnish such reasonable evidence to the Bidder no later than seven days prior to the expiration of the time for withdrawal of Bids. Unless such reasonable evidence is furnished within the allotted time, the Bidder will not be required to execute the Agreement between the Owner and Contractor.

§ 6.3 Submittals

§ 6.3.1 After notification of selection for the award of the Contract, the Bidder shall, as soon as practicable or as stipulated in the Bidding Documents, submit in writing to the Owner through the Architect:

- .1 a designation of the Work to be performed with the Bidder's own forces;
- .2 names of the principal products and systems proposed for the Work and the manufacturers and suppliers of each; and
- names of persons or entities (including those who are to furnish materials or equipment fabricated to a special design) proposed for the principal portions of the Work.

§ 6.3.2 The Bidder will be required to establish to the satisfaction of the Architect and Owner the reliability and responsibility of the persons or entities proposed to furnish and perform the Work described in the Bidding Documents.

§ 6.3.3 Prior to the execution of the Contract, the Architect will notify the Bidder if either the Owner or Architect, after due investigation, has reasonable objection to a person or entity proposed by the Bidder. If the Owner or Architect has reasonable objection to a proposed person or entity, the Bidder may, at the Bidder's option, withdraw the Bid or submit an acceptable substitute person or entity. The Bidder may also submit any required adjustment in the Base Bid or Alternate Bid to account for the difference in cost occasioned by such substitution. The Owner may accept the adjusted bid price or disqualify the Bidder. In the event of either withdrawal or disqualification, bid security will not be forfeited.

§ 6.3.4 Persons and entities proposed by the Bidder and to whom the Owner and Architect have made no reasonable objection must be used on the Work for which they were proposed and shall not be changed except with the written consent of the Owner and Architect.

ARTICLE 7 PERFORMANCE BOND AND PAYMENT BOND

§ 7.1 Bond Requirements

- § 7.1.1 If stipulated in the Bidding Documents, the Bidder shall furnish bonds covering the faithful performance of the Contract and payment of all obligations arising thereunder.
- § 7.1.2 If the furnishing of such bonds is stipulated in the Bidding Documents, the cost shall be included in the Bid. If the furnishing of such bonds is required after receipt of bids and before execution of the Contract, the cost of such bonds shall be added to the Bid in determining the Contract Sum.
- § 7.1.3 The Bidder shall provide surety bonds from a company or companies lawfully authorized to issue surety bonds in the jurisdiction where the Project is located.
- § 7.1.4 Unless otherwise indicated below, the Penal Sum of the Payment and Performance Bonds shall be the amount of the Contract Sum.
- (If Payment or Performance Bonds are to be in an amount other than 100% of the Contract Sum, indicate the dollar amount or percentage of the Contract Sum.)

§ 7.2 Time of Delivery and Form of Bonds

- § 7.2.1 The Bidder shall deliver the required bonds to the Owner not later than three days following the date of execution of the Contract. If the Work is to commence sooner in response to a letter of intent, the Bidder shall, prior to commencement of the Work, submit evidence satisfactory to the Owner that such bonds will be furnished and delivered in accordance with this Section 7.2.1.
- § 7.2.2 Unless otherwise provided, the bonds shall be written on AIA Document A312, Performance Bond and Payment Bond.
- § 7.2.3 The bonds shall be dated on or after the date of the Contract.
- § 7.2.4 The Bidder shall require the attorney-in-fact who executes the required bonds on behalf of the surety to affix to the bond a certified and current copy of the power of attorney.

ARTICLE 8 ENUMERATION OF THE PROPOSED CONTRACT DOCUMENTS

- § 8.1 Copies of the proposed Contract Documents have been made available to the Bidder and consist of the following documents:
 - .1 AIA Document A101TM_2017, Standard Form of Agreement Between Owner and Contractor, unless otherwise stated below.
 - (Insert the complete AIA Document number, including year, and Document title.)
 - Not applicable to this project
 - .2 AIA Document A101TM–2017, Exhibit A, Insurance and Bonds, unless otherwise stated below. (Insert the complete AIA Document number, including year, and Document title.)
 - Not applicable to this project
 - .3 AIA Document A201TM–2017, General Conditions of the Contract for Construction, unless otherwise stated below.
 - (Insert the complete AIA Document number, including year, and Document title.)

(3B9ADA47)

| | otherwise stated below. (Insert the complete AIA Docum | ent number, including | year, and Document title.) | |
|----|--|------------------------|------------------------------|------------------|
| | | | | |
| | | | | |
| | 5 AIA Document E203 TM —2013, Buindicated below: (Insert the date of the E203-201.) | _ | odeling and Digital Data E | xhibit, dated as |
| | Not applicable to this project | | | |
| | 6 Drawings | | | |
| | Number Per Drawings List on Covershee | Title | Date | |
| | 7 Specifications | | | |
| | Section Per Table of Conents | Title | Date | Pages |
| .: | 8 Addenda: | | | |
| | Number | Date | Pages | |
| | Other Exhibits: (Check all boxes that apply and required.) | include appropriate in | nformation identifying the e | exhibit where |
| | [] AIA Document E204 TM —(Insert the date of the E | | ects Exhibit, dated as indic | ated below: |
| | [] The Sustainability Plan: | | | |
| | Title | Date | Pages | |
| | [] Supplementary and other | Conditions of the Con | tract: | |
| | Document | Title | Date | Pages |
| · | Other documents listed below: (List here any additional document) | ents that are intended | to form part of the Proposo | ed Contract |
| | Documents.) | | | |

.4 AIA Document A151TM–2019, Standard Form of Agreement between Owner and Vendor for Furniture, Furnishings, and Equipment (FF&E), unless



DOCUMENT 002113.10 INSTRUCTIONS TO BIDDERS INFORMATION

Addenda, if any, will be issued to only those persons whose name and address are on record with the Owner as having obtained the Contract Documents.

Contractors shall only obtain documents from the bidding service in order ensure to be placed on the official Plan Holder List, to receive Addenda and any other Bid correspondence. Bids received from Contractors other than those on the official Plan Holders List will not be accepted.

In order to be considered as a viable bidder, all prospective Prime Contractors are required, and subcontractors and suppliers are also encouraged, to be registered as a plan holder under this specific project on www.debiddocuments.com. This allows identification of plan holders and ensures there is a record of where addenda and clarifications are sent along with contractor contact information so that contact can be made to any prospective bidder if needed.

The successful bidder will be promptly notified and must be prepared to enter into a contract for the services requested in conformity with the information in the proposal.

No questions or inquiries regarding this bid will be accepted within three (3) business days prior to the bid opening.

Questions regarding the Contract Documents are to be directed to Cody Messier, P.E., Delaware Engineering, D.P.C., in writing via email, at: cmessier@delawareengineering.com.

Bidders shall promptly notify Cody Messier, P.E., Delaware Engineering, D.P.C., in writing by email, of any errors, omissions, conflicts or ambiguity within the Contract Documents, as soon as possible and ideally within 5 days prior to the bid, but not later than within 7 days of bid opening.

Cody Messier, P.E., Delaware Engineering, D.P.C. to Bidders listed on the official Plan Holders List. An emailed response from the Bidder, to the Addendum sent by Cody Messier, P.E., Delaware Engineering, D.P.C. will act as proof that the Bidder received the Addendum. In addition, to an emailed response, Bidders must acknowledge receipt of all Addenda by signing and dating each Addendum and the Acknowledgement of Receipt of Addenda, Failure of any Bidder to receive any such Addendum or interpretation shall not relive such Bidder from any obligation under this Bid submittal. All Addenda issued shall become part of the Contract Documents.

All bids must include the completed Bid Form, Non-Collusive Bidding and Disbarment Certifications, and Lobbying Certifications. No bidder may withdraw his/her bid withinforty-five (45) calendar days after the actual date of the opening thereof.

Bidders **must** provide prices for **all** items, including all alternates. The Town of Milton reserves the right to accept or reject any or all alternates.

Each bid must be accompanied by security in an amount not less than five percent (5%) of the amount of the bid in the form and subject to the conditions provided in the Instructions to Bidders.

DOCUMENT 002113.10 INSTRUCTIONS TO BIDDERS INFORMATION

The Bidders to whom the Contracts are awarded will be required to furnish Performance, Payment and Guarantee Bonds from an acceptable Surety Company for an amount not less than 100% of the accepted bid.

The successful Bidder will be required to comply with all provisions of the Federal Government Equal Employment Opportunity clauses issued by the Secretary of Labor on May 2, 1968 and published in the Federal Register (41 CFR Part 60-1, 33 F.2 7804).

This public work contract requires that not less than the minimum salaries and wages set forth in the Contract Documents (see Exhibits) must be paid on this project; that the Contractor must ensure that employees and applicants for employment are not discriminated against because of their race, creed, color, religion, sex or national origin. The Contractor(s) must comply with the State wage rates under New York State Department of Labor **PRC# 2021012906.** (www.labor.state.ny.us).

This public works contract requires that all Contractors comply with Labor Law 220, Section 220-h, which requires that on all public work projects of at least \$25,000, all laborers, workers and mechanics on the site be certified as having successfully completed the OSHA 10-hour construction safety and health course.

The Contractor must also be aware that, in conformance with Workers' Compensation Law §57, the contractor must provide either form CE-200 (Certificate of Attestation of Exemption from NYS Workers' Compensation and/or Disability Benefits Coverage), or form C-105.2 (Certificate of Workers' Compensation Insurance), or form SI-12 (Certificate of Workers' Compensation Self-Insurance) http://www.wcb.state.ny.us/content/main/Employers/IM.pdf before the Notice to Proceed can be issued.

The Town of Milton reserves the right to consider the bids for forty-five (45) days after receipt before awarding any Contract, and to waive any minor informalities in, and to reject, any and all bids. All bids are subject to final review and approval by the Town of Milton before any award of contract may be made. Receipt of bids by the Town of Milton shall not be construed as authority to bind the Town of Milton.

The work shall be substantially completed 180 calendar days from Notice to Proceed and completed and ready for final payment on **December 26, 2023.**

END OF DOCUMENT 002213.10

DOCUMENT 002213

SUPPLEMENTARY INSTRUCTIONS TO BIDDERS

1.1 INSTRUCTIONS TO BIDDERS

- A. Instructions to Bidders for Project consist of the following:
 - 1. AIA Document A701, "Instructions to Bidders."
 - 2. The following Supplementary Instructions to Bidders that modify and add to the requirements of the Instructions to Bidders.

1.2 SUPPLEMENTARY INSTRUCTIONS TO BIDDERS, GENERAL

A. The following supplements modify AIA Document A701, "Instructions to Bidders." Where a portion of the Instructions to Bidders is modified or deleted by these Supplementary Instructions to Bidders, unaltered portions of the Instructions to Bidders shall remain in effect.

1.3 ARTICLE 2 - BIDDER'S REPRESENTATIONS

- A. Add Section 2.1.3.1:
 - 1. 2.1.3.1 The Bidder has investigated all required fees, permits, and regulatory requirements of authorities having jurisdiction and has properly included in the submitted bid the cost of such fees, permits, and requirements not otherwise indicated as provided by Owner.
- B. Add Section 2.1.5:
 - 1. 2.1.5 The Bidder is a properly licensed Contractor according to the laws and regulations of the State of New York and meets qualifications indicated in the Procurement and Contracting Documents.
- C. Add Section 2.1.6:
 - 1. 2.1.6 The Bidder has incorporated into the Bid adequate sums for work performed by installers whose qualifications meet those indicated in the Procurement and Contracting Documents.

1.4 ARTICLE 3 - BIDDING DOCUMENTS

- A. 3.2 Interpretation or Correction of Procurement and Contracting Documents:
 - 1. Add Section 3.2.2.1:
 - a. 3.2.2.1 Submit Bidder's Requests for Interpretation using form bound in the Project Manual.

B. 3.4 - Addenda:

- 1. Delete Section 3.4.3 and replace with the following:
 - a. 3.4.3 Addenda may be issued at any time prior to the receipt of bids.
- 2. Add Section 3.4.4.1:
 - a. 3.4.4.1 Owner may elect to waive the requirement for acknowledging receipt of 3.4.4 Addenda as follows:
 - 3.4.4.1.1 Information received as part of the Bid indicates that the Bid, as submitted, reflects modifications to the Procurement and Contracting Documents included in an unacknowledged Addendum.
 - 2) 3.4.4.1.2 Modifications to the Procurement and Contracting Documents in an unacknowledged Addendum do not, in the opinion of Owner, affect the Contract Sum or Contract Time.

1.5 ARTICLE 4 - BIDDING PROCEDURES

- A. 4.1 Preparation of Bids:
 - 1. Add Section 4.1.1.1:
 - a. 4.1.1.1 Printable electronic Bid Forms and related documents are available from Architect.
 - 2. Add Section 4.1.8:
 - a. 4.1.8 The Bid shall include unit prices when called for by the Procurement and Contracting Documents. Owner may elect to consider unit prices in the determination of award. Unit prices will be incorporated into the Contract.
 - 3. Add Section 4.1.9:
 - a. 4.1.9 Owner may elect to disqualify a bid due to failure to submit a bid in the form requested, failure to bid requested alternates or unit prices, failure to complete entries in all blanks in the Bid Form, or inclusion by the Bidder of any alternates, conditions, limitations or provisions not called for.
- B. 4.3 Submission of Bids:
 - 1. Add Section 4.3.1.2:
 - a. 4.3.1.2 Include Bidder's Contractor License Number applicable in Project jurisdiction on the face of the sealed bid envelope.
- C. 4.4 Modification or Withdrawal of Bids:
 - 1. Add the following sections to 4.4.2:

- a. 4.4.2.1 Such modifications to or withdrawal of a bid may only be made by persons authorized to act on behalf of the Bidder. Authorized persons are those so identified in the Bidder's corporate bylaws, specifically empowered by the Bidder's charter or similar legally binding document acceptable to Owner, or by a power of attorney, signed and dated, describing the scope and limitations of the power of attorney. Make such documentation available to Owner at the time of seeking modifications or withdrawal of the Bid
- b. 4.4.2.2 Owner will consider modifications to a bid written on the sealed bid envelope by authorized persons when such modifications comply with the following: the modification is indicated by a percent or stated amount to be added to or deducted from the Bid; the amount of the Bid itself is not made known by the modification; a signature of the authorized person, along with the time and date of the modification, accompanies the modification. Completion of an unsealed bid form, awaiting final figures from the Bidder, does not require power of attorney due to the evidenced authorization of the Bidder implied by the circumstance of the completion and delivery of the Bid.

D. 4.5 - Break-Out Pricing Bid Supplement:

- 1. Add Section 4.5:
 - a. 4.5 Provide detailed cost breakdowns no later than two business days following Architect's request.
- E. 4.6 Subcontractors, Suppliers, and Manufacturers List Bid Supplement:
 - 1. Add Section 4.6:
 - a. 4.6 Provide list of major subcontractors, suppliers, and manufacturers furnishing or installing products no later than two business days following Architect's request. Include those subcontractors, suppliers, and manufacturers providing work totaling three percent or more of the Bid amount. Do not change subcontractors, suppliers, and manufacturers from those submitted without approval of Architect.

1.6 ARTICLE 5 - CONSIDERATION OF BIDS

- A. 5.2 Rejection of Bids:
 - 1. Add Section 5.2.1:
 - a. 5.2.1 Owner reserves the right to reject a bid based on Owner's and Architect's evaluation of qualification information submitted following opening of bids. Owner's evaluation of the Bidder's qualifications will include: status of licensure and record of compliance with licensing requirements, record of quality of completed work, record of Project completion and ability to complete, record of financial management including financial resources available to complete Project and record of timely payment of obligations, record of Project site management including compliance with requirements of authorities having jurisdiction, record of and number of current claims and disputes and the status of their resolution, and qualifications of the Bidder's proposed Project staff and proposed subcontractors.

1.7 ARTICLE 6 - POSTBID INFORMATION

- A. 6.1 Contractor's Qualification Statement:
 - 1. Add Section 6.1.1:
 - a. 6.1.1 Submit Contractor's Qualification Statement no later than two business days following Architect's request.
- B. 6.3 Submittals:
 - 1. Add Section 6.3.1.4:
 - a. 6.3.1.4 Submit information requested in Sections 6.3.1.1, 6.3.1.2, and 6.3.1.3 no later than two business days following Architect's request.

1.8 ARTICLE 7 - PERFORMANCE BOND AND PAYMENT BOND

- A. 7.1 Bond Requirements:
 - 1. Add Section 7.1.1.1:
 - a. 7.1.1.1 Both a Performance Bond and a Payment Bond will be required, each in an amount equal to 100 percent of the Contract Sum.
- B. 7.2 Time of Delivery and Form of Bonds:
 - 1. Delete the first sentence of Section 7.2.1 and insert the following:
 - a. The Bidder shall deliver the required bonds to Owner no later than 10 days after the date of Notice of Intent to Award and no later than the date of execution of the Contract, whichever occurs first. Owner may deem the failure of the Bidder to deliver required bonds within the period of time allowed a default.
 - 2. Delete Section 7.2.3 and insert the following:
 - a. 7.2.3 Bonds shall be executed and be in force on the date of the execution of the Contract.

1.9 ARTICLE 9 - EXECUTION OF THE CONTRACT

- A. Add Article 9:
 - 1. 9.1.1 Subsequent to the Notice of Intent to Award, and within 10 days after the prescribed Form of Agreement is presented to the Awardee for signature, the Awardee shall execute and deliver the Agreement to Owner through Architect, in such number of counterparts as Owner may require.
 - 2. 9.1.2 Owner may deem as a default the failure of the Awardee to execute the Contract and to supply the required bonds when the Agreement is presented for signature within the period of time allowed.

- 3. 9.1.3 Unless otherwise indicated in the Procurement and Contracting Documents or the executed Agreement, the date of commencement of the Work shall be the date of the executed Agreement.
- 4. 9.1.4 In the event of a default, Owner may declare the amount of the Bid security forfeited and elect to either award the Contract to the next responsible bidder or re-advertise for bids.

1.10 ARTICLE 10 – START OF WORK AND TIME OF COMPLETION

A. Add Article 10:

- 1. 10.1.1 Time is of the essence. Work of this Contract, specifically ordering of materials, shall be started within seven (7) days after receipt by the successful contractor of a Notice to Proceed from the Owner.
- 2. 10.1.2 All bidders are advised that work is required to be coordinated to allow for Owner's continued use of all facilities.
- 3. 10.1.3 All work as indicated in the Contract Documents shall be substantially complete in accordance with the Contract. At that time, and upon the work of this Contract being substantially complete, the Owner's Representative will issue a Certificate of Substantial Completion, which will establish the date of substantial completion. Within 30 days from the date of substantial completion, the Contractor shall have fully completed the work of the Contract, as specified.

1.11 ARTICLE 11 – EQUIVALENTS

A. Add Article 11:

- 1. 11.1.1 Equivalent: A product or system, proposed for inclusion in the base bid, prior to the award of contract, whose components or characteristics are identical to, or exceed, the specified criteria for that product or system. If accepted, an equivalent results in no change to the contract amount. The Architect and/or Engineer's decision is the final authority regarding whether a product is equivalent or not.
- 2. 11.1.2 Substitution: A product or system proposed for substitution, after the award of contract, whose components or characteristics differ from the specified criteria for that product or system. If accepted, a substitution may result in a change to the contract amount. Substitutions will only be accepted in the event that products or systems are discontinued.
- 3. 11.1.3 Prospective bidders are advised that whenever specific brands, manufacturers, materials, or equipment are referenced in the specifications, they are regarded as the required standard of quality and are presumed to be equal. The bidder may select one of the specified items or, if the bidder desires, he may use any type brand, manufacturer, material, or equipment other than those named in the specification that one feels is equivalent, unless otherwise stipulated in the specific section.
- 4. 11.1.4 The successful bidders shall submit within ten (10) days after opening of bids, and prior to award of contract, what kind, type, brand, manufacturer, or equipment is included in the base bid for the specified items. When requested, successful bidder shall submit information describing in specific detail wherein the equivalent bid material differs from in appearance, quality and performance required by the base specification.

- 5. 11.1.5 The risk of whether bid equivalents will be accepted is borne by the Bidder.
- 6. 11.1.6 No substitutions will be considered after the Contract award unless specifically provided in the Contract Documents. Refer to Section 012500 "Substitution Procedures" for additional information.

1.12 ARTICLE 12 – PERMITS, TAXES, AND ASSESSMENTS

A. Add Article 12:

- 12.1.1 The Contractor, in submitting a bid for this Contract, shall include in his Base Bid all costs and liabilities for permits. The General Construction Contractor shall apply to the County for a building permit at each site of which there shall be no charge. The General Construction Contractor shall submit the required written request, including application, drawings, etc., to the Owner for the building permit and the Owner shall provide at no cost. Written request shall include a letter with the address and description of the project to the County Code Officer along with two (2) sets of 24 x 36 drawings, one (1) set of 11 x 17 drawings and a USB drive with a PDF of all drawings. The Contractor shall also include within his Base Bid taxes and assessments upon the wages and salaries paid to employees of the Contractor and his subcontractors under the Contract, or any other taxes, which may be assessed by the Federal, State, or Local governments except as noted herein.
 - a. 12.1.1.1 The General Construction Contractor shall obtain the building permit and the NYSDOT work permit. The Owner shall provide permits from DEC, ACOE, and Town (if applicable).
- 2. 12.1.2 The Owner is exempt from payment of sales and compensating use taxes of the State of New York and of all cities and counties, and the Contractor shall notify all Subcontractors and material suppliers to this effect so the bid, the Contract Sum, and subsequent requisitions for payment will not include any amount for sales or use taxes.
- 3. 12.1.3 In all operations connected with the work herein specified, all city and town ordinances and laws controlling or limiting in any way the action of those engaged in the work must be respected and strictly complied with.

1.13 ARTICLE 13 – LAWS AND REGULATIONS

A. Add Article 13:

- 1. 13.1.1 The Bidder's attention is directed to the fact that all applicable Federal, State, or other Laws, orders, Rules and Regulations of all Authorities having jurisdiction over construction work in the locality of the project shall apply to the Contract throughout, and they will be deemed to be included in the Contract the same as though herein written out in full.
- 2. 13.1.2 These Construction Documents, and the joint and several phases of construction hereby contemplated are to be governed, at all times, by applicable provisions of the Federal law(s), including but not limited to the latest amendments of the following:
 - a. Williams Steiger Occupational Safety & Health Act of 1970, Public Law 910596;
 - b. Part 1910 Occupational Safety and Health Standards, Chapter XVII of Title 29, Code of Federal Regulations;
 - c. Page 1518 Safety and Health Regulations for Construction Chapter XIII of Title 29, Code of Federal Regulations.

1.14 ARTICLE 14 – NON-COLLUSIVE BIDDING CERTIFICATION AND CORPORATE

A. Add Article 14:

1. 14.1.1 – Pursuant to the requirements of Section 103 d of the General Municipal Law, each proposal submitted shall be accompanied by a fully executed Non-Collusive Bidding Certification, a copy of which is attached to the bid form.

1.15 ARTICLE 15 – NON-SEGREGATED FACILITIES CERTIFICATION

A. Add Article 15:

1. 15.1.1 – Notice of Requirement for Certification of Non-Segregated Facilities Bidders are cautioned as follows: By signing this bid, the Bidder will be deemed to have agreed to the provisions of the "Certification of Non-Segregated Facilities". The Certification provides that the Bidders does not maintain or provide for his employees' facilities, which are segregated on a basis of race, creed, color, or national origin, whether such facilities are segregated by directive or on a de facto basis. The Certification also provides that he will not maintain such segregated facilities. Failure of a Bidder to agree to the Certification of Non-Segregated Facilities will render his bid nonresponsive to the terms of solicitation involving awards of contracts exceeding \$10,000.00, which are not exempt from the provisions of the Equal Opportunity Clause.

1.16 ARTICLE 16 – ASSIGNMENT OF CONTRACT

A. Add Article 16:

1. 16.1.1 – The successful Bidder is prohibited from assigning, transferring, conveying, subletting, or otherwise disposing of the same, or his right, title, or interest therein, or of his power to execute such contract to any person or corporation without the previous consent in writing of the Owner. If such assignment, transfer conveyance, subletting, or otherwise, is made without the required consent of the Owner, the Contract herein shall be revoked, and annulled in accordance with Section 109 of the General Municipal Law, which is incorporated herein.

1.17 ARTICLE 17 – GENERAL COVERAGE CLAUSE

A. Add Article 17:

1. 17.1.1 – Each and every provision of law and clause required by law to be inserted in this contract shall be deemed to have been inserted herein, and if through mistake or otherwise, such provision is not inserted, then upon the application of either party, this Contract shall be physically amended forthwith to make such insertion.

1.18 ARTICLE 18 – NON-WAIVER

A. Add Article 18:

18.1.1 – No waiver of any breach of any condition in this agreement shall be binding unless the same shall be in writing and signed by the party waiving the said breach. No such waiver shall in any way affect any other term or condition of this agreement of

constitute a cause or excuse for the repetition of such or any other breach unless the waiver shall include the same.

END OF DOCUMENT 002213

DOCUMENT 002513

PREBID MEETINGS

1.1 PREBID MEETING

- A. Architect will conduct a Prebid meeting as indicated below:
 - 1. Meeting Date: June 8, 2023
 - 2. Meeting Time: 1:00 p.m., local time.
 - 3. Location: Via Zoom at the following link
 - a. https://us02web.zoom.us/j/87110767969
- B. Attendance:
 - 1. Prime Bidders: Attendance at Prebid meeting is recommended.
 - 2. Subcontractors: Attendance at Prebid meeting is recommended.
- C. Bidder Questions: Submit written questions to be addressed at Prebid meeting minimum of two business days prior to meeting.
- D. Agenda: Prebid meeting agenda will include review of topics that may affect proper preparation and submittal of bids, including the following:
 - 1. Procurement and Contracting Requirements:
 - a. Advertisement for Bids.
 - b. Instructions to Bidders.
 - c. Bidder Qualifications.
 - d. Bonding.
 - e. Insurance.
 - f. Bid Security.
 - g. Bid Form and Attachments.
 - h. Bid Submittal Requirements.
 - i. Bid Submittal Checklist.
 - j. Notice of Award.
 - 2. Communication during Bidding Period:
 - a. Obtaining documents.
 - b. Access to Project Web site.
 - c. Bidder's Requests for Information.
 - d. Bidder's Substitution Request/Prior Approval Request.
 - e. Addenda.
 - 3. Contracting Requirements:
 - a. Agreement.
 - b. The General Conditions.

- c. The Supplementary Conditions.
- d. Other Owner requirements.
- 4. Construction Documents:
 - a. Scopes of Work.
 - b. Temporary Facilities.
 - c. Use of Site.
 - d. Work Restrictions.
 - e. Alternates, Allowances, and Unit Prices.
 - f. Substitutions following award.
- 5. Separate Contracts:
 - a. Work by Owner.
 - b. Work of Other Contracts.
- 6. Schedule:
 - a. Project Schedule.
 - b. Contract Time.
 - c. Liquidated Damages.
 - d. Other Bidder Questions.
- 7. Site/facility visit or walkthrough.
- 8. Post-Meeting Addendum.
- E. Minutes: Entity responsible for conducting meeting will record and distribute meeting minutes to attendees. Minutes of meeting are issued as Available Information and do not constitute a modification to the Procurement and Contracting Documents. Modifications to the Procurement and Contracting Documents are issued by written Addendum only.
 - 1. Sign-in Sheet: Minutes will include list of meeting attendees.
 - 2. List of Planholders: Minutes will include list of planholders.

END OF DOCUMENT 002513

Request for Information ("RFI") TO: FROM: Delaware Engineering, DPC 28 Madison Ave Ext., Albany, NY 12203 PROJECT: **ISSUE DATE:** RFI No. 001 Town of Milton Rowland Street Highway Facility - Cold Storage **PEMB** REQUESTED REPLY DATE: PROJECT NUMBERS: 23-2654 / **COPIES TO: RFI DESCRIPTION:** (Fully describe the question or type of information requested.) REFERENCES/ATTACHMENTS: (List specific documents researched when seeking the information requested.) SPECIFICATIONS: **DRAWINGS:** OTHER: **SENDER'S RECOMMENDATION:** (If RFI concerns a site or construction condition, the sender may provide a recommended solution, including cost and/or schedule considerations.) **RECEIVER'S REPLY:** (Provide answer to RFI, including cost and/or schedule considerations.) BY DATE **COPIES TO**

Note: This reply is not an authorization to proceed with work involving additional cost, time or both. If any reply requires a change to the Contract Documents, a Change Order, Construction Change Directive or a Minor Change in the work must be executed in accordance with the Contract Documents.

DOCUMENT 002600

PROCUREMENT SUBSTITUTION PROCEDURES

1.1 DEFINITIONS

- A. Procurement Substitution Requests: Requests for changes in products, materials, equipment, and methods of construction from those indicated in the Procurement and Contracting Documents, submitted prior to receipt of bids.
- B. Substitution Requests: Requests for changes in products, materials, equipment, and methods of construction from those indicated in the Contract Documents, submitted following Contract award. See Section 012500 "Substitution Procedures" for conditions under which Substitution requests will be considered following Contract award.

1.2 QUALITY ASSURANCE

A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

1.3 PROCUREMENT SUBSTITUTIONS

- A. Procurement Substitutions, General: By submitting a bid, the Bidder represents that its bid is based on materials and equipment described in the Procurement and Contracting Documents, including Addenda. Bidders are encouraged to request approval of qualifying substitute materials and equipment when the Specifications Sections list materials and equipment by product or manufacturer name.
- B. Procurement Substitution Requests will be received and considered by Owner when the following conditions are satisfied, as determined by Architect; otherwise requests will be returned without action:
 - 1. Extensive revisions to the Contract Documents are not required.
 - 2. Proposed changes are in keeping with the general intent of the Contract Documents, including the level of quality of the Work represented by the requirements therein.
 - 3. The request is fully documented and properly submitted.

1.4 SUBMITTALS

- A. Procurement Substitution Request: Submit to **Architect**. Procurement Substitution Request must be made in writing in compliance with the following requirements:
 - 1. Requests for substitution of materials and equipment will be considered if received no later than 10 days prior to date of bid opening.

- 2. Submittal Format: Submit electronic copies of each written Procurement Substitution Request, using CSI Substitution Request Form 1.5C.
 - a. Identify the product or the fabrication or installation method to be replaced in each request. Include related Specifications Sections and drawing numbers.
 - b. Provide complete documentation on both the product specified and the proposed substitute, including the following information as appropriate:
 - 1) Point-by-point comparison of specified and proposed substitute product data, fabrication drawings, and installation procedures.
 - 2) Copies of current, independent third-party test data of salient product or system characteristics.
 - 3) Samples where applicable or when requested by Architect.
 - 4) Detailed comparison of significant qualities of the proposed substitute with those of the Work specified. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
 - 5) Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
 - 6) Research reports, where applicable, evidencing compliance with building code in effect for Project, from ICC-ES.
 - 7) Coordination information, including a list of changes or modifications needed to other parts of the Work and to construction performed by Owner and separate contractors, which will become necessary to accommodate the proposed substitute.
 - c. Provide certification by manufacturer that the substitute proposed is equal to or superior to that required by the Procurement and Contracting Documents, and that its in-place performance will be equal to or superior to the product or equipment specified in the application indicated.
 - d. Bidder, in submitting the Procurement Substitution Request, waives the right to additional payment or an extension of Contract Time because of the failure of the substitute to perform as represented in the Procurement Substitution Request.

B. Architect's Action:

- 1. Architect may request additional information or documentation necessary for evaluation of the Procurement Substitution Request. Architect will notify all bidders of acceptance of the proposed substitute by means of an Addendum to the Procurement and Contracting Documents.
- C. Architect's approval of a substitute during bidding does not relieve Contractor of the responsibility to submit required shop drawings and to comply with all other requirements of the Contract Documents.

END OF DOCUMENT 002600

DOCUMENT 003113

PRELIMINARY SCHEDULES

1.1 PROJECT SCHEDULE

- A. This Document with its referenced attachments is part of the Procurement and Contracting Requirements for Project. They provide Owner's information for Bidders' convenience and are intended to supplement rather than serve in lieu of Bidders' own investigations. They are made available for Bidders' convenience and information, but do not affect Contract Time requirements. This Document and its attachments are not part of the Contract Documents.
- B. Available Project information includes the following:
 - 1. Project Schedule.
 - a. Pre-Engineered Metal Building Bids Due: 06/23/2023
 - b. Town Board Action on Pre-Engineered Metal Building: 06/28/2023
 - c. Multiple Prime Construction (by others) Bids Due: 09/08/2023
 - d. Town Board Action on Multiple Prime Construction (by others): 09/27/2023
 - e. Pre-engineered Metal Building Delivery (by others) to Site: 12/26/2023
 - f. Construction Completion: 01/26/2024

C. Related Requirements:

- 1. Document 004113 "Bid Form Stipulated Sum (Single-Prime Contract)" for Contract Time.
- 2. Section 011000 "Summary" for phased construction requirements.
- 3. Section 013200 "Construction Progress Documentation" for Contractor's construction schedule requirements.

END OF DOCUMENT 003113



DOCUMENT 004113

BID FORM - STIPULATED SUM (SINGLE-PRIME CONTRACT)

| 1.1 | BID INFORMATION |
|-----|--|
| A. | Bidder: |
| B. | Project Name: Rowland Street Highway Facility - Cold Storage PEMB |
| C. | Project Location: Milton, NY. Latitude: 43.056274; Longitude: -73.850838 |
| D. | Owner: Town of Milton |
| E. | Owner Project Number: None. |
| F. | Architect: Delaware Engineering, DPC |
| G. | Architect Project Number: 23-2654. |
| 1.2 | CERTIFICATIONS AND BASE BID |
| A. | Base Bid, Single-Prime (All Trades) Contract: The undersigned Bidder, having carefully examined the Procurement and Contracting Requirements, Conditions of the Contract, Drawings, Specifications, and all subsequent Addenda, as prepared by Delaware Engineering, DPC, and Architect's consultants, having visited the site, and being familiar with all conditions and requirements of the Work, hereby agrees to furnish all material, labor, equipment and services, including all scheduled allowances, necessary to complete the construction of the above-named project, according to the requirements of the Procurement and Contracting Documents, for the stipulated sum of: |
| | 1 |
| 1.3 | BID GUARANTEE |
| A. | The undersigned Bidder agrees to execute a contract for this Work in the above amount and to furnish surety as specified within 10 days after a written Notice of Award, if offered within 45 days after receipt of bids, and on failure to do so agrees to forfeit to Owner the attached cash, cashier's check, certified check, U.S. money order, or bid bond, as liquidated damages for such failure, in the following amount constituting five percent (5%) of the Base Bid amount above: |
| | 1 Dollars (\$). |
| В. | In the event Owner does not offer Notice of Award within the time limits stated above, Owner will return to the undersigned the cash, cashier's check, certified check, U.S. money order, or bid bond. |

1.4 ACCEPTANCE

- A. This offer shall be open to acceptance and is irrevocable for forty-five (45) calendar days from the Bid closing date. Contract Award shall be determined by the Lowest Responsible Base Bid plus any combination of Alternates, and consideration of any Unit Prices, at the discretion of the Owner.
- B. If this Bid is accepted by the Owner within the time period stated above, we will:
 - 1. Execute the Agreement within seven days of receipt of Notice of Award.
 - 2. Furnish the required bonds within seven (7) days of receipt of Notice of Award in the form described in Contract Documents. Commence Work within fifteen (15) days after written Notice to Proceed
- C. If this Bid is accepted within the time stated, and we fail to commence the Work or we fail to provide the required bonds, the Bid security shall be forfeited as damages to the Owner by reason of our failure, limited in amount to the lesser of the face value of the Bid security or the difference between this Bid and the Bid upon which a Contract is signed. In the event our Bid is not accepted within the time stated above, the required Bid security will be returned to the undersigned, according to the provisions of the Instructions to Bidders, unless a mutually satisfactory arrangement is made for its retention and validity for an extended period of time.
- D. The sum given in the Base Bid represents the entire cost of the Project. The sum given shall include any and all cost for insurance, including all insurance required by the Agreement, any and all fees for licenses and permits. The Undersigned agrees that no claim will be made for any additional costs regardless of any increases in costs such as higher wage scales or material prices. No amount is included in the Base Bid for sales or use taxes on materials and supplies to be incorporated in the work, except as specified.
- E. The Undersigned has carefully checked all the figures used in compiling the sum given in the Base Bid and understands that the Owner will not be responsible for any errors or omissions incurred by the Undersigned in making up of this Bid. The Undersigned further understands that no modification or withdrawal of this proposal will be permitted after the time specified for the receipt of Bids.
- F. The Undersigned has examined the location of the proposed Work, Drawings, Specifications and other Contract Documents and is familiar with local conditions at the place where Work is to be performed.
- G. The Undersigned agrees to provide to the Owner with a detailed cost (material and labor) breakdown of each item per site, prior to award of Contract.

1.5 TIME OF COMPLETION

A. The undersigned Bidder proposes and agrees hereby to commence the Work of the Contract Documents on a date specified in a written Notice to Proceed to be issued by Architect, and shall fully complete the Work within 180 calendar days.

| 1.6 | ACKNOWLEDGEMENT OF ADDENDA | | |
|-----|---|--|--|
| A. | The undersigned Bidder acknowledges receipt of and use of the following Addenda in the preparation of this Bid: | | |
| | 1. Addendum No. 1, dated 2. Addendum No. 2, dated 3. Addendum No. 3, dated 4. Addendum No. 4, dated | | |
| 1.7 | BID SUPPLEMENTS | | |
| A. | The following supplements are a part of this Bid Form and are attached hereto. | | |
| | Bid Form Supplement – Bid Security Form AIA A310. Bid Form Supplement – Non-Collusion Affidavit Bid Form Supplement – Certification of Non-segregated Facilities Bid Form Supplement – Certification of Prime Contractor Equal Employment Opportunity Bid Form Supplement – Iranian Energy Sector Divestment Certification. | | |
| 1.8 | CONTRACTOR'S LICENSE | | |
| A. | The undersigned further states that it is a duly licensed contractor, for the type of work proposed, in The State of New York, and that all fees, permits, etc., pursuant to submitting this proposal have been paid in full. | | |
| 1.9 | SUBMISSION OF BID | | |
| A. | Respectfully submitted this day of, 20 | | |
| B. | Submitted By:(Name of bidding firm or corporation). | | |
| C. | Authorized Signature:(Handwritten signature). | | |
| D. | Signed By:(Type or print name). | | |
| E. | Title:(Owner/Partner/President/Vice President). | | |
| F. | Witnessed By:(Handwritten signature). | | |
| G. | Attest:(Handwritten signature). | | |
| Н. | By:(Type or print name). | | |
| I. | Title:(Corporate Secretary or Assistant Secretary). | | |
| J. | Street Address: . | | |

| R | owland S | treet Highway | Facility_ | Cold Storage | PFMR |
|---|-----------|---------------|-----------|--------------|---------|
| 1 | owiana si | ireei miynwav | raciliv - | Coia Siorage | I INVID |

Town of Milton

| K. | City, State, Zip: | |
|----|-------------------|------------------------------|
| L. | Phone: | |
| M. | License No.: | |
| N. | Federal ID No.: | (Affix Corporate Seal Here). |

END OF DOCUMENT 004113

DOCUMENT 004313

BID SECURITY FORMS

1.1 BID FORM SUPPLEMENT

A. A completed bid bond form is required to be attached to the Bid Form.

1.2 BID BOND FORM

- A. AIA Document A310-2010 "Bid Bond" is the recommended form for a bid bond. A bid bond acceptable to Owner, or other bid security as described in the Instructions to Bidders, is required to be attached to the Bid Form as a supplement.
- B. Copies of AIA standard forms may be obtained from The American Institute of Architects; https://www.aiacontracts.org/; email: docspurchases@aia.org; (800) 942-7732.

END OF DOCUMENT 004313

Bid Bond

CONTRACTOR:

(Name, legal status and address)

SURETY:

(Name, legal status and principal place of business)

OWNER:

(Name, legal status and address)
Town of Milton
503 Geyser Road, Ballston Spa, NY 12020

BOND AMOUNT: \$

PROJECT:

(Name, location or address, and Project number, if any) Town of Milton Rowland Street Highway Facility - Cold Storage PEMB

The Contractor and Surety are bound to the Owner in the amount set forth above, for the payment of which the Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, as provided herein. The conditions of this Bond are such that if the Owner accepts the bid of the Contractor within the time specified in the bid documents, or within such time period as may be agreed to by the Owner and Contractor, and the Contractor either (1) enters into a contract with the Owner in accordance with the terms of such bid, and gives such bond or bonds as may be specified in the bidding or Contract Documents, with a surety admitted in the jurisdiction of the Project and otherwise acceptable to the Owner, for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof; or (2) pays to the Owner the difference, not to exceed the amount of this Bond, between the amount specified in said bid and such larger amount for which the Owner may in good faith contract with another party to perform the work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect. The Surety hereby waives any notice of an agreement between the Owner and Contractor to extend the time in which the Owner may accept the bid. Waiver of notice by the Surety shall not apply to any extension exceeding sixty (60) days in the aggregate beyond the time for acceptance of bids specified in the bid documents, and the Owner and Contractor shall obtain the Surety's consent for an extension beyond sixty (60) days.

If this Bond is issued in connection with a subcontractor's bid to a Contractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

When this Bond has been furnished to comply with a statutory or other legal requirement in the location of the Project, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An Additions and Deletions Report that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

| | (Contractor as Principal) | (Sea |
|-----------|---------------------------|-------|
| (Witness) | (Title) | |
| | (Surety) | (Seal |
| (Witness) | (Title) | |
| | | |
| | | |

2

NON-COLLUSION AFFIDAVIT OF BIDDER

| State of | of | _) | |
|----------|--|--|--|
| Count | y of |)ss. _) | |
| | | | , being first duly sworn, deposes and says |
| that: | | | |
| (1) | ` - | r, officer, representative ubmitted the attached | - |
| (2) | He is fully informed respecting the preparation and contents of the attached Bid and of a pertinent circumstances respecting such Bid; | | |
| (3) | Such Bid is genuine | and is not a collusive of | or sham Bid; |

- (4) a. By submission of this Bid, each Bidder and each person signing on behalf of any Bidder certifies, and in the case of a joint Bid each party thereto certifies as to its own organization, under penalty of perjury, that to the best of his knowledge and belief;
 - 1. The prices in this Bid, have been arrived at independently without collusion, consultation, communication, or agreement, for the purpose of restricting competition, as to any matter relating to such prices with any other bidder or with any competitor;
 - 2. Unless otherwise required by law, the prices which have been quoted in this bid have not been knowingly disclosed by the Bidder and will not knowingly be disclosed by the Bidder prior to opening, directly or indirectly, to any other bidder or to any competitor; and
 - 3. No attempt has been made or will be made by the Bidder to induce any other person, partnership or corporation to submit or not to submit a Bid for the purpose of restricting competition.
 - b. A Bid shall not be considered for award nor shall any award be made where clauses (4)a, 1, 2 and 3 above have not been complied with; provided however, that if in any case the Bidder cannot make the foregoing certification, the Bidder shall so state and shall furnish with the Bid a signed statement which sets forth in detail the reasons therefore. Where (4) a, 1, 2 and 3 above have not been complied with, the Bid shall not be considered for award nor shall any award be made unless the head of the purchasing unit of the state, public department or

(5)

agency to which the Bid is made, or his designee, determines that such disclosure was not made for the purpose of restricting competition.

The fact that a Bidder (i) has published price lists, rates, or tariffs covering items being procured, (ii) has informed prospective customers of proposed or pending publication of new or revised price lists for such items, or (iii) has sold the same items to other customers at the same prices being bid, does not constitute, without more, a disclosure within the meaning of clause (4) a, 2.

Any Bid hereafter made to the Municipality or any public department, agency or official thereof by a corporate Bidder for work or services performed or to be performed or goods sold or to be sold, where competitive bidding is required by statute, rule or regulation, and where such Bid contains the certification referred to in subparagraph (4) a, of this section, shall be deemed to have been authorized by the Board of Directors of the Bidder and such authorization shall be deemed to include the signing and submission of the Bid and the inclusion therein of the certificate as to non-collusion as the act and deed of the corporation.

The price or prices quoted in the attached Bid are fair and proper and are not tainted by

| · · · · · · · · · · · · · · · · · · · | nce or unlawful agreement on the part of the Bidder or wners, employees, or parties in interest, including this |
|--|--|
| _ | Signed: |
| _ | Title: |
| Subscribed and sworn to before me this | day of, 20 |
| Notary Public | |
| My Commission expires | _ |

CERTIFICATION OF NONSEGREGATED FACILITIES

This Bidder certifies that he does not maintain or provide for his employees any segregated facilities at any of his establishments, and that he does not permit his employees to perform their services at any location, under his control, where segregated facilities are maintained. The Bidder certifies further that he will not maintain or provide for his employees any segregated facilities at any of his establishments, and that he will not permit his employees to perform their services at any location under his control where segregated facilities are maintained. The Bidder agrees that a breach of his certification will be a violation of the Equal Opportunity clause in any Contract resulting from acceptance of this Bid. As used in this certification, the term "segregated facilities": means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, time clock, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive or are, in fact, segregated on the basis of race, color, religion, or national origin, because of habit, local custom or otherwise. The Bidder agrees that (except where he had obtained identical certification from proposed Subcontractors for specific time periods) he will obtain identical certifications from proposed Subcontractors prior to the award of Subcontracts exceeding \$10,000 which are not exempt from the provisions of the Equal Opportunity clause, and that he will retain such certifications in his files.

| Note: The penalt | ty for making false statements in offers is prescribed in 18 U | J.S.C. Paragraph 1001 |
|-------------------|--|-----------------------|
| Date: | | |
| Ву: | Title: | _ |
| Official Address: | | |
| | | |
| | | |
| - | | |

CERTIFICATION OF PRIME CONTRACTOR REGARDING EQUAL EMPLOYMENT OPPORTUNITY


| NAME OF BIDDER PROJECT NUMBER |
|--|
| INSTRUCTIONS This certification is required pursuant to Executive Order 11246, Part II, Section 203 (b), (30 F.R. 1231925). Each prospective contractor shall state in his bid proposal whether he has participated in any previous contract or subcontract subject to the Equal Opportunity Clause; and, if so, whether he has filed a compliance reports due under applicable filing requirements. |
| SUBCONTRACTOR'S CERTIFICATION |
| CONTRACTOR'S NAME: |
| ADDRESS: |
| Subcontractor has participated in a previous contract or subcontract subject to the Equal Opportunity Clause. |
| YES NO |
| 2. Compliance reports were required to be filed in connection with such contract or subcontract. |
| YES NO |
| IF YES, state what reports were filed and with what agency. |
| 3. Subcontractor has filed all compliance reports due under applicable instructions, including SF-100. |
| YES NO |
| 4. If answer to item 3 is "NO", please explain in detail on reverse side of this certification. |
| CERTIFICATION - THE INFORMATION ABOVE IS TRUE AND COMPLETE TO THE BEST OF M KNOWLEDGE AND BELIEF. A WILLFULLY FALSE STATEMENT IS PUNISHABLE BY LAW (U.S. CODE, TITLE 18, SECTION 1001.) |
| NAME AND TITLE OF SIGNER (PLEASE TYPE) |
| (SIGNATURE) (DATE) |

IRANIAN ENERGY SECTOR DIVESTMENT CERTIFICATION

- 1. Contractor/proposer hereby represents that said contractor/proposer is in compliance with New York State General Municipal Law Section 103-g entitled "Iranian Energy Sector Divestment", in that said contractor/proposer has not:
 - a) Provided goods or services of \$20 million or more in the energy sector of Iran including but not limited to the provision of oil or liquefied natural gas tankers or products used to construct or maintain pipelines used to transport oil or liquefied natural gas for the energy sector of Iran; or
 - b) Acted as a financial institution and extended \$20 million or more in credit to another person for forty-five (45) days or more, if that person's intent was to use the credit to provide goods or services in the energy sector in Iran.
- 2. Any contractor/proposer who has undertaken any of the above and is identified on a list created pursuant to Section 165-a (3) (b) of the New York State Finance Law as a person engaging in investment activities in Iran, shall not be deemed a responsible bidder pursuant to Section 103 of the New York State General Municipal Law.
- 3. Except as otherwise specifically provided herein, every contractor/ proposer submitting a bid/proposal in response to this request for bids/request for proposals must certify and affirm the following under penalties of perjury:
 - a) "By submission of this bid, each bidder and each person signing on behalf of any bidder certifies and in the case of a joint bid, each party thereto certifies as to its own organization, under penalty of perjury, that to the best of its knowledge and belief, that each bidder is not on the list created pursuant to NYS Finance Law Section 165-a (3) (b)."
 - The Village will accept this statement electronically in accordance with the provisions of Section 103 of the General Municipal Law.
- 4. Except as otherwise specifically provided herein, any bid/proposal that is submitted without having complied with subdivision (a) above, shall not be, considered for award. In any case where the bidder/proposer cannot make the certification as set forth in subdivision (a) above, the bidder/proposer shall so state and shall furnish with the bid a signed statement setting forth in detail the reasons therefore. The Village reserves its rights, in accordance with General Municipal Law Section 103-g to award the bid/proposal to any bidder/proposer who cannot make the certification, on a case-by-case basis under the following circumstances:

- a) The investment activities in Iran were made before April 12, 20 I 2, the investment activities in Iran have not been expanded or renewed after April 12, 2012 and the bidder/proposer has adopted, publicized and is implementing a formal plan to cease the investment activities in Iran and to refrain from engaging in any new investments in Iran; or
- b) The Village has made a determination that the goods or services are necessary for the Village to perform its functions and that, absent such an exemption, the Village would be unable to obtain the goods or services for which the bid/proposal is offered. Such determination shall be made by the Village in writing and shall be a public document.

| | Signature | Title | |
|---------|---|-----------------------|--|
| | Company Name | Date | |
| | · |) | |
| SS: Cou | unty of |) | |
| and app | On thisday of eared to me known and known to me to b ng instrument and acknowledged that he e | e the person describe | |



SECTION 006000

PROJECT FORMS

1.1 FORM OF AGREEMENT AND GENERAL CONDITIONS

- A. The following form of Owner/Contractor Agreement and form of the General Conditions shall be used for Project:
 - 1. AIA Document A151-2019 "Standard Form of Agreement between Owner and Vendor for Furniture, Furnishings, and Equipment (FF&E)."
 - a. The General Conditions for Project are AIA Document A201-2017 "General Conditions of the Contract for Construction."
 - 2. The Supplementary Conditions for Project are incorporated into a modified copy of the General Conditions included in the Project Manual.
 - 3. Owner's document(s) bound following this Document.

1.2 ADMINISTRATIVE FORMS

- A. Administrative Forms: Additional administrative forms are specified in Division 01 General Requirements.
- B. Copies of AIA standard forms may be obtained from the American Institute of Architects; www.aiacontractdocsaiacontracts.org; (800) 942-7732.

C. Preconstruction Forms:

- 1. Form of Performance Bond and Labor and Material Bond: AIA Document A312-2010 "Performance Bond and Payment Bond."
- 2. Form of Certificate of Insurance: AIA Document G715-2017 "Supplemental Attachment for ACORD Certificate of Insurance 25."

D. Information and Modification Forms:

- 1. Form for Requests for Information (RFIs): AIA Document G716-2004 "Request for Information (RFI)."
- 2. Form of Request for Proposal: AIA Document G709-2018 "Proposal Request."
- 3. Change Order Form: AIA Document G701-2017 "Change Order."
- 4. Form of Architect's Memorandum for Minor Changes in the Work: AIA Document G710-2017 "Architect's Supplemental Instructions."
- 5. Form of Change Directive: AIA Document G714-2017 "Construction Change Directive."

E. Payment Forms:

- 1. Schedule of Values Form: AIA Document G703-1992 "Continuation Sheet."
- 2. Payment Application: AIA Document G702-1992/703-1992 "Application and Certificate for Payment and Continuation Sheet."

- 3. Form of Contractor's Affidavit: AIA Document G706-1994 "Contractor's Affidavit of Payment of Debts and Claims."
- 4. Form of Affidavit of Release of Liens: AIA Document G706A-1994 "Contractor's Affidavit of Payment of Release of Liens."
- 5. Form of Consent of Surety: AIA Document G707-1994 "Consent of Surety to Final Payment."

END OF SECTION 006000

Standard Form of Agreement between Owner and Vendor for Furniture, Furnishings, and Equipment (FF&E)

AGREEMENT made as of the day of in the year (In words, indicate day, month, and year.)

BETWEEN the Owner:

(Name, legal status, address, and other information)

Town of Milton 503 Geyser Road, Ballston Spa, NY 12020

and the Vendor:

(Name, legal status, address, and other information)

for the following Project: (Name, location, and detailed description)

Town of Milton Rowland Street Highway Facility - Cold Storage PEMB

The Architect:

(Name, legal status, address, and other information)

Delaware Engineering, DPC 28 Madison Ave Ext., Albany, NY 12203

The Owner and Vendor agree as follows.

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An Additions and Deletions Report that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

TABLE OF ARTICLES

- 1 GENERAL PROVISIONS
- 2 CONTRACT SUM AND PAYMENTS
- 3 TIME
- 4 OWNER
- 5 VENDOR
- 6 TITLE AND RISK OF LOSS
- 7 DELIVERY AND INSTALLATION
- 8 ACCEPTANCE
- 9 WARRANTIES
- 10 ARCHITECT
- 11 RELATED ACTIVITIES OF OWNER OR OF SEPARATE VENDORS
- 12 PROTECTION OF PERSONS AND PROPERTY
- 13 INSURANCE
- 14 CLAIMS AND DISPUTES
- 15 ENUMERATION OF CONTRACT DOCUMENTS

ARTICLE 1 GENERAL PROVISIONS

§ 1.1 Governing Law, including the Uniform Commercial Code

This Agreement is for the sale of goods, specifically furniture, furnishings, and equipment (FF&E), and shall be governed by the law of the place where the Project is located, excluding that jurisdiction's choice of law rule and including the jurisdiction's Uniform Commercial Code (UCC) as adopted. If this Agreement conflicts with terms provided by the UCC, the Agreement shall prevail. If the parties have selected arbitration as the method of binding dispute resolution, the Federal Arbitration Act shall govern Section 14.7.

§ 1.2 The Contract Documents

The Contract Documents are enumerated in Article 15 and consist of this Agreement (including, if applicable, Supplementary and other Conditions of the Contract), Drawings, Specifications, Addenda issued prior to the execution of this Agreement, other documents listed in this Agreement, and Modifications issued after execution of this Agreement. The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Vendor. The Contract Documents are complementary, and what is required by one shall be as binding as if required by all. Performance by the Vendor shall be required to the extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the indicated results.

§ 1.3 The Contract

The Contract Documents form the Contract for the Work. The Contract represents the entire and integrated agreement between the parties hereto and supersedes all prior proposals, offers, terms and conditions, negotiations, representations, or agreements, either written or oral. The Contract may be amended or modified only by a Modification. The Contract Documents shall not be construed to create a contractual relationship of any kind between any persons or entities other than the Owner and the Vendor. The primary purpose of the Contract is the sale of goods, and any services provided are incidental to such primary purpose.

§ 1.4 Modifications

A Modification is a written amendment to the Contract for changes in the Work signed by both parties or a written order for a minor change in the Work signed by the Architect. A minor change in the Work is a change that is consistent with the intent of the Contract Documents and does not involve an adjustment in the Contract Sum or an extension of the Contract Time.

§ 1.5 The Work

The Work means the Vendor's performance, including the sale of FF&E and any incidental fabrication, shipping, warehousing, delivery, installation, and other items or services required by the Contract Documents and provided, or to be provided, by the Vendor. The Work includes all labor, materials, temporary protection, storage, and equipment necessary to fulfill the Vendor's obligations, except as specifically indicated in the Contract Documents to be the responsibility of others. The Work may constitute the whole or a part of the Project.

§ 1.6 Instruments of Service

Instruments of Service are representations, in any medium of expression now known or later developed, of the tangible and intangible creative work performed by the Architect and the Architect's consultants under their respective professional services agreements. Instruments of Service may include, without limitation, studies, surveys, models, sketches, drawings, specifications, and other similar materials.

§ 1.7 Ownership and Use of Drawings, Specifications, and Other Instruments of Service

§ 1.7.1 The Architect and the Architect's consultants shall be deemed the authors and owners of their respective Instruments of Service, including the Drawings and Specifications, and will retain all common law, statutory, and other reserved rights in their Instruments of Service, including copyrights. The Vendor, sub-vendors, and suppliers shall not own or claim a copyright in the Instruments of Service. Submittal or distribution to meet official regulatory requirements or for other purposes in connection with the Project is not to be construed as publication in derogation of the Architect's or Architect's consultants' reserved rights.

§ 1.7.2 The Vendor, sub-vendors, and suppliers are authorized to use and reproduce the Instruments of Service provided to them, subject to the protocols established pursuant to Sections 1.8 and 1.9, solely and exclusively for execution of the Work. All copies made under this authorization shall bear the copyright notice, if any, shown on the Instruments of Service. The Vendor, sub-vendors, and suppliers may not use the Instruments of Service on other projects, or in connection with additions to this Project outside the scope of the Work without the specific written consent of the Owner, Architect, and the Architect's consultants.

§ 1.8 Digital Data Use and Transmission

The parties shall agree upon protocols governing the transmission and use of Instruments of Service or any other information or documentation in digital form. The parties will use AIA Document E203TM–2013, Building Information Modeling and Digital Data Exhibit, to establish the protocols for the development, use, transmission, and exchange of digital data.

§ 1.9 Building Information Models Use and Reliance

Any use of, or reliance on, all or a portion of a building information model without agreement to protocols governing the use of, and reliance on, the information contained in the model and without having those protocols set forth in AIA Document E203TM—2013, Building Information Modeling and Digital Data Exhibit, and the requisite AIA Document G202TM—2013, Project Building Information Modeling Protocol Form, shall be at the using or relying party's sole risk and without liability to the other party and its vendors or consultants, the authors of, or contributors to, the building information model, and each of their agents and employees.

§ 1.10 Severability

The invalidity of any provision of the Contract Documents shall not invalidate the Contract or its remaining provisions. If it is determined that any provision of the Contract Documents violates any law, or is otherwise invalid or unenforceable, then that provision shall be revised to the extent necessary to make that provision legal and enforceable. In such case the Contract Documents shall be construed, to the fullest extent permitted by law, to give effect to the parties' intentions and purposes in executing the Contract.

§ 1.11 Notice

§ 1.11.1 Except as otherwise provided in Section 1.11.2, where the Contract Documents require one party to notify or give notice to the other party, such notice shall be provided in writing to the designated representative of the party to whom the notice is addressed and shall be deemed to have been duly served if delivered in person, by mail, by courier, or by electronic transmission in accordance with AIA Document E203TM–2013, Building Information Modeling and Digital Data Exhibit, if completed, or as otherwise set forth below:

(If other than in accordance with AIA Document E203–2013, insert requirements for delivering Notice in electronic format such as name, title, and email address of the recipient and whether and how the system will be required to generate a read receipt for the transmission.)

§ 1.11.2 Notice of Claims shall be provided in writing and shall be deemed to have been duly served only if delivered to the designated representative of the party to whom the notice is addressed by certified or registered mail, or by courier providing proof of delivery.

§ 1.12 Assignment of Contract

Neither party to the Contract shall assign the Contract without written consent of the other, except that the Owner may, without consent of the Vendor, assign the Contract to a lender providing financing for the Project if the lender assumes the Owner's rights and obligations under the Contract Documents. The Vendor shall execute all consents reasonably required to facilitate such assignment.

ARTICLE 2 CONTRACT SUM AND PAYMENTS

§ 2.1 Contract Sum

§ 2.1.1 The Owner shall pay the Vendor the Contract Sum in current funds for the Vendor's performance of the Contract. The Contract Sum shall be (\$), subject to additions and deductions as provided in the Contract Documents.

§ 2.1.2 Alternates

Item

§ 2.1.2.1 Alternates, if any, included in the Contract Sum:

§ 2.1.2.2 Subject to the conditions noted below, the following alternates may be accepted by the Owner following execution of this Agreement. Upon acceptance, the Owner shall issue a Modification to this Agreement. (Insert below each alternate and the conditions that must be met for the Owner to accept the alternate.)

Price

Item Price Conditions for Acceptance

§ 2.1.3 Unit prices, if any:

(Identify the item and state the unit price and the quantity limitations, if any, to which the unit price will be applicable.)

Item Units and Limitations Price per Unit (\$0.00)

§ 2.1.4 Allowances, if any, included in the Contract Sum: *(Identify each allowance.)*

Item Price

§ 2.1.5 Liquidated damages, if any:

(Insert terms and conditions for liquidated damages, if any.)

§ 2.1.6 Other:

(Insert provisions for bonus or other incentives, if any, that might result in a change to the Contract Sum.)

§ 2.2 Payments

§ 2.2.1 The Owner shall make payments to the Vendor in conformance with the following payment terms: (Insert payment terms, such as payment due dates, deposit requirements, and prompt payment discounts, if any.)

- § 2.2.2 When payment is due pursuant to the payment terms of Section 2.2.1, the Vendor shall submit to the Owner an itemized invoice, supported by data substantiating the Vendor's right to payment.
- § 2.2.3 Except with the Owner's knowledge and consent, the Vendor shall not engage in any activity, or offer any employment, interest, or contribution to the Owner's employees or consultants, that would reasonably appear to compromise the Owner's employees' or consultants' judgment with respect to this Project.

ARTICLE 3 TIME

§ 3.1 Contract Time

- § 3.1.1 Unless otherwise provided, Contract Time is the period of time, including authorized adjustments, allotted in the Contract Documents for completion of the Work. The Contract Time shall be measured from the date of commencement. The term "day" as used in the Contract Documents shall mean calendar day unless otherwise specifically defined.
- § 3.1.2 Time limits stated in the Contract Documents are of the essence of the Contract. By executing this Agreement, the Vendor confirms that the Contract Time is a reasonable period for performing the Work.
- § 3.1.3 If the Vendor is delayed at any time in the commencement or progress of the Work by (1) changes ordered in the Work; (2) labor disputes, fire, unusual delay in deliveries, abnormal adverse weather conditions not reasonably anticipatable, unavoidable casualties, or any causes beyond the Vendor's control; or (3) other causes that the Vendor asserts, and the Architect determines, justify delay, then the Contract Time shall be extended for such reasonable time as the Architect may determine, subject to the provisions of Article 14.
- § 3.1.4 If the Vendor fails to achieve completion of the Work as provided in this Article 3, liquidated damages, if any, shall be assessed as set forth in Section 2.1.5.

§ 3.2 Date of Commencement

The date of commencement of the Work shall be: (Check one of the following boxes.)

| [] The date of this Agreement. | |
|--|-----|
| [X] A date set forth in a notice to proceed issued by the Owner. | |
| [] Established as follows: (Insert a date or a means to determine the date of commencement of the Work | :.) |
| | _ |

If a date of commencement of the Work is not selected, then the date of commencement shall be the date of this Agreement.

§ 3.3 Completion

- § 3.3.1 Completion of the Work occurs upon acceptance of all FF&E in the Contract Documents in accordance with Article 8.
- § 3.3.2 Subject to adjustments of the Contract Time as provided in the Contract Documents, the Vendor shall achieve completion of the entire Work:

(Check the appropriate box and complete the necessary information.)

- Not later than () calendar days from the date of commencement of the Work.
- [X] By the following date: January 26, 2024.
- § 3.3.3 Subject to adjustments of the Contract Time as provided in the Contract Documents, if portions of the Work are to be completed prior to completion of the entire Work, the Vendor shall achieve completion of such portions by the following dates:

Portion of Work

Completion Date

ARTICLE 4 OWNER

§ 4.1 The Owner's Representative

The Owner shall identify a representative authorized to act on behalf of the Owner with respect to the Project. The Owner's representative shall not be changed without ten days' prior notice to the Vendor. The Owner identifies the following representative:

(Name, address, email address, and other information)

Scott Ostrander

503 Geyser Road, Ballston Spa, NY 12020

§ 4.2 Information and Services Required of the Owner

- § 4.2.1 The Owner shall retain an architect lawfully licensed to practice architecture, or an entity lawfully practicing architecture, in the jurisdiction where the Project is located. That person or entity is identified as the Architect in the Agreement and is referred to throughout the Contract Documents as if singular in number.
- § 4.2.2 Unless otherwise provided in the Contract Documents, the Owner shall provide
 - .1 areas of the Project premises that the Vendor may use to perform the Work;
 - .2 access to the Project premises for the Vendor at reasonable times;
 - .3 information regarding any restrictions on the use of, or access to, the Project premises;
 - .4 suitable space for receipt, inspection, acceptance, and staging of materials and FF&E;
 - .5 utilities and facilities on the Project premises and vertical transportation necessary for progress and execution of the Work; and
 - **.6** a secured premises for storage of FF&E until acceptance.
- § 4.2.3 The Owner shall furnish information or services required of the Owner by the Contract Documents with reasonable promptness. The Owner shall furnish any other information or services under the Owner's control and relevant to the Vendor's performance of the Work with reasonable promptness after receiving the Vendor's written request for such information or services.

ARTICLE 5 VENDOR

§ 5.1 The Vendor's Representative

The Vendor shall identify a representative authorized to act on behalf of the Vendor with respect to the Project. The Vendor's representative shall not be changed without ten days' prior notice to the Owner and Architect. The Vendor identifies the following representative:

Init.

AIA Document A151 – 2019. Copyright © 2003, 2007, and 2019. All rights reserved. "The American Institute of Architects," "American Institute of Architects," "AIA," the AIA Logo, and "AIA Contract Documents" are trademarks of The American Institute of Architects. This document was produced at 10:53:23 ET on 05/24/2023 under Order No.4104238150 which expires on 12/07/2023, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail docinfo@aiacontracts.com.

User Notes:

- § 5.2 The Vendor shall not be relieved of its obligations to perform the Work in accordance with the Contract Documents by activities or duties of the Architect in the Architect's administration of the Contract.
- § 5.3 The Vendor shall coordinate its Work with the work provided by the Owner and the Owner's other vendors, consultants, and contractors. The Vendor may communicate with the Owner's other vendors, consultants, and contractors, for the purposes of completing the Work. The Vendor shall keep the Owner reasonably informed of any such communications. The Vendor shall be entitled to rely on the accuracy and completeness of work and information furnished by the Owner and the Owner's other vendors, consultants, and contractors. The Vendor shall provide prompt written notice to the Owner if the Vendor becomes aware of any error, omission, or inconsistency in such work or information.

§ 5.4 Review of Contract Documents and Inspection of Project Premises by Vendor

- § 5.4.1 Execution of the Contract by the Vendor is a representation that the Vendor has visited the Project premises, if required in the Contract Documents, and correlated personal observations with requirements of the Contract Documents.
- § 5.4.2 Before starting each portion of the Work, including placing orders for FF&E, the Vendor shall (1) carefully study and compare the various Contract Documents relative to that portion of the Work, as well as the information furnished by the Owner pursuant to Section 4.2; (2) visit and inspect the Project premises in order to gain an understanding of the conditions under which the Work is to be performed; (3) determine availability of facilities for access, delivery, transportation, and staging; (4) determine any restrictions imposed by the Owner and the Owner's separate vendors and contractors; and (5) correlate observations with the requirements of the Contract Documents. The Vendor shall promptly report to the Owner and Architect conditions observed that would impede the Vendor's performance of the Work. The Vendor's obligations to review the Contract Documents are for the purpose of facilitating delivery and installation by the Vendor and are not for the purpose of discovering errors, omissions, or inconsistencies in the Contract Documents; however, the Vendor shall promptly report to the Architect any errors, inconsistencies, or omissions discovered by or made known to the Vendor as a request for information in such form as the Architect may require. It is recognized that the Vendor's review is made in the Vendor's capacity as a vendor and not as a licensed design professional, unless otherwise specifically provided for in the Contract Documents.
- § 5.4.3 The Vendor is not required to ascertain that the Contract Documents are in accordance with applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, but the Vendor shall promptly report to the Architect any nonconformity discovered by or made known to the Vendor as a request for information in such form as the Architect may require.
- § 5.4.4 If the Vendor believes that additional cost or time is involved because of clarifications or instructions the Architect issues in response to the Vendor's notices or requests for information pursuant to Sections 5.4.2 or 5.4.3, the Vendor shall submit Claims as provided in Article 14. If the Vendor fails to perform the obligations of Sections 5.4.2 or 5.4.3, the Vendor shall pay such costs and damages to the Owner, subject to Section 14.12, as would have been avoided if the Vendor had performed such obligations. If the Vendor performs those obligations, the Vendor shall not be liable to the Owner or Architect for damages resulting from errors, inconsistencies, or omissions in the Contract Documents, for differences between field measurements or conditions and the Contract Documents, or for nonconformities of the Contract Documents to applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities.

§ 5.5 Supervision

§ 5.5.1 The Vendor shall supervise and direct the Work using the Vendor's best skill and attention. The Vendor shall be solely responsible for and have control over the means, methods, techniques, sequences, and procedures of

fabrication, shipment, delivery, and installation, and for coordinating all portions of the Work under the Contract, unless the Contract Documents give other specific instructions concerning these matters.

§ 5.5.2 The Vendor shall be responsible to the Owner for acts and omissions of the Vendor's employees, subvendors, and their agents and employees, and other persons or entities performing portions of the Work for or on behalf of the Vendor or any of its sub-vendors.

§ 5.5.3 The Vendor shall be responsible for inspection of portions of the Work already performed to determine that such portions are in proper condition for subsequent Work.

§ 5.6 Labor and Materials

§ 5.6.1 Unless otherwise provided in the Contract Documents, the Vendor shall provide and pay for labor, materials, tools, installation equipment and machinery, delivery, and other facilities and services necessary for proper execution and completion of the Work whether temporary or permanent and whether or not incorporated or to be incorporated in the Work.

§ 5.6.2 The Vendor shall enforce strict discipline and good order among the Vendor's employees and other persons carrying out the Work. The Vendor shall not permit employment of unfit persons or persons not skilled in tasks assigned to them.

§ 5.6.3 The Vendor shall make no substitution or change in the Contract Documents unless done in accordance with a Modification, and after providing the Architect notice and a reasonable opportunity to evaluate the proposed substitution or change and consult with the Owner.

§ 5.7 Taxes

The Vendor shall pay sales, consumer, use, and other similar taxes that are legally enacted when quotes are received or negotiations concluded, whether or not yet effective or merely scheduled to go into effect.

§ 5.8 Permits, Fees, Notices, and Compliance with Laws

§ 5.8.1 Unless otherwise provided in the Contract Documents, the Vendor shall secure and pay for permits, fees, licenses, and inspections by government agencies necessary for proper execution and completion of the Work that are customarily secured after execution of the Contract and legally required at the time bids are received or negotiations concluded.

§ 5.8.2 The Vendor shall comply with and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities applicable to performance of the Work. If the Vendor performs Work knowing it to be contrary to applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, the Vendor shall assume appropriate responsibility for such Work and shall bear the costs attributable to correction.

§ 5.9 Allowances

The Vendor shall include in the Contract Sum all allowances stated in the Contract Documents. The Owner shall select items under allowances with reasonable promptness. Allowance amounts shall include the costs to the Vendor of items delivered at the Project premises and all required taxes, less applicable trade discounts. Vendor's costs for unloading and handling at the Project premises, labor, installation, overhead, profit, and other expenses contemplated for stated allowance amounts shall be included in the Contract Sum but not in the allowance. Whenever costs are more than or less than allowances, the Contract Sum shall be adjusted accordingly by Modification. The amount of the Modification shall reflect the difference between actual costs and the allowances under Section 2.1.4.

§ 5.10 Vendor's Schedules

§ 5.10.1 The Vendor, promptly after being awarded the Contract, shall submit for the Owner's and Architect's information a progress schedule for the Work. The schedule shall not exceed time limits current under the Contract Documents, shall be revised at appropriate intervals as required by the progress of the Work and Project, shall be related to the entire Project, and shall provide for expeditious and practicable execution of the Work.

§ 5.10.2 The Vendor shall perform the Work in general accordance with the most recent schedule submitted to the Owner and Architect.

§ 5.10.3 The Vendor's progress schedule shall indicate dates for commencement and completion of phases of the Work within the Contract Time, including dates for order placement, fabrication, shipping, delivery, and installation. The schedule shall indicate other critical dates, such as deadlines for approval of submittals of colors, finishes, and materials. The Vendor shall obtain and submit for the Owner's and the Architect's information written confirmation from sub-vendors of dates of fabrication and delivery.

§ 5.10.4 The Vendor shall cooperate with the Owner and Architect in coordinating the Vendor's progress schedule with those of contractors and separate vendors and with the requirements of the Owner and Architect. The Vendor shall cooperate in determining mutually acceptable dates and times for delivery, installation, and inspection of the Work, and use of services and facilities provided to the Vendor, all to be confirmed in writing within a reasonable time in advance of such dates and times.

§ 5.11 Submittals

§ 5.11.1 The Vendor shall review for compliance with the Contract Documents and submit to the Architect shop drawings, product data, samples, and similar submittals required by the Contract Documents in coordination with the Vendor's progress schedule and in such sequence as to allow the Architect reasonable time for review. By submitting shop drawings, product data, samples, and similar submittals, the Vendor represents to the Owner and Architect that the Vendor has (1) reviewed and approved them; (2) determined and verified materials, field measurements, and field installation criteria related thereto, or will do so; and (3) checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents. The Work shall be in accordance with approved submittals. Shop drawings, product data, samples and similar submittals are not Contract Documents.

§ 5.11.2 The Vendor shall provide the Owner with available manufacturer's warranty documents, product data, and material safety data sheets.

§ 5.12 Cleaning Up

The Vendor shall keep the Project premises and surrounding area free from accumulation of waste materials and rubbish caused by operations under the Contract. At completion of the Work, the Vendor shall remove waste materials, rubbish, the Vendor's tools, construction equipment, machinery, and surplus material from and about the Project.

§ 5.13 Access to Work

The Vendor shall provide the Owner and Architect with reasonable access to the Work in preparation and progress wherever located.

§ 5.14 Indemnification

§ 5.14.1 To the fullest extent permitted by law, the Vendor shall indemnify and hold harmless the Owner, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work, provided that such claim, damage, loss, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), but only to the extent caused by the negligent acts or omissions of the Vendor, a sub-vendor, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, regardless of whether or not such claim, damage, loss, or expense is caused in part by a party indemnified hereunder. Such obligation shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity which would otherwise exist as to a party or person described in this Section 5.14.1.

§ 5.14.2 In claims against any person or entity indemnified under Section 5.14.1 by an employee of the Vendor, a sub-vendor, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, the indemnification obligation under Section 5.14.1 shall not be limited by a limitation on amount or type of damages, compensation, or benefits payable by or for the Vendor or sub-vendor under workers' compensation acts, disability benefit acts, or other employee benefit acts.

§ 5.14.3 Provided the Owner has fulfilled its payment obligations under the Contract Documents, the Vendor shall defend and indemnify the Owner from all loss, liability, damage or expense, including reasonable attorney's fees and litigation expenses, arising out of any lien claim or other claim for payment by any sub-vendor or supplier of any tier. Upon receipt of notice of a lien claim or other claim for payment, the Owner shall notify the Vendor. If approved by the applicable court, when required, the Vendor may substitute a surety bond for the property against which the lien or other claim for payment has been asserted.

ARTICLE 6 TITLE AND RISK OF LOSS

- § 6.1 Title to all FF&E shall be transferred to the Owner upon acceptance in accordance with Article 8.
- § 6.2 The risk of loss with respect to all FF&E provided by the Vendor shall remain with the Vendor, and the Owner has no obligation to insure such FF&E, until acceptance in accordance with Article 8.

ARTICLE 7 DELIVERY AND INSTALLATION

- § 7.1 The Vendor shall deliver FF&E in accordance with the Vendor's progress schedule, or at a time agreed upon by the Owner and Architect, and in accordance with Article 5.
- § 7.2 Delivery and installation of all FF&E shall be made at the Project premises unless otherwise specified in the Contract Documents.
- § 7.3 The Vendor shall coordinate with the Owner regarding the logistics of the Vendor's delivery and installation obligations at the Project premises.

ARTICLE 8 ACCEPTANCE

- § 8.1 The Owner and Architect may conduct a preliminary inspection of FF&E within seven days after its delivery to the Project premises for the purpose of verifying the delivery and quantities. Preliminary inspections shall not constitute acceptance of, taking charge over, or taking control of, such FF&E. The Architect shall report to the Vendor any defects, damage, deficiencies, or nonconformity observed during the preliminary inspection.
- § 8.2 When the Vendor considers the Work, or a portion thereof which the Owner agrees to accept separately, to be complete, the Vendor shall notify the Owner and Architect. The Vendor shall allow the Owner and Architect a reasonable amount of time to inspect the FF&E to determine, based on conformance with the Contract Documents, if it is accepted or rejected in whole or in part. Based on the Architect's recommendation to the Owner and the Owner's own inspection, if any, the Owner shall accept or reject the FF&E, in whole or in part.
- § 8.3 If the Owner rejects any of the FF&E, the Owner, or the Architect acting on behalf of the Owner, shall notify the Vendor within seven days of the date of inspection, specifying the basis for such rejection. Upon rejection, the Vendor shall provide a remedy and evidence of arrangements to accomplish such remedy. The Owner shall allow the Vendor a reasonable amount of time to remedy the rejected FF&E. When the Vendor considers the remedied FF&E to be complete, the parties shall follow the procedures set forth in Section 8.2. If the Owner rejects any of the FF&E for a second time, the Owner shall promptly notify the Vendor and the Vendor shall promptly remove the rejected FF&E from the Project premises and refund payments made for such rejected goods to the Owner. If the Vendor disagrees with an Owner's rejection, the Vendor may make a claim.
- § 8.4 FF&E not inspected in accordance with Section 8.2 or rejected in accordance with Section 8.3 shall be deemed accepted.
- § 8.5 The Owner's acceptance under this Article 8 cannot be revoked; however, the provisions of this Article 8 do not preclude recovery of damages as provided by law. The Owner's acceptance, or failure to discover a Vendor's breach after acceptance, shall not bar the Owner from making claims in accordance with Article 14 or from remedies and damages due to the Vendor's breach of this Agreement, including the Vendor's breach of warranties in Article 9.

ARTICLE 9 WARRANTIES

§ 9.1 The Vendor warrants to the Owner that the FF&E furnished under the Contract will be of good quality and new unless the Contract Documents require or permit otherwise. The Vendor further warrants that the FF&E will conform to the requirements of the Contract Documents. FF&E not conforming to these requirements may be

considered defective. The Vendor's warranty excludes remedy for damage or defect caused by abuse, alterations to the FF&E not executed by the Vendor, improper or insufficient maintenance, improper operation, or normal wear and tear and normal usage.

- § 9.2 The Vendor assigns to the Owner all FF&E manufacturers' warranties and guarantees upon acceptance in accordance with Article 8.
- § 9.3 The Vendor hereby provides to the Owner all warranties relating to the FF&E implied by law, including the warranty of merchantability and warranty of fitness for a particular purpose.
- § 9.4 The Vendor acknowledges that no exclusion of, or limitation on, warranties contained in any proposal, product literature, or other submittal shall affect the warranties provided in this Article 9.

ARTICLE 10 ARCHITECT

- § 10.1 The Architect will provide administration of the Contract as described in the Contract Documents and will be an Owner's representative during the Vendor's performance, and until completion, of the Work. The Architect will have authority to act on behalf of the Owner only to the extent provided in the Contract Documents, unless otherwise modified in writing in accordance with other provisions of the Contract.
- § 10.2 Except as otherwise provided in the Contract Documents or when direct communications have been specially authorized, the Owner and Vendor shall endeavor to communicate with each other through the Architect about matters arising out of or relating to the Contract. Communications by and with the Architect's consultants shall be through the Architect. Communications by and with sub-vendors and suppliers shall be through the Vendor. Communications by and with separate vendors shall be through the Owner. The Contract Documents may specify other communication protocols.
- § 10.3 The Architect will assist the Owner in coordinating schedules for fabrication, delivery, and installation of the Work, but will not be responsible for failure of the Vendor or a sub-vendor to meet schedules for completion or to perform their respective duties and responsibilities in conformance with applicable schedules.
- § 10.4 The Architect will visit the Project premises at intervals appropriate to the stage of the Work, or as otherwise agreed with the Owner, to become generally familiar with, and to keep the Owner informed about, the progress and quality of the portion of the Work completed, and to determine, in general, if the Work observed is being performed in a manner indicating that the Work, when fully completed, will be in accordance with the Contract Documents. The Architect will not have control over, charge of, or responsibility for, the means, methods, techniques, sequences, or procedures of fabrication, shipment, delivery, storage, or installation, or for the safety precautions and programs in connection with the Work, as these are solely the Vendor's rights and responsibilities under the Contract Documents.
- § 10.5 The Architect may order minor changes in the Work. The Architect's order for minor changes shall be in writing. If the Vendor believes that the proposed minor change in the Work will affect the Contract Sum or Contract Time, the Vendor shall notify the Architect and shall not proceed to implement the change in the Work. If the Vendor performs the Work set forth in the Architect's order for a minor change without prior notice to the Architect that such change will affect the Contract Sum or Contract Time, the Vendor waives any adjustment to the Contract Sum or extension of the Contract Time.
- § 10.6 The Architect will conduct inspections of FF&E and provide recommendations as set forth in Article 8. Pursuant to Article 8, the Architect is only responsible for identifying defects, deficiencies, or nonconformities that the Architect actually observes, or reasonably should observe, during its inspections. The Architect is not required to make exhaustive or continuous inspections to fulfill its responsibilities in Article 8 and has no responsibility to discover latent defects.
- § 10.7 The Architect will review and approve or take other appropriate action upon the Vendor's submittals such as shop drawings, product data, and samples, but only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents.

ARTICLE 11 RELATED ACTIVITIES OF OWNER OR OF SEPARATE VENDORS

§ 11.1 The Owner shall coordinate the activities of the Owner's own forces and of each separate vendor or contractor, if any, with the Work.

§ 11.2 If the Work depends for proper execution or results upon activities by the Owner or a separate vendor or contractor, the Vendor shall, prior to proceeding with that portion of the Work, promptly report to the Owner and Architect apparent discrepancies or defects in, or arising from, the activities of the Owner or separate vendors or contractors, that would impede the Vendor in achieving proper execution and results. If the Vendor fails to report reasonably discoverable discrepancies or defects, it shall be responsible for deficiencies or defects in its Work due to such deficiencies or defects.

§ 11.3 The Vendor shall reimburse the Owner for costs the Owner incurs that are payable to a separate vendor or contractor because of the Vendor's delays, improperly timed activities, or damage to the work of a separate vendor or contractor. The Owner shall be responsible to the Vendor for costs the Vendor incurs because of the delays, improperly timed activities, or damage to the Work caused by a separate vendor or contractor.

§ 11.4 If a dispute arises among the Vendor, separate vendors, or contractors, and the Owner as to the responsibility under their respective contracts for maintaining the Project premises and surrounding area free from waste materials and rubbish, the Owner may clean up and the Architect will allocate the cost among those responsible.

ARTICLE 12 PROTECTION OF PERSONS AND PROPERTY

§ 12.1 Safety Precautions and Programs

The Vendor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Contract. The Vendor shall take reasonable precautions for safety of, and shall provide reasonable protection to prevent damage, injury, or loss to

- .1 employees on the Work and other persons who may be affected thereby;
- .2 the Work, and materials and FF&E to be incorporated therein, whether in storage on or off the Project premises, under care, custody, or control of the Vendor or sub-vendors; and
- .3 other property at the Project premises or adjacent thereto.

The Vendor shall comply with, and give notices required by, applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities bearing on safety of persons and property and their protection from damage, injury, or loss. The Vendor shall promptly remedy damage and loss to property caused in whole or in part by the Vendor, sub-vendors, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable and for which the Vendor is responsible under Sections 12.1.2 and 12.1.3. The Vendor may make a claim for the cost to remedy the damage or loss to the extent such damage or loss is attributable to acts or omissions of the Owner or Architect, or of anyone for whose acts either of them may be liable, and not attributable to the fault or negligence of the Vendor. The foregoing obligations of the Vendor are in addition to the Vendor's obligations under Section 5.14.

§ 12.2 Hazardous Materials and Substances

§ 12.2.1 The Vendor is responsible for compliance with the requirements of the Contract Documents regarding hazardous materials or substances. If the Vendor encounters a hazardous material or substance not addressed in the Contract Documents, and if reasonable precautions will be inadequate to prevent foreseeable bodily injury or death to persons resulting from a material or substance, including but not limited to asbestos or polychlorinated biphenyl (PCB), encountered on the Project premises by the Vendor, the Vendor shall, upon recognizing the condition, immediately stop Work in the affected area and notify the Owner and Architect of the condition. When the material or substance has been rendered harmless, Work in the affected area shall resume upon written agreement of the Owner and Vendor. By written agreement between the Owner and Vendor, the Contract Time shall be extended appropriately, and the Contract Sum shall be increased in the amount of the Vendor's reasonable additional costs of shutdown, delay, and start-up.

§ 12.2.2 To the fullest extent permitted by law, the Owner shall indemnify and hold harmless the Vendor, subvendors, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses, and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work in the affected area, if in fact, the material or substance presents the risk of bodily injury or death as described in Section 12.2.1 and has not been rendered harmless, provided that such claim, damage, loss, or

expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), except to the extent that such damage, loss, or expense is due to the fault or negligence of the party seeking indemnity.

§ 12.2.3 If, without negligence on the part of the Vendor, the Vendor is held liable by a government agency for the cost of remediation of a hazardous material or substance solely by reason of performing Work as required by the Contract Documents, the Owner shall indemnify the Vendor for all cost and expense thereby incurred.

ARTICLE 13 INSURANCE

- § 13.1 The Vendor shall purchase and maintain insurance of the types and limits of liability, containing the endorsements, and subject to the terms and conditions, as described in this Article 13 or elsewhere in the Contract Documents. The Vendor shall purchase and maintain the insurance required by this Agreement from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located. The Vendor shall maintain the required insurance from the date of commencement of the Work to the date of completion of the Work, unless a different duration is stated below.
- § 13.2 Commercial General Liability insurance for the Project written on an occurrence form with policy limits of not less than One Million Dollars and Zero Cents (\$ 1000000.00) each occurrence, Two Million Dollars and Zero Cents (\$ 2000000.00) general aggregate, and Two Million Dollars and Zero Cents (\$ 2000000.00) aggregate for products-completed operations hazard, providing coverage for claims including
 - .1 damages because of bodily injury, sickness or disease, including occupational sickness or disease, and death of any person;
 - .2 personal and advertising injury;
 - .3 damages because of physical damage to or destruction of tangible property, including the loss of use of such property;
 - .4 bodily injury or property damage arising out of completed operations; and
 - .5 the Vendor's indemnity obligations under Section 5.14.
- § 13.3 Automobile Liability covering vehicles owned by the Vendor and non-owned vehicles used by the Vendor, with policy limits of not less than One Million Dollars and Zero Cents (\$ 1000000.00) per accident, for bodily injury, death of any person, and property damage arising out of the ownership, maintenance, and use of those motor vehicles along with any other statutorily required automobile coverage.
- § 13.4 The Vendor may achieve the required limits and coverage for Commercial General Liability and Automobile Liability through a combination of primary and excess or umbrella liability insurance, provided such primary and excess or umbrella insurance policies result in the same or greater coverage as those required under Sections 13.2 and 13.3, and in no event shall any excess or umbrella liability insurance provide narrower coverage than the primary policy. The excess policy shall not require the exhaustion of the underlying limits only through the actual payment by the underlying insurers.
- § 13.5 Workers' Compensation at statutory limits.
- § 13.6 Employers' Liability with policy limits not less than One Million Dollars and Zero Cents (\$ 1000000.00) each accident, One Million Dollars and Zero Cents (\$ 1000000.00) each employee, and One Million Dollars and Zero Cents (\$ 1000000.00) policy limit.
- § 13.7 If the Vendor is required to furnish professional services as part of the Work, the Vendor shall procure Professional Liability insurance covering performance of the professional services, with policy limits of not less than (\$) per claim and (\$) in the aggregate.
- § 13.8 The Vendor shall provide certificates of insurance acceptable to the Owner evidencing compliance with the requirements in this Article 13 at the following times: (1) prior to commencement of the Work; (2) upon renewal or replacement of each required policy of insurance; and (3) upon the Owner's written request. An additional certificate evidencing continuation of liability coverage, including coverage for completed operations, shall be submitted with the final invoice and thereafter upon renewal or replacement of such coverage until the expiration of the period required by Section 13.1. The certificates will show the Owner as an additional insured on the Vendor's Commercial General Liability and excess or umbrella liability policy.

§ 13.9 The Vendor shall disclose to the Owner any deductible or self- insured retentions applicable to any insurance required to be provided by the Vendor.

§ 13.10 To the fullest extent permitted by law, the Vendor shall cause the commercial liability coverage required by this Article 13 to include (1) the Owner, the Architect, and the Architect's Consultants as additional insureds for claims caused in whole or in part by the Vendor's negligent acts or omissions during the Vendor's operations; and (2) the Owner as an additional insured for claims caused in whole or in part by the Vendor's negligent acts or omissions for which loss occurs during completed operations. The additional insured coverage shall be primary and non-contributory to any of the Owner's general liability insurance policies and shall apply to both ongoing and completed operations. To the extent commercially available, the additional insured coverage shall be no less than that provided by Insurance Services Office, Inc. (ISO) forms CG 20 10 07 04, CG 20 37 07 04, and, with respect to the Architect and the Architect's Consultants, CG 20 32 07 04.

§ 13.11 Within three (3) business days of the date the Vendor becomes aware of an impending or actual cancellation or expiration of any insurance required by this Article 13, the Vendor shall provide notice to the Owner of such impending or actual cancellation or expiration. Upon receipt of notice from the Vendor, the Owner shall, unless the lapse in coverage arises from an act or omission of the Owner, have the right to stop the Work until the lapse in coverage has been cured by the procurement of replacement coverage by the Vendor. The furnishing of notice by the Vendor shall not relieve the Vendor of any contractual obligation to provide any required coverage.

§ 13.12 Other Insurance Provided by the Vendor

(List below any other insurance coverage to be provided by the Vendor and any applicable limits.)

| Coverage | Limits |
|---------------------------|--|
| Umbrella Liability Policy | \$3,000,000.00; to cover General Liability and Auto |
| | Liability; Name Town and Engineer as additional insured |
| Polution Liability Policy | \$1,000,000.00; Name Town and Engineer as additional insured |

§ 13.13 Waiver of Subrogation

§ 13.13.1 The Owner and Vendor waive all rights against (1) each other and any of their sub-vendors, agents, and employees, each of the other; (2) the Architect and Architect's consultants; and (3) separate vendors or contractors, if any, and any of their sub-vendors, subcontractors, sub-subcontractors, agents, and employees, for damages caused by fire, or other causes of loss, to the extent those losses are covered by property insurance required by this Agreement or other property insurance applicable to the Project, except such rights as they have to proceeds of such insurance. The Owner or Vendor, as appropriate, shall require similar written waivers in favor of the individuals and entities identified above from the Architect, Architect's consultants, separate vendors and contractors, and sub-vendors, subcontractors, and sub-subcontractors. The policies of insurance purchased and maintained by each person or entity agreeing to waive claims pursuant to this Section 13.13.1 shall not prohibit this waiver of subrogation. This waiver of subrogation shall be effective as to a person or entity (1) even though that person or entity would otherwise have a duty of indemnification, contractual, or otherwise, (2) even though that person or entity did not pay the insurance premium directly or indirectly, or (3) whether or not the person or entity had an insurable interest in the damaged property.

§ 13.13.2 A loss insured under the Owner's property insurance shall be adjusted by the Owner as fiduciary and made payable to the Owner as fiduciary for the insureds, as their interests may appear, subject to requirements of any applicable mortgagee clause. The Owner shall pay the Architect and Vendor their just shares of insurance proceeds received by the Owner, and by appropriate agreements, written where legally required for validity, the Architect and Vendor shall make payments to their consultants and sub-vendors in similar manner.

ARTICLE 14 CLAIMS AND DISPUTES

§ 14.1 Binding Dispute Resolution

For any claim subject to, but not resolved by, mediation pursuant to Section 14.6, the method of binding dispute resolution shall be as follows:

(Check the appropriate box.)

| (| TI I |
|----|--|
| [] | Arbitration pursuant to Section 14.7 of this Agreement |

[X] Litigation in a court of competent jurisdiction

[] Other (Specify)

If the Owner and Vendor do not select a method of binding dispute resolution, or do not subsequently agree in writing to a binding dispute resolution method other than litigation, claims will be resolved in a court of competent jurisdiction.

§ 14.2 Claims, disputes, and other matters in question arising out of or relating to this Contract, including those alleging an error or omission by the Architect but excluding those arising under Section 12.2, shall be referred initially to the Architect for decision. Such matters, except those waived as provided for in Section 14.12, shall, after initial decision by the Architect or 30 days after submission of the matter to the Architect, be subject to mediation as a condition precedent to binding dispute resolution.

§ 14.3 Notice of Claims

Claims by either the Owner or Vendor shall be initiated by notice to the other party in accordance with Section 1.11.2.

§ 14.4 Time Limits on Claims

The Owner and Vendor shall commence all claims and causes of action against the other and arising out of or related to the Contract in accordance with the requirements of the final dispute resolution method selected in this Agreement, whether in contract, tort, breach of warranty, or otherwise, within the period specified by applicable law, but in any case not more than 10 years after the date of completion of the Work. The Owner and Vendor waive all claims and causes of action not commenced in accordance with this Section 14.4.

§ 14.5 If a claim, dispute, or other matter in question relates to or is the subject of a mechanic's lien, the party asserting such matter may proceed in accordance with applicable law to comply with the lien procedures, including notice or filing deadlines.

§ 14.6 The parties shall endeavor to resolve their disputes by mediation which, unless the parties mutually agree otherwise, shall be administered by the American Arbitration Association in accordance with their Construction Industry Mediation Procedures in effect on the date of this Agreement. A request for mediation shall be made in writing, delivered to the other party to this Agreement, and filed with the person or entity administering the mediation. The request may be made concurrently with the binding dispute resolution proceedings but, in such event, mediation shall proceed in advance of binding dispute resolution proceedings, which shall be stayed pending mediation for a period of 60 days from the date of filing, unless stayed for a longer period by agreement of the parties or court order. If an arbitration is stayed pursuant to this Section, the parties may nonetheless proceed to the selection of the arbitrator(s) and agree upon a schedule for later proceedings.

§ 14.7 If the parties have selected arbitration as the method for binding dispute resolution in this Agreement, any claim, subject to, but not resolved by, mediation shall be subject to arbitration which, unless the parties mutually agree otherwise, shall be administered by the American Arbitration Association, in accordance with the Construction Industry Arbitration Rules in effect on the date of this Agreement. Demand for arbitration shall be made in writing, delivered to the other party to the Contract, and filed with the person or entity administering the arbitration. The award rendered by the arbitrator or arbitrators shall be final, and judgment may be entered upon it in accordance with applicable law in any court having jurisdiction thereof.

§ 14.8 Subject to the rules of the American Arbitration Association or other applicable arbitration rules, either party, at its sole discretion, may consolidate an arbitration conducted under this Agreement with any other arbitration to which it is a party provided that (1) the arbitration agreement governing the other arbitration permits consolidation; (2) the arbitrations to be consolidated substantially involve common questions of law or fact; and (3) the arbitrations employ materially similar procedural rules and methods for selecting arbitrator(s).

§ 14.9 Subject to the rules of the American Arbitration Association or other applicable arbitration rules, any party to an arbitration may include by joinder persons or entities substantially involved in a common question of law or fact whose presence is required if complete relief is to be accorded in arbitration provided that the party sought to be joined consents in writing to such joinder. Consent to arbitration involving an additional person or entity shall not constitute consent to arbitration of a Claim not described in the written Consent.

§ 14.10 The foregoing agreement to arbitrate and other agreements to arbitrate with an additional person or entity duly consented to by parties to this Agreement shall be specifically enforceable under applicable law in any court having jurisdiction thereof.

§ 14.11 Continuing Contract Performance

Pending final resolution of a Claim, except as otherwise agreed in writing, the Vendor shall proceed diligently with performance of the Contract and the Owner shall continue to make payments in accordance with the Contract Documents.

§ 14.12 Waiver of Claims for Consequential Damages

The Vendor and Owner waive claims against each other for consequential damages arising out of or relating to this Contract. This mutual waiver includes

- .1 damages incurred by the Owner for rental expenses, for losses of use, income, profit, financing, business and reputation, and for loss of management or employee productivity or of the services of such persons; and
- .2 damages incurred by the Vendor for principal office expenses including the compensation of personnel stationed there, for losses of financing, business, and reputation, and for loss of profit except anticipated profit arising directly from the Work.

This mutual waiver is applicable, without limitation, to all consequential damages. Nothing contained in this Section 14.12 shall be deemed to preclude an assessment of liquidated damages, when applicable, in accordance with the requirements of the Contract Documents.

ARTICLE 15 ENUMERATION OF CONTRACT DOCUMENTS

§ 15.1 The Contract Documents are defined in Article 1 and, except for Modifications issued after execution of this Agreement, are enumerated in the sections below.

§ 15.2 The Agreement is this executed AIA Document A151TM_2019, Standard Form of Agreement Between Owner and Vendor for Furniture, Furnishings, and Equipment.

§ 15.3 AIA Document A201[™]_2017, General Conditions of the Contract for Construction.

§ 15.4 AIA Document E203TM—2013, Building Information Modeling and Digital Data Exhibit, dated as indicated

(Insert the date of the E203–2013 incorporated into this Agreement.)

§ 15.4 The Specifications:

(Either list the Specifications here or refer to an exhibit attached to this Agreement.)

Title of Specifications exhibit: Rowland Street Highway Facility - Cold Storage Pre-Engineered Metal Building **Specifications**

16

| Se | ection | Title | | Date | Pages | | |
|---|---|-------------------------------------|--------------------------|------------|-------|--|--|
| § 15.5 The (Either list | | re or refer to an exhibit o | attached to this Agreeme | ent.) | | | |
| Title of Drawings | Title of Drawings exhibit: Rowland Street Highway Facility - Cold Storage Pre-Engineered Metal Building Drawings | | | | | | |
| Nu | umber | Title | | Date | | | |
| § 15.6 The | Addenda, if any: | | | | | | |
| Nu | umber | | | Date | Pages | | |
| the quotation § 15.7 Addi | Portions of Addenda relating to quotations or proposal requirements are not part of the Contract Documents unless the quotation or proposal requirements are enumerated in this Article 15. § 15.7 Additional documents, if any, forming part of the Contract Documents: .1 Other Exhibits: | | | | | | |
| | | xes that apply.) stainability Plan: | | | | | |
| | Title | istaliaointy 1 Ian. | Dete | Damas | | | |
| | Title | | Date | Pages | | | |
| | [] Supplementary and other Conditions of the Contract: | | | | | | |
| | Document | | Title | Date | Pages | | |
| .2 Other documents, if any, listed below: (List here any additional documents that are intended to form part of the Contract Documents.) | | | | | | | |
| This Agree | ement entered into | as of the day and year f | irst written above. | | | | |
| OWNER (S | Signature) | | VENDOR (Sign | ature) | | | |
| , | ander, Town Sup | ervisor | (3.8.1 | -/ | | | |
| | name and title) | -1.1001 | (Printed name | and title) | | | |
| | | | | | | | |



General Conditions of the Contract for Construction

for the following PROJECT:

(Name and location or address)

Town of Milton Rowland Street Highway Facility - Cold Storage PEMB

THE OWNER:

(Name, legal status and address)

Town of Milton 503 Geyser Road, Ballston Spa, NY 12020

THE ARCHITECT:

(Name, legal status and address)

Delaware Engineering, DPC 28 Madison Ave Ext., Albany, NY 12203

TABLE OF ARTICLES

- 1 GENERAL PROVISIONS
- 2 OWNER
- 3 CONTRACTOR
- 4 ARCHITECT
- **5 SUBCONTRACTORS**
- **6 CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS**
- 7 CHANGES IN THE WORK
- 8 TIME

User Notes:

- 9 PAYMENTS AND COMPLETION
- 10 PROTECTION OF PERSONS AND PROPERTY
- 11 INSURANCE AND BONDS
- 12 UNCOVERING AND CORRECTION OF WORK
- 13 MISCELLANEOUS PROVISIONS
- 14 TERMINATION OR SUSPENSION OF THE CONTRACT
- 15 CLAIMS AND DISPUTES

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An Additions and Deletions Report that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

For guidance in modifying this document to include supplementary conditions, see AIA Document A503™, Guide for Supplementary Conditions.

| INDEX | 2.5, 3.1.3, 3.5, 3.10.2, 4.2.7 |
|---|---|
| (Topics and numbers in bold are Section headings.) | Architect's Authority to Reject Work |
| 5 / | 3.5, 4.2.6, 12.1.2, 12.2.1 |
| | Architect's Copyright |
| Acceptance of Nonconforming Work | 1.1.7, 1.5 |
| 9.6.6, 9.9.3, 12.3 | Architect's Decisions |
| Acceptance of Work | 3.7.4, 4.2.6, 4.2.7, 4.2.11, 4.2.12, 4.2.13, 4.2.14, 6.3, |
| 9.6.6, 9.8.2, 9.9.3, 9.10.1, 9.10.3, 12.3 | 7.3.4, 7.3.9, 8.1.3, 8.3.1, 9.2, 9.4.1, 9.5, 9.8.4, 9.9.1, |
| Access to Work | 13.4.2, 15.2 |
| 3.16, 6.2.1, 12.1 | Architect's Inspections |
| Accident Prevention | 3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.8.3, 9.9.2, 9.10.1, 13.4 |
| | Architect's Instructions |
| 10 | |
| Acts and Omissions | 3.2.4, 3.3.1, 4.2.6, 4.2.7, 13.4.2 |
| 3.2, 3.3.2, 3.12.8, 3.18, 4.2.3, 8.3.1, 9.5.1, 10.2.5, | Architect's Interpretations |
| 10.2.8, 13.3.2, 14.1, 15.1.2, 15.2 | 4.2.11, 4.2.12 |
| Addenda | Architect's Project Representative |
| 1.1.1 | 4.2.10 |
| Additional Costs, Claims for | Architect's Relationship with Contractor |
| 3.7.4, 3.7.5, 10.3.2, 15.1.5 | 1.1.2, 1.5, 2.3.3, 3.1.3, 3.2.2, 3.2.3, 3.2.4, 3.3.1, 3.4.2 |
| Additional Inspections and Testing | 3.5, 3.7.4, 3.7.5, 3.9.2, 3.9.3, 3.10, 3.11, 3.12, 3.16, |
| 9.4.2, 9.8.3, 12.2.1, 13.4 | 3.18, 4.1.2, 4.2, 5.2, 6.2.2, 7, 8.3.1, 9.2, 9.3, 9.4, 9.5, |
| Additional Time, Claims for | 9.7, 9.8, 9.9, 10.2.6, 10.3, 11.3, 12, 13.3.2, 13.4, 15.2 |
| 3.2.4, 3.7.4, 3.7.5, 3.10.2, 8.3.2, 15.1.6 | Architect's Relationship with Subcontractors |
| Administration of the Contract | 1.1.2, 4.2.3, 4.2.4, 4.2.6, 9.6.3, 9.6.4, 11.3 |
| 3.1.3, 4.2, 9.4, 9.5 | Architect's Representations |
| Advertisement or Invitation to Bid | 9.4.2, 9.5.1, 9.10.1 |
| 1.1.1 | Architect's Site Visits |
| Aesthetic Effect | 3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.5.1, 9.9.2, 9.10.1, 13.4 |
| 4.2.13 | Asbestos |
| Allowances | 10.3.1 |
| 3.8 | Attorneys' Fees |
| Applications for Payment | 3.18.1, 9.6.8, 9.10.2, 10.3.3 |
| 4.2.5, 7.3.9, 9.2, 9.3, 9.4, 9.5.1, 9.5.4, 9.6.3, 9.7, 9.10 | Award of Separate Contracts |
| Approvals | 6.1.1, 6.1.2 |
| 2.1.1, 2.3.1, 2.5, 3.1.3, 3.10.2, 3.12.8, 3.12.9, | Award of Subcontracts and Other Contracts for |
| 3.12.10.1, 4.2.7, 9.3.2, 13.4.1 | Portions of the Work |
| Arbitration | 5.2 |
| 8.3.1, 15.3.2, 15.4 | Basic Definitions |
| ARCHITECT | 1.1 |
| 4 | Bidding Requirements |
| Architect, Definition of | 1.1.1 |
| 4.1.1 | Binding Dispute Resolution |
| Architect, Extent of Authority | 8.3.1, 9.7, 11.5, 13.1, 15.1.2, 15.1.3, 15.2.1, 15.2.5, |
| 2.5, 3.12.7, 4.1.2, 4.2, 5.2, 6.3, 7.1.2, 7.3.4, 7.4, 9.2, | 15.2.6.1, 15.3.1, 15.3.2, 15.3.3, 15.4.1 |
| 9.3.1, 9.4, 9.5, 9.6.3, 9.8, 9.10.1, 9.10.3, 12.1, 12.2.1, | Bonds, Lien |
| 13.4.1, 13.4.2, 14.2.2, 14.2.4, 15.1.4, 15.2.1 | 7.3.4.4, 9.6.8, 9.10.2, 9.10.3 |
| Architect, Limitations of Authority and | Bonds, Performance, and Payment |
| Responsibility | 7.3.4.4, 9.6.7, 9.10.3, 11.1.2, 11.1.3, 11.5 |
| 2.1.1, 3.12.4, 3.12.8, 3.12.10, 4.1.2, 4.2.1, 4.2.2, | Building Information Models Use and Reliance |
| 4.2.3, 4.2.6, 4.2.7, 4.2.10, 4.2.12, 4.2.13, 5.2.1, 7.4, | 1.8 |
| 9.4.2, 9.5.4, 9.6.4, 15.1.4, 15.2 | Building Permit |
| Architect's Additional Services and Expenses | 3.7.1 |
| 2.5, 12.2.1, 13.4.2, 13.4.3, 14.2.4 | Capitalization |
| Architect's Administration of the Contract | 1.3 |
| 3.1.3, 3.7.4, 15.2, 9.4.1, 9.5 | Certificate of Substantial Completion |
| Architect's Approvals | 9.8.3, 9.8.4, 9.8.5 |
| monitori s Approvais | 7.0.3, 7.0. 1 , 7.0.3 |

Init.

User Notes:

AIA Document A201 – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017. All rights reserved. "The American Institute of Architects," "American Institute of Architects," "AIA," the AIA Logo, and "AIA Contract Documents" are trademarks of The American Institute of Architects. This document was produced at 14:57:08 ET on 05/18/2023 under Order No.4104238150 which expires on 12/07/2023, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail docinfo@aiacontracts.com.

| Certificates for Payment 4.2.1, 4.2.5, 4.2.9, 9.3.3, 9.4, 9.5, 9.6.1, 9.6.6, 9.7, | 3.7.4, 4.2.8, 8.3.1, 10.3 Conditions of the Contract |
|---|---|
| 9.10.1, 9.10.3, 14.1.1.3, 14.2.4, 15.1.4 | 1.1.1, 6.1.1, 6.1.4 |
| Certificates of Inspection, Testing or Approval | Consent, Written |
| 13.4.4 | 3.4.2, 3.14.2, 4.1.2, 9.8.5, 9.9.1, 9.10.2, 9.10.3, 13.2, |
| Certificates of Insurance | 15.4.4.2 |
| 9.10.2 | Consolidation or Joinder |
| Change Orders | 15.4.4 |
| 1.1.1, 3.4.2, 3.7.4, 3.8.2.3, 3.11, 3.12.8, 4.2.8, 5.2.3, | CONSTRUCTION BY OWNER OR BY |
| 7.1.2, 7.1.3, 7.2, 7.3.2, 7.3.7, 7.3.9, 7.3.10, 8.3.1, | SEPARATE CONTRACTORS |
| 9.3.1.1, 9.10.3, 10.3.2, 11.2, 11.5, 12.1.2 | 1.1.4, 6 |
| Change Orders, Definition of | Construction Change Directive, Definition of |
| 7.2.1 | 7.3.1 |
| CHANGES IN THE WORK | Construction Change Directives |
| 2.2.2, 3.11, 4.2.8, 7, 7.2.1, 7.3.1, 7.4, 8.3.1, 9.3.1.1, | 1.1.1, 3.4.2, 3.11, 3.12.8, 4.2.8, 7.1.1, 7.1.2, 7.1.3, |
| 11.5 | 7.3, 9.3.1.1 |
| Claims, Definition of | Construction Schedules, Contractor's |
| 15.1.1 | 3.10, 3.11, 3.12.1, 3.12.2, 6.1.3, 15.1.6.2 |
| Claims, Notice of | Contingent Assignment of Subcontracts |
| 1.6.2, 15.1.3 | 5.4, 14.2.2.2 |
| CLAIMS AND DISPUTES | Continuing Contract Performance |
| 3.2.4, 6.1.1, 6.3, 7.3.9, 9.3.3, 9.10.4, 10.3.3, 15, 15.4 | 15.1.4 |
| Claims and Timely Assertion of Claims | Contract, Definition of |
| 15.4.1 | 1.1.2 |
| Claims for Additional Cost | CONTRACT, TERMINATION OR SUSPENSION |
| 3.2.4, 3.3.1, 3.7.4, 7.3.9, 9.5.2, 10.2.5, 10.3.2, 15.1.5 | OF THE |
| Claims for Additional Time | 5.4.1.1, 5.4.2, 11.5, 14 |
| 3.2.4, 3.3.1, 3.7.4, 6.1.1, 8.3.2, 9.5.2, 10.3.2, 15.1.6 | Contract Administration |
| Concealed or Unknown Conditions, Claims for | 3.1.3, 4, 9.4, 9.5 |
| 3.7.4 | Contract Award and Execution, Conditions Relating |
| Claims for Damages | to |
| 3.2.4, 3.18, 8.3.3, 9.5.1, 9.6.7, 10.2.5, 10.3.3, 11.3, | 3.7.1, 3.10, 5.2, 6.1 |
| 11.3.2, 14.2.4, 15.1.7 | Contract Documents, Copies Furnished and Use of |
| Claims Subject to Arbitration 15.4.1 | 1.5.2, 2.3.6, 5.3 Contract Documents, Definition of |
| Cleaning Up | 1.1.1 |
| 3.15, 6.3 | Contract Sum |
| Commencement of the Work, Conditions Relating to | 2.2.2, 2.2.4, 3.7.4, 3.7.5, 3.8, 3.10.2, 5.2.3, 7.3, 7.4, |
| 2.2.1, 3.2.2, 3.4.1, 3.7.1, 3.10.1, 3.12.6, 5.2.1, 5.2.3, | 9.1, 9.2, 9.4.2, 9.5.1.4, 9.6.7, 9.7, 10.3.2, 11.5, 12.1.2, |
| 6.2.2, 8.1.2, 8.2.2, 8.3.1, 11.1, 11.2, 15.1.5 | 12.3, 14.2.4, 14.3.2, 15.1.4.2, 15.1.5, 15.2.5 |
| Commencement of the Work, Definition of | Contract Sum, Definition of |
| 8.1.2 | 9.1 |
| Communications | Contract Time |
| 3.9.1, 4.2.4 | 1.1.4, 2.2.1, 2.2.2, 3.7.4, 3.7.5, 3.10.2, 5.2.3, 6.1.5, |
| Completion, Conditions Relating to | 7.2.1.3, 7.3.1, 7.3.5, 7.3.6, 7, 7, 7.3.10, 7.4, 8.1.1, |
| 3.4.1, 3.11, 3.15, 4.2.2, 4.2.9, 8.2, 9.4.2, 9.8, 9.9.1, | 8.2.1, 8.2.3, 8.3.1, 9.5.1, 9.7, 10.3.2, 12.1.1, 12.1.2, |
| 9.10, 12.2, 14.1.2, 15.1.2 | 14.3.2, 15.1.4.2, 15.1.6.1, 15.2.5 |
| COMPLETION, PAYMENTS AND | Contract Time, Definition of |
| 9 | 8.1.1 |
| Completion, Substantial | CONTRACTOR |
| 3.10.1, 4.2.9, 8.1.1, 8.1.3, 8.2.3, 9.4.2, 9.8, 9.9.1, | 3 |
| 9.10.3, 12.2, 15.1.2 | Contractor, Definition of |
| Compliance with Laws | 3.1, 6.1.2 |
| 2.3.2, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 10.2.2, | Contractor's Construction and Submittal Schedules |
| 13.1, 13.3, 13.4.1, 13.4.2, 13.5, 14.1.1, 14.2.1.3, | 3.10, 3.12.1, 3.12.2, 4.2.3, 6.1.3, 15.1.6.2 |
| 15.2.8, 15.4.2, 15.4.3 | Contractor's Employees |
| Concealed or Unknown Conditions | |

Init.

AIA Document A201 – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017. All rights reserved. "The American Institute of Architects," "American Institute of Architects," "AIA," the AIA Logo, and "AIA Contract Documents" are trademarks of The American Institute of Architects. This document was produced at 14:57:08 ET on 05/18/2023 under Order No.4104238150 which expires on 12/07/2023, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail docinfo@aiacontracts.com.

3

2.2.4, 3.3.2, 3.4.3, 3.8.1, 3.9, 3.18.2, 4.2.3, 4.2.6, Damage to the Work 3.14.2, 9.9.1, 10.2.1.2, 10.2.5, 10.4, 12.2.4 10.2, 10.3, 11.3, 14.1, 14.2.1.1 Contractor's Liability Insurance Damages, Claims for 3.2.4, 3.18, 6.1.1, 8.3.3, 9.5.1, 9.6.7, 10.3.3, 11.3.2, Contractor's Relationship with Separate Contractors 11.3, 14.2.4, 15.1.7 and Owner's Forces Damages for Delay 3.12.5, 3.14.2, 4.2.4, 6, 11.3, 12.2.4 6.2.3, 8.3.3, 9.5.1.6, 9.7, 10.3.2, 14.3.2 Date of Commencement of the Work, Definition of Contractor's Relationship with Subcontractors 1.2.2, 2.2.4, 3.3.2, 3.18.1, 3.18.2, 4.2.4, 5, 9.6.2, 9.6.7, 9.10.2, 11.2, 11.3, 11.4 Date of Substantial Completion, Definition of Contractor's Relationship with the Architect 8.1.3 Day, Definition of 1.1.2, 1.5, 2.3.3, 3.1.3, 3.2.2, 3.2.3, 3.2.4, 3.3.1, 3.4.2, 3.5.1, 3.7.4, 3.10, 3.11, 3.12, 3.16, 3.18, 4.2, 5.2, 8.1.4 6.2.2, 7, 8.3.1, 9.2, 9.3, 9.4, 9.5, 9.7, 9.8, 9.9, 10.2.6, Decisions of the Architect 10.3, 11.3, 12, 13.4, 15.1.3, 15.2.1 3.7.4, 4.2.6, 4.2.7, 4.2.11, 4.2.12, 4.2.13, 6.3, 7.3.4, Contractor's Representations 7.3.9, 8.1.3, 8.3.1, 9.2, 9.4, 9.5.1, 9.8.4, 9.9.1, 13.4.2, 3.2.1, 3.2.2, 3.5, 3.12.6, 6.2.2, 8.2.1, 9.3.3, 9.8.2 14.2.2, 14.2.4, 15.1, 15.2 Contractor's Responsibility for Those Performing the Decisions to Withhold Certification 9.4.1, 9.5, 9.7, 14.1.1.3 3.3.2, 3.18, 5.3, 6.1.3, 6.2, 9.5.1, 10.2.8 Defective or Nonconforming Work, Acceptance, Contractor's Review of Contract Documents Rejection and Correction of 2.5, 3.5, 4.2.6, 6.2.3, 9.5.1, 9.5.3, 9.6.6, 9.8.2, 9.9.3, Contractor's Right to Stop the Work 9.10.4, 12.2.1 2.2.2, 9.7 **Definitions** Contractor's Right to Terminate the Contract 1.1, 2.1.1, 3.1.1, 3.5, 3.12.1, 3.12.2, 3.12.3, 4.1.1, 5.1, 6.1.2, 7.2.1, 7.3.1, 8.1, 9.1, 9.8.1, 15.1.1 Contractor's Submittals Delays and Extensions of Time 3.10, 3.11, 3.12, 4.2.7, 5.2.1, 5.2.3, 9.2, 9.3, 9.8.2, 3.2, 3.7.4, 5.2.3, 7.2.1, 7.3.1, 7.4, 8.3, 9.5.1, 9.7, 9.8.3, 9.9.1, 9.10.2, 9.10.3 10.3.2, 10.4, 14.3.2, 15.1.6, 15.2.5 Contractor's Superintendent Digital Data Use and Transmission 3.9, 10.2.6 1.7 Contractor's Supervision and Construction Disputes 6.3, 7.3.9, 15.1, 15.2 **Procedures** 1.2.2, 3.3, 3.4, 3.12.10, 4.2.2, 4.2.7, 6.1.3, 6.2.4, Documents and Samples at the Site 7.1.3, 7.3.4, 7.3.6, 8.2, 10, 12, 14, 15.1.4 3.11 Coordination and Correlation Drawings, Definition of 1.2, 3.2.1, 3.3.1, 3.10, 3.12.6, 6.1.3, 6.2.1 1.1.5 Copies Furnished of Drawings and Specifications Drawings and Specifications, Use and Ownership of 1.5, 2.3.6, 3.11 3.11 Copyrights Effective Date of Insurance 1.5, 3.17 8.2.2 Correction of Work Emergencies 2.5, 3.7.3, 9.4.2, 9.8.2, 9.8.3, 9.9.1, 12.1.2, 12.2, 12.3, 10.4, 14.1.1.2, 15.1.5 15.1.3.1, 15.1.3.2, 15.2.1 Employees, Contractor's Correlation and Intent of the Contract Documents 3.3.2, 3.4.3, 3.8.1, 3.9, 3.18.2, 4.2.3, 4.2.6, 10.2, 1.2 10.3.3, 11.3, 14.1, 14.2.1.1 Cost, Definition of Equipment, Labor, or Materials 7.3.4 1.1.3, 1.1.6, 3.4, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, Costs 4.2.6, 4.2.7, 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 2.5, 3.2.4, 3.7.3, 3.8.2, 3.15.2, 5.4.2, 6.1.1, 6.2.3, 9.10.2, 10.2.1, 10.2.4, 14.2.1.1, 14.2.1.2 7.3.3.3, 7.3.4, 7.3.8, 7.3.9, 9.10.2, 10.3.2, 10.3.6, Execution and Progress of the Work 11.2, 12.1.2, 12.2.1, 12.2.4, 13.4, 14 1.1.3, 1.2.1, 1.2.2, 2.3.4, 2.3.6, 3.1, 3.3.1, 3.4.1, 3.7.1,**Cutting and Patching** 3.10.1, 3.12, 3.14, 4.2, 6.2.2, 7.1.3, 7.3.6, 8.2, 9.5.1, 9.9.1, 10.2, 10.3, 12.1, 12.2, 14.2, 14.3.1, 15.1.4 3.14, 6.2.5 Damage to Construction of Owner or Separate Extensions of Time 3.2.4, 3.7.4, 5.2.3, 7.2.1, 7.3, 7.4, 9.5.1, 9.7, 10.3.2, Contractors 3.14.2, 6.2.4, 10.2.1.2, 10.2.5, 10.4, 12.2.4 10.4, 14.3, 15.1.6, 15.2.5

Init.

AlA Document A201 – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017. All rights reserved. "The American Institute of Architects," "American Institute of Architects," "AlA," the AlA Logo, and "AlA Contract Documents" are trademarks of The American Institute of Architects. This document was produced at 14:57:08 ET on 05/18/2023 under Order No.4104238150 which expires on 12/07/2023, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AlA Contract Documents® Terms of Service. To report copyright violations, e-mail docinfo@aiacontracts.com.

| Fai | lure of Payment | INSURANCE AND BONDS |
|------|--|---|
| 9.5 | .1.3, 9.7, 9.10.2, 13.5, 14.1.1.3, 14.2.1.2 | 11 |
| | ılty Work | Insurance Companies, Consent to Partial Occupancy |
| | e Defective or Nonconforming Work) | 9.9.1 |
| | al Completion and Final Payment | Insured loss, Adjustment and Settlement of |
| | .1, 4.2.9, 9.8.2, 9.10, 12.3, 14.2.4, 14.4.3 | 11.5 |
| | | - |
| | ancial Arrangements, Owner's | Intent of the Contract Documents |
| | .1, 13.2.2, 14.1.1.4 | 1.2.1, 4.2.7, 4.2.12, 4.2.13 |
| | NERAL PROVISIONS | Interest |
| 1 | | 13.5 |
| Go | verning Law | Interpretation |
| 13. | 1 | 1.1.8, 1.2.3, 1.4, 4.1.1, 5.1, 6.1.2, 15.1.1 |
| Gua | arantees (See Warranty) | Interpretations, Written |
| Haz | zardous Materials and Substances | 4.2.11, 4.2.12 |
| 10. | 2.4, 10.3 | Judgment on Final Award |
| | ntification of Subcontractors and Suppliers | 15.4.2 |
| 5.2 | * * | Labor and Materials, Equipment |
| - | emnification | 1.1.3, 1.1.6, 3.4, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, |
| | 7, 3.18, 9.6.8, 9.10.2, 10.3.3, 11.3 | 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, 10.2.1, |
| | | 10.2.4, 14.2.1.1, 14.2.1.2 |
| | ormation and Services Required of the Owner | |
| | .2, 2.2, 2.3, 3.2.2, 3.12.10.1, 6.1.3, 6.1.4, 6.2.5, | Labor Disputes |
| | .1, 9.9.2, 9.10.3, 10.3.3, 11.2, 13.4.1, 13.4.2, | 8.3.1 |
| | 1.1.4, 14.1.4, 15.1.4 | Laws and Regulations |
| | ial Decision | 1.5, 2.3.2, 3.2.3, 3.2.4, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, |
| 15. | | 9.9.1, 10.2.2, 13.1, 13.3.1, 13.4.2, 13.5, 14, 15.2.8, |
| Init | ial Decision Maker, Definition of | 15.4 |
| 1.1. | .8 | Liens |
| Init | ial Decision Maker, Decisions | 2.1.2, 9.3.1, 9.3.3, 9.6.8, 9.10.2, 9.10.4, 15.2.8 |
| 14. | 2.4, 15.1.4.2, 15.2.1, 15.2.2, 15.2.3, 15.2.4, 15.2.5 | Limitations, Statutes of |
| | ial Decision Maker, Extent of Authority | 12.2.5, 15.1.2, 15.4.1.1 |
| | 2.4, 15.1.4.2, 15.2.1, 15.2.2, 15.2.3, 15.2.4, 15.2.5 | Limitations of Liability |
| | ary or Damage to Person or Property | 3.2.2, 3.5, 3.12.10, 3.12.10.1, 3.17, 3.18.1, 4.2.6, |
| | 2.8, 10.4 | 4.2.7, 6.2.2, 9.4.2, 9.6.4, 9.6.7, 9.6.8, 10.2.5, 10.3.3, |
| | pections | 11.3, 12.2.5, 13.3.1 |
| | 3, 3.3.3, 3.7.1, 4.2.2, 4.2.6, 4.2.9, 9.4.2, 9.8.3, | Limitations of Time |
| | | |
| | .2, 9.10.1, 12.2.1, 13.4 | 2.1.2, 2.2, 2.5, 3.2.2, 3.10, 3.11, 3.12.5, 3.15.1, 4.2.7, |
| | tructions to Bidders | 5.2, 5.3, 5.4.1, 6.2.4, 7.3, 7.4, 8.2, 9.2, 9.3.1, 9.3.3, |
| 1.1. | | 9.4.1, 9.5, 9.6, 9.7, 9.8, 9.9, 9.10, 12.2, 13.4, 14, 15, |
| | tructions to the Contractor | 15.1.2, 15.1.3, 15.1.5 |
| | .4, 3.3.1, 3.8.1, 5.2.1, 7, 8.2.2, 12, 13.4.2 | Materials, Hazardous |
| | truments of Service, Definition of | 10.2.4, 10.3 |
| 1.1. | | Materials, Labor, Equipment and |
| | urance | 1.1.3, 1.1.6, 3.4.1, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, |
| 6.1 | .1, 7.3.4, 8.2.2, 9.3.2, 9.8.4, 9.9.1, 9.10.2, 10.2.5, | 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, |
| 11 | | 10.2.1.2, 10.2.4, 14.2.1.1, 14.2.1.2 |
| Ins | urance, Notice of Cancellation or Expiration | Means, Methods, Techniques, Sequences and |
| | 1.4, 11.2.3 | Procedures of Construction |
| | urance, Contractor's Liability | 3.3.1, 3.12.10, 4.2.2, 4.2.7, 9.4.2 |
| 11. | | Mechanic's Lien |
| | urance, Effective Date of | 2.1.2, 9.3.1, 9.3.3, 9.6.8, 9.10.2, 9.10.4, 15.2.8 |
| | 2, 14.4.2 | Mediation |
| | | |
| | urance, Owner's Liability | 8.3.1, 15.1.3.2, 15.2.1, 15.2.5, 15.2.6, 15.3, 15.4.1, |
| 11. | | 15.4.1.1 |
| | urance, Property | Minor Changes in the Work |
| | 2.5, 11.2, 11.4, 11.5 | 1.1.1, 3.4.2, 3.12.8, 4.2.8, 7.1, 7.4 |
| | urance, Stored Materials | MISCELLANEOUS PROVISIONS |
| 9.3 | .2 | 13 |
| | | |

Init.

User Notes:

AIA Document A201 – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017. All rights reserved. "The American Institute of Architects," "American Institute of Architects," "AIA," the AIA Logo, and "AIA Contract Documents" are trademarks of The American Institute of Architects. This document was produced at 14:57:08 ET on 05/18/2023 under Order No.4104238150 which expires on 12/07/2023, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail docinfo@aiacontracts.com.

| Modifications, Definition of | Separate Contracts |
|--|---|
| 1.1.1 | 6.1 |
| Modifications to the Contract | Owner's Right to Stop the Work |
| 1.1.1, 1.1.2, 2.5, 3.11, 4.1.2, 4.2.1, 5.2.3, 7, 8.3.1, 9.7, | 2.4 |
| 10.3.2 | Owner's Right to Suspend the Work |
| Mutual Responsibility 6.2 | 14.3 Owner's Right to Terminate the Contract |
| Nonconforming Work, Acceptance of | 14.2, 14.4 |
| 9.6.6, 9.9.3, 12.3 | Ownership and Use of Drawings, Specifications and |
| Nonconforming Work, Rejection and Correction of | Other Instruments of Service |
| 2.4, 2.5, 3.5, 4.2.6, 6.2.4, 9.5.1, 9.8.2, 9.9.3, 9.10.4, | 1.1.1, 1.1.6, 1.1.7, 1.5, 2.3.6, 3.2.2, 3.11, 3.17, 4.2.12, |
| 12.2 | 5.3 |
| Notice | Partial Occupancy or Use |
| 1.6, 1.6.1, 1.6.2, 2.1.2, 2.2.2., 2.2.3, 2.2.4, 2.5, 3.2.4, | 9.6.6, 9.9 |
| 3.3.1, 3.7.4, 3.7.5, 3.9.2, 3.12.9, 3.12.10, 5.2.1, 7.4, | Patching, Cutting and |
| 8.2.2 9.6.8, 9.7, 9.10.1, 10.2.8, 10.3.2, 11.5, 12.2.2.1, | 3.14, 6.2.5 |
| 13.4.1, 13.4.2, 14.1, 14.2.2, 14.4.2, 15.1.3, 15.1.5, | Patents |
| 15.1.6, 15.4.1 | 3.17 |
| Notice of Cancellation or Expiration of Insurance | Payment, Applications for |
| 11.1.4, 11.2.3 | 4.2.5, 7.3.9, 9.2, 9.3, 9.4, 9.5, 9.6.3, 9.7, 9.8.5, 9.10.1, |
| Notice of Claims | 14.2.3, 14.2.4, 14.4.3 |
| 1.6.2, 2.1.2, 3.7.4, 9.6.8, 10.2.8, 15.1.3, 15.1.5, | Payment, Certificates for |
| 15.1.6, 15.2.8, 15.3.2, 15.4.1 | 4.2.5, 4.2.9, 9.3.3, 9.4, 9.5, 9.6.1, 9.6.6, 9.7, 9.10.1, |
| Notice of Testing and Inspections | 9.10.3, 14.1.1.3, 14.2.4 |
| 13.4.1, 13.4.2 | Payment, Failure of |
| Observations, Contractor's | 9.5.1.3, 9.7, 9.10.2, 13.5, 14.1.1.3, 14.2.1.2 |
| 3.2, 3.7.4 Occupancy | Payment, Final 4.2.1, 4.2.9, 9.10, 12.3, 14.2.4, 14.4.3 |
| 2.3.1, 9.6.6, 9.8 | Payment Bond, Performance Bond and |
| Orders, Written | 7.3.4.4, 9.6.7, 9.10.3, 11.1.2 |
| 1.1.1, 2.4, 3.9.2, 7, 8.2.2, 11.5, 12.1, 12.2.2.1, 13.4.2, | Payments, Progress |
| 14.3.1 | 9.3, 9.6, 9.8.5, 9.10.3, 14.2.3, 15.1.4 |
| OWNER | PAYMENTS AND COMPLETION |
| 2 | 9 |
| Owner, Definition of | Payments to Subcontractors |
| 2.1.1 | 5.4.2, 9.5.1.3, 9.6.2, 9.6.3, 9.6.4, 9.6.7, 14.2.1.2 |
| Owner, Evidence of Financial Arrangements | PCB |
| 2.2 , 13.2.2, 14.1.1.4 | 10.3.1 |
| Owner, Information and Services Required of the | Performance Bond and Payment Bond |
| 2.1.2, 2.2, 2.3, 3.2.2, 3.12.10, 6.1.3, 6.1.4, 6.2.5, | 7.3.4.4, 9.6.7, 9.10.3, 11.1.2 |
| 9.3.2, 9.6.1, 9.6.4, 9.9.2, 9.10.3, 10.3.3, 11.2, 13.4.1, 13.4.2, 14.1.1.4, 14.1.4, 15.1.4 | Permits, Fees, Notices and Compliance with Laws 2.3.1, 3.7, 3.13, 7.3.4.4, 10.2.2 |
| Owner's Authority | PERSONS AND PROPERTY, PROTECTION OF |
| 1.5, 2.1.1, 2.3.32.4, 2.5, 3.4.2, 3.8.1, 3.12.10, 3.14.2, | 10 |
| 4.1.2, 4.2.4, 4.2.9, 5.2.1, 5.2.4, 5.4.1, 6.1, 6.3, 7.2.1, | Polychlorinated Biphenyl |
| 7.3.1, 8.2.2, 8.3.1, 9.3.2, 9.5.1, 9.6.4, 9.9.1, 9.10.2, | 10.3.1 |
| 10.3.2, 11.4, 11.5, 12.2.2, 12.3, 13.2.2, 14.3, 14.4, | Product Data, Definition of |
| 15.2.7 | 3.12.2 |
| Owner's Insurance | Product Data and Samples, Shop Drawings |
| 11.2 | 3.11, 3.12, 4.2.7 |
| Owner's Relationship with Subcontractors | Progress and Completion |
| 1.1.2, 5.2, 5.3, 5.4, 9.6.4, 9.10.2, 14.2.2 | 4.2.2, 8.2, 9.8, 9.9.1, 14.1.4, 15.1.4 |
| Owner's Right to Carry Out the Work | Progress Payments |
| 2.5, 14.2.2 Overnou's Bight to Clean Un | 9.3, 9.6, 9.8.5, 9.10.3, 14.2.3, 15.1.4 |
| Owner's Right to Clean Up 6.3 | Project, Definition of 1.1.4 |
| Owner's Right to Perform Construction and to Award | Project Representatives |
| Owner a regit to refform Construction and to Award | 1 Tojoct Representatives |

Init.

AIA Document A201 – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017. All rights reserved. "The American Institute of Architects," "American Institute of Architects," "AIA," the AIA Logo, and "AIA Contract Documents" are trademarks of The American Institute of Architects. This document was produced at 14:57:08 ET on 05/18/2023 under Order No.4104238150 which expires on 12/07/2023, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail docinfo@aiacontracts.com.

| 4.2.10 | 6.1.1 |
|--|---|
| Property Insurance | Shop Drawings, Definition of |
| 10.2.5, 11.2 | 3.12.1 |
| Proposal Requirements | Shop Drawings, Product Data and Samples |
| 1.1.1 | 3.11, 3.12, 4.2.7 |
| | |
| PROTECTION OF PERSONS AND PROPERTY | Site, Use of |
| 10 | 3.13, 6.1.1, 6.2.1 |
| Regulations and Laws | Site Inspections |
| 1.5, 2.3.2, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 9.9.1, | 3.2.2, 3.3.3, 3.7.1, 3.7.4, 4.2, 9.9.2, 9.4.2, 9.10.1, 13.4 |
| 10.2.2, 13.1, 13.3, 13.4.1, 13.4.2, 13.5, 14, 15.2.8, | Site Visits, Architect's |
| 15.4 | 3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.5.1, 9.9.2, 9.10.1, 13.4 |
| Rejection of Work | Special Inspections and Testing |
| 4.2.6, 12.2.1 | 4.2.6, 12.2.1, 13.4 |
| Releases and Waivers of Liens | Specifications, Definition of |
| 9.3.1, 9.10.2 | 1.1.6 |
| Representations | Specifications |
| 3.2.1, 3.5, 3.12.6, 8.2.1, 9.3.3, 9.4.2, 9.5.1, 9.10.1 | 1.1.1, 1.1.6, 1.2.2, 1.5, 3.12.10, 3.17, 4.2.14 |
| Representatives | Statute of Limitations |
| 2.1.1, 3.1.1, 3.9, 4.1.1, 4.2.10, 13.2.1 | 15.1.2, 15.4.1.1 |
| Responsibility for Those Performing the Work | Stopping the Work |
| 3.3.2, 3.18, 4.2.2, 4.2.3, 5.3, 6.1.3, 6.2, 6.3, 9.5.1, 10 | 2.2.2, 2.4, 9.7, 10.3, 14.1 |
| Retainage | Stored Materials |
| 9.3.1, 9.6.2, 9.8.5, 9.9.1, 9.10.2, 9.10.3 | 6.2.1, 9.3.2, 10.2.1.2, 10.2.4 |
| Review of Contract Documents and Field Conditions | Subcontractor, Definition of |
| by Contractor | 5.1.1 |
| 3.2, 3.12.7, 6.1.3 | SUBCONTRACTORS |
| Review of Contractor's Submittals by Owner and | 5 |
| Architect | Subcontractors, Work by |
| 3.10.1, 3.10.2, 3.11, 3.12, 4.2, 5.2, 6.1.3, 9.2, 9.8.2 | 1.2.2, 3.3.2, 3.12.1, 3.18, 4.2.3, 5.2.3, 5.3, 5.4, |
| Review of Shop Drawings, Product Data and | 9.3.1.2, 9.6.7 |
| Samples by Contractor | Subcontractual Relations |
| 3.12 | 5.3, 5.4, 9.3.1.2, 9.6, 9.10, 10.2.1, 14.1, 14.2.1 |
| Rights and Remedies | Submittals |
| 1.1.2, 2.4, 2.5, 3.5, 3.7.4, 3.15.2, 4.2.6, 5.3, 5.4, 6.1, | 3.10, 3.11, 3.12, 4.2.7, 5.2.1, 5.2.3, 7.3.4, 9.2, 9.3, |
| 6.3, 7.3.1, 8.3, 9.5.1, 9.7, 10.2.5, 10.3, 12.2.1, 12.2.2, | 9.8, 9.9.1, 9.10.2, 9.10.3 |
| 12.2.4, 13.3, 14, 15.4 | Submittal Schedule |
| Royalties, Patents and Copyrights | 3.10.2, 3.12.5, 4.2.7 |
| 3.17 | Subrogation, Waivers of |
| Rules and Notices for Arbitration | 6.1.1, 11.3 |
| 15.4.1 | Substances, Hazardous |
| Safety of Persons and Property | 10.3 |
| 10.2, 10.4 | Substantial Completion |
| Safety Precautions and Programs | 4.2.9, 8.1.1, 8.1.3, 8.2.3, 9.4.2, 9.8, 9.9.1, 9.10.3, |
| 3.3.1, 4.2.2, 4.2.7, 5.3, 10.1, 10.2, 10.4 | 12.2, 15.1.2 |
| Samples, Definition of | Substantial Completion, Definition of |
| 3.12.3 | 9.8.1 |
| Samples, Shop Drawings, Product Data and | Substitution of Subcontractors |
| 3.11, 3.12, 4.2.7 | 5.2.3, 5.2.4 |
| Samples at the Site, Documents and | Substitution of Architect |
| 3.11 | 2.3.3 |
| Schedule of Values | Substitutions of Materials |
| 9.2, 9.3.1 | 3.4.2, 3.5, 7.3.8 |
| Schedules, Construction | Sub-subcontractor, Definition of |
| 3.10, 3.12.1, 3.12.2, 6.1.3, 15.1.6.2 | 5.1.2 |
| Separate Contracts and Contractors | Subsurface Conditions |
| 1.1.4, 3.12.5, 3.14.2, 4.2.4, 4.2.7, 6, 8.3.1, 12.1.2 | 3.7.4 |
| Separate Contractors, Definition of | Successors and Assigns |
| separate Contractors, Denninon of | Successors and Assigns |

Init.

User Notes:

AIA Document A201 – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017. All rights reserved. "The American Institute of Architects," "American Institute of Architects," "AIA," the AIA Logo, and "AIA Contract Documents" are trademarks of The American Institute of Architects. This document was produced at 14:57:08 ET on 05/18/2023 under Order No.4104238150 which expires on 12/07/2023, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail docinfo@aiacontracts.com.

13.2 2.1.2, 2.2, 2.5, 3.2.2, 3.10, 3.11, 3.12.5, 3.15.1, 4.2, Superintendent 5.2, 5.3, 5.4, 6.2.4, 7.3, 7.4, 8.2, 9.2, 9.3.1, 9.3.3, 3.9, 10.2.6 9.4.1, 9.5, 9.6, 9.7, 9.8, 9.9, 9.10, 12.2, 13.4, 14, Supervision and Construction Procedures 15.1.2, 15.1.3, 15.4 1.2.2, 3.3, 3.4, 3.12.10, 4.2.2, 4.2.7, 6.1.3, 6.2.4, Time Limits on Claims 7.1.3, 7.3.4, 8.2, 8.3.1, 9.4.2, 10, 12, 14, 15.1.4 3.7.4, 10.2.8, 15.1.2, 15.1.3 Title to Work Suppliers 1.5, 3.12.1, 4.2.4, 4.2.6, 5.2.1, 9.3, 9.4.2, 9.5.4, 9.6, 9.3.2, 9.3.3 9.10.5, 14.2.1 UNCOVERING AND CORRECTION OF WORK Surety 12 5.4.1.2, 9.6.8, 9.8.5, 9.10.2, 9.10.3, 11.1.2, 14.2.2, Uncovering of Work 15.2.7 12.1 Unforeseen Conditions, Concealed or Unknown Surety, Consent of 9.8.5, 9.10.2, 9.10.3 3.7.4, 8.3.1, 10.3 Surveys **Unit Prices** 1.1.7, 2.3.4 7.3.3.2, 9.1.2 Suspension by the Owner for Convenience Use of Documents 1.1.1, 1.5, 2.3.6, 3.12.6, 5.3 Suspension of the Work Use of Site 3.7.5, 5.4.2, 14.3 3.13, 6.1.1, 6.2.1 Suspension or Termination of the Contract Values, Schedule of 5.4.1.1, 14 9.2, 9.3.1 Waiver of Claims by the Architect **Taxes** 3.6, 3.8.2.1, 7.3.4.4 13.3.2 Termination by the Contractor Waiver of Claims by the Contractor 9.10.5, 13.3.2, 15.1.7 14.1, 15.1.7 Termination by the Owner for Cause Waiver of Claims by the Owner 5.4.1.1, 14.2, 15.1.7 9.9.3, 9.10.3, 9.10.4, 12.2.2.1, 13.3.2, 14.2.4, 15.1.7 Termination by the Owner for Convenience Waiver of Consequential Damages 14.4 14.2.4, 15.1.7 Termination of the Architect Waiver of Liens 9.3, 9.10.2, 9.10.4 Termination of the Contractor Employment Waivers of Subrogation 14.2.2 6.1.1, 11.3 Warranty TERMINATION OR SUSPENSION OF THE 3.5, 4.2.9, 9.3.3, 9.8.4, 9.9.1, 9.10.2, 9.10.4, 12.2.2, CONTRACT 15.1.2 14 Weather Delays Tests and Inspections 8.3, 15.1.6.2 3.1.3, 3.3.3, 3.7.1, 4.2.2, 4.2.6, 4.2.9, 9.4.2, 9.8.3, Work, Definition of 9.9.2, 9.10.1, 10.3.2, 12.2.1, 13.4 1.1.3 TIME Written Consent 8 1.5.2, 3.4.2, 3.7.4, 3.12.8, 3.14.2, 4.1.2, 9.3.2, 9.10.3, Time, Delays and Extensions of 13.2, 13.3.2, 15.4.4.2 3.2.4, 3.7.4, 5.2.3, 7.2.1, 7.3.1, 7.4, 8.3, 9.5.1, 9.7, Written Interpretations 10.3.2, 10.4, 14.3.2, 15.1.6, 15.2.5 4.2.11, 4.2.12

Written Orders

1.1.1, 2.4, 3.9, 7, 8.2.2, 12.1, 12.2, 13.4.2, 14.3.1

(3B9ADA40)

8

User Notes:

Time Limits

ARTICLE 1 GENERAL PROVISIONS

§ 1.1 Basic Definitions

§ 1.1.1 The Contract Documents

The Contract Documents are enumerated in the Agreement between the Owner and Contractor (hereinafter the Agreement) and consist of the Agreement, Conditions of the Contract (General, Supplementary and other Conditions), Drawings, Specifications, Addenda issued prior to execution of the Contract, other documents listed in the Agreement, and Modifications issued after execution of the Contract. A Modification is (1) a written amendment to the Contract signed by both parties, (2) a Change Order, (3) a Construction Change Directive, or (4) a written order for a minor change in the Work issued by the Architect. Unless specifically enumerated in the Agreement, the Contract Documents do not include the advertisement or invitation to bid, Instructions to Bidders, sample forms, other information furnished by the Owner in anticipation of receiving bids or proposals, the Contractor's bid or proposal, or portions of Addenda relating to bidding or proposal requirements.

§ 1.1.2 The Contract

The Contract Documents form the Contract for Construction. The Contract represents the entire and integrated agreement between the parties hereto and supersedes prior negotiations, representations, or agreements, either written or oral. The Contract may be amended or modified only by a Modification. The Contract Documents shall not be construed to create a contractual relationship of any kind (1) between the Contractor and the Architect or the Architect's consultants, (2) between the Owner and a Subcontractor or a Sub-subcontractor, (3) between the Owner and the Architect or the Architect's consultants, or (4) between any persons or entities other than the Owner and the Contractor. The Architect shall, however, be entitled to performance and enforcement of obligations under the Contract intended to facilitate performance of the Architect's duties.

§ 1.1.3 The Work

The term "Work" means the construction and services required by the Contract Documents, whether completed or partially completed, and includes all other labor, materials, equipment, and services provided or to be provided by the Contractor to fulfill the Contractor's obligations. The Work may constitute the whole or a part of the Project.

§ 1.1.4 The Project

The Project is the total construction of which the Work performed under the Contract Documents may be the whole or a part and which may include construction by the Owner and by Separate Contractors.

§ 1.1.5 The Drawings

The Drawings are the graphic and pictorial portions of the Contract Documents showing the design, location and dimensions of the Work, generally including plans, elevations, sections, details, schedules, and diagrams.

§ 1.1.6 The Specifications

The Specifications are that portion of the Contract Documents consisting of the written requirements for materials, equipment, systems, standards and workmanship for the Work, and performance of related services.

§ 1.1.7 Instruments of Service

Instruments of Service are representations, in any medium of expression now known or later developed, of the tangible and intangible creative work performed by the Architect and the Architect's consultants under their respective professional services agreements. Instruments of Service may include, without limitation, studies, surveys, models, sketches, drawings, specifications, and other similar materials.

§ 1.1.8 Initial Decision Maker

The Initial Decision Maker is the person identified in the Agreement to render initial decisions on Claims in accordance with Section 15.2. The Initial Decision Maker shall not show partiality to the Owner or Contractor and shall not be liable for results of interpretations or decisions rendered in good faith.

§ 1.2 Correlation and Intent of the Contract Documents

§ 1.2.1 The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complementary, and what is required by one shall be as binding as if required by all; performance by the Contractor shall be required only to the extent

consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the indicated results.

- § 1.2.1.1 The invalidity of any provision of the Contract Documents shall not invalidate the Contract or its remaining provisions. If it is determined that any provision of the Contract Documents violates any law, or is otherwise invalid or unenforceable, then that provision shall be revised to the extent necessary to make that provision legal and enforceable. In such case the Contract Documents shall be construed, to the fullest extent permitted by law, to give effect to the parties' intentions and purposes in executing the Contract.
- § 1.2.2 Organization of the Specifications into divisions, sections and articles, and arrangement of Drawings shall not control the Contractor in dividing the Work among Subcontractors or in establishing the extent of Work to be performed by any trade.
- § 1.2.3 Unless otherwise stated in the Contract Documents, words that have well-known technical or construction industry meanings are used in the Contract Documents in accordance with such recognized meanings.

§ 1.3 Capitalization

Terms capitalized in these General Conditions include those that are (1) specifically defined, (2) the titles of numbered articles, or (3) the titles of other documents published by the American Institute of Architects.

§ 1.4 Interpretation

In the interest of brevity the Contract Documents frequently omit modifying words such as "all" and "any" and articles such as "the" and "an," but the fact that a modifier or an article is absent from one statement and appears in another is not intended to affect the interpretation of either statement.

§ 1.5 Ownership and Use of Drawings, Specifications, and Other Instruments of Service

- § 1.5.1 The Architect and the Architect's consultants shall be deemed the authors and owners of their respective Instruments of Service, including the Drawings and Specifications, and retain all common law, statutory, and other reserved rights in their Instruments of Service, including copyrights. The Contractor, Subcontractors, Subsubcontractors, and suppliers shall not own or claim a copyright in the Instruments of Service. Submittal or distribution to meet official regulatory requirements or for other purposes in connection with the Project is not to be construed as publication in derogation of the Architect's or Architect's consultants' reserved rights.
- § 1.5.2 The Contractor, Subcontractors, Sub-subcontractors, and suppliers are authorized to use and reproduce the Instruments of Service provided to them, subject to any protocols established pursuant to Sections 1.7 and 1.8, solely and exclusively for execution of the Work. All copies made under this authorization shall bear the copyright notice, if any, shown on the Instruments of Service. The Contractor, Subcontractors, Sub-subcontractors, and suppliers may not use the Instruments of Service on other projects or for additions to the Project outside the scope of the Work without the specific written consent of the Owner, Architect, and the Architect's consultants.

§ 1.6 Notice

User Notes:

- § 1.6.1 Except as otherwise provided in Section 1.6.2, where the Contract Documents require one party to notify or give notice to the other party, such notice shall be provided in writing to the designated representative of the party to whom the notice is addressed and shall be deemed to have been duly served if delivered in person, by mail, by courier, or by electronic transmission if a method for electronic transmission is set forth in the Agreement.
- § 1.6.2 Notice of Claims as provided in Section 15.1.3 shall be provided in writing and shall be deemed to have been duly served only if delivered to the designated representative of the party to whom the notice is addressed by certified or registered mail, or by courier providing proof of delivery.

§ 1.7 Digital Data Use and Transmission

The parties shall agree upon protocols governing the transmission and use of Instruments of Service or any other information or documentation in digital form. The parties will use AIA Document E203TM–2013, Building Information Modeling and Digital Data Exhibit, to establish the protocols for the development, use, transmission, and exchange of digital data.

§ 1.8 Building Information Models Use and Reliance

Any use of, or reliance on, all or a portion of a building information model without agreement to protocols governing the use of, and reliance on, the information contained in the model and without having those protocols set forth in AIA Document E203TM–2013, Building Information Modeling and Digital Data Exhibit, and the requisite AIA Document G202TM–2013, Project Building Information Modeling Protocol Form, shall be at the using or relying party's sole risk and without liability to the other party and its contractors or consultants, the authors of, or contributors to, the building information model, and each of their agents and employees.

ARTICLE 2 OWNER

§ 2.1 General

§ 2.1.1 The Owner is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Owner shall designate in writing a representative who shall have express authority to bind the Owner with respect to all matters requiring the Owner's approval or authorization. Except as otherwise provided in Section 4.2.1, the Architect does not have such authority. The term "Owner" means the Owner or the Owner's authorized representative.

§ 2.1.2 The Owner shall furnish to the Contractor, within fifteen days after receipt of a written request, information necessary and relevant for the Contractor to evaluate, give notice of, or enforce mechanic's lien rights. Such information shall include a correct statement of the record legal title to the property on which the Project is located, usually referred to as the site, and the Owner's interest therein.

§ 2.2 Evidence of the Owner's Financial Arrangements

§ 2.2.1 Prior to commencement of the Work and upon written request by the Contractor, the Owner shall furnish to the Contractor reasonable evidence that the Owner has made financial arrangements to fulfill the Owner's obligations under the Contract. The Contractor shall have no obligation to commence the Work until the Owner provides such evidence. If commencement of the Work is delayed under this Section 2.2.1, the Contract Time shall be extended appropriately.

§ 2.2.2 Following commencement of the Work and upon written request by the Contractor, the Owner shall furnish to the Contractor reasonable evidence that the Owner has made financial arrangements to fulfill the Owner's obligations under the Contract only if (1) the Owner fails to make payments to the Contractor as the Contract Documents require; (2) the Contractor identifies in writing a reasonable concern regarding the Owner's ability to make payment when due; or (3) a change in the Work materially changes the Contract Sum. If the Owner fails to provide such evidence, as required, within fourteen days of the Contractor's request, the Contractor may immediately stop the Work and, in that event, shall notify the Owner that the Work has stopped. However, if the request is made because a change in the Work materially changes the Contract Sum under (3) above, the Contractor may immediately stop only that portion of the Work affected by the change until reasonable evidence is provided. If the Work is stopped under this Section 2.2.2, the Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shutdown, delay and start-up, plus interest as provided in the Contract Documents.

§ 2.2.3 After the Owner furnishes evidence of financial arrangements under this Section 2.2, the Owner shall not materially vary such financial arrangements without prior notice to the Contractor.

§ 2.2.4 Where the Owner has designated information furnished under this Section 2.2 as "confidential," the Contractor shall keep the information confidential and shall not disclose it to any other person. However, the Contractor may disclose "confidential" information, after seven (7) days' notice to the Owner, where disclosure is required by law, including a subpoena or other form of compulsory legal process issued by a court or governmental entity, or by court or arbitrator(s) order. The Contractor may also disclose "confidential" information to its employees, consultants, sureties, Subcontractors and their employees, Sub-subcontractors, and others who need to know the content of such information solely and exclusively for the Project and who agree to maintain the confidentiality of such information.

§ 2.3 Information and Services Required of the Owner

§ 2.3.1 Except for permits and fees that are the responsibility of the Contractor under the Contract Documents, including those required under Section 3.7.1, the Owner shall secure and pay for necessary approvals, easements,

assessments and charges required for construction, use or occupancy of permanent structures or for permanent changes in existing facilities.

- § 2.3.2 The Owner shall retain an architect lawfully licensed to practice architecture, or an entity lawfully practicing architecture, in the jurisdiction where the Project is located. That person or entity is identified as the Architect in the Agreement and is referred to throughout the Contract Documents as if singular in number.
- § 2.3.3 If the employment of the Architect terminates, the Owner shall employ a successor to whom the Contractor has no reasonable objection and whose status under the Contract Documents shall be that of the Architect.
- § 2.3.4 The Owner shall furnish surveys describing physical characteristics, legal limitations and utility locations for the site of the Project, and a legal description of the site. The Contractor shall be entitled to rely on the accuracy of information furnished by the Owner but shall exercise proper precautions relating to the safe performance of the Work.
- § 2.3.5 The Owner shall furnish information or services required of the Owner by the Contract Documents with reasonable promptness. The Owner shall also furnish any other information or services under the Owner's control and relevant to the Contractor's performance of the Work with reasonable promptness after receiving the Contractor's written request for such information or services.
- § 2.3.6 Unless otherwise provided in the Contract Documents, the Owner shall furnish to the Contractor one copy of the Contract Documents for purposes of making reproductions pursuant to Section 1.5.2.

§ 2.4 Owner's Right to Stop the Work

If the Contractor fails to correct Work that is not in accordance with the requirements of the Contract Documents as required by Section 12.2 or repeatedly fails to carry out Work in accordance with the Contract Documents, the Owner may issue a written order to the Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, the right of the Owner to stop the Work shall not give rise to a duty on the part of the Owner to exercise this right for the benefit of the Contractor or any other person or entity, except to the extent required by Section 6.1.3.

§ 2.5 Owner's Right to Carry Out the Work

If the Contractor defaults or neglects to carry out the Work in accordance with the Contract Documents and fails within a ten-day period after receipt of notice from the Owner to commence and continue correction of such default or neglect with diligence and promptness, the Owner may, without prejudice to other remedies the Owner may have, correct such default or neglect. Such action by the Owner and amounts charged to the Contractor are both subject to prior approval of the Architect and the Architect may, pursuant to Section 9.5.1, withhold or nullify a Certificate for Payment in whole or in part, to the extent reasonably necessary to reimburse the Owner for the reasonable cost of correcting such deficiencies, including Owner's expenses and compensation for the Architect's additional services made necessary by such default, neglect, or failure. If current and future payments are not sufficient to cover such amounts, the Contractor shall pay the difference to the Owner. If the Contractor disagrees with the actions of the Owner or the Architect, or the amounts claimed as costs to the Owner, the Contractor may file a Claim pursuant to Article 15.

ARTICLE 3 CONTRACTOR

§ 3.1 General

- § 3.1.1 The Contractor is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Contractor shall be lawfully licensed, if required in the jurisdiction where the Project is located. The Contractor shall designate in writing a representative who shall have express authority to bind the Contractor with respect to all matters under this Contract. The term "Contractor" means the Contractor or the Contractor's authorized representative.
- § 3.1.2 The Contractor shall perform the Work in accordance with the Contract Documents.
- § 3.1.3 The Contractor shall not be relieved of its obligations to perform the Work in accordance with the Contract Documents either by activities or duties of the Architect in the Architect's administration of the Contract, or by tests, inspections or approvals required or performed by persons or entities other than the Contractor.

§ 3.2 Review of Contract Documents and Field Conditions by Contractor

§ 3.2.1 Execution of the Contract by the Contractor is a representation that the Contractor has visited the site, become generally familiar with local conditions under which the Work is to be performed, and correlated personal observations with requirements of the Contract Documents.

§ 3.2.2 Because the Contract Documents are complementary, the Contractor shall, before starting each portion of the Work, carefully study and compare the various Contract Documents relative to that portion of the Work, as well as the information furnished by the Owner pursuant to Section 2.3.4, shall take field measurements of any existing conditions related to that portion of the Work, and shall observe any conditions at the site affecting it. These obligations are for the purpose of facilitating coordination and construction by the Contractor and are not for the purpose of discovering errors, omissions, or inconsistencies in the Contract Documents; however, the Contractor shall promptly report to the Architect any errors, inconsistencies or omissions discovered by or made known to the Contractor as a request for information in such form as the Architect may require. It is recognized that the Contractor's review is made in the Contractor's capacity as a contractor and not as a licensed design professional, unless otherwise specifically provided in the Contract Documents.

§ 3.2.3 The Contractor is not required to ascertain that the Contract Documents are in accordance with applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, but the Contractor shall promptly report to the Architect any nonconformity discovered by or made known to the Contractor as a request for information in such form as the Architect may require.

§ 3.2.4 If the Contractor believes that additional cost or time is involved because of clarifications or instructions the Architect issues in response to the Contractor's notices or requests for information pursuant to Sections 3.2.2 or 3.2.3, the Contractor shall submit Claims as provided in Article 15. If the Contractor fails to perform the obligations of Sections 3.2.2 or 3.2.3, the Contractor shall pay such costs and damages to the Owner, subject to Section 15.1.7, as would have been avoided if the Contractor had performed such obligations. If the Contractor performs those obligations, the Contractor shall not be liable to the Owner or Architect for damages resulting from errors, inconsistencies or omissions in the Contract Documents, for differences between field measurements or conditions and the Contract Documents, or for nonconformities of the Contract Documents to applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities.

§ 3.3 Supervision and Construction Procedures

§ 3.3.1 The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for, and have control over, construction means, methods, techniques, sequences, and procedures, and for coordinating all portions of the Work under the Contract. If the Contract Documents give specific instructions concerning construction means, methods, techniques, sequences, or procedures, the Contractor shall evaluate the jobsite safety thereof and shall be solely responsible for the jobsite safety of such means, methods, techniques, sequences, or procedures. If the Contractor determines that such means, methods, techniques, sequences or procedures may not be safe, the Contractor shall give timely notice to the Owner and Architect, and shall propose alternative means, methods, techniques, sequences, or procedures. The Architect shall evaluate the proposed alternative solely for conformance with the design intent for the completed construction. Unless the Architect objects to the Contractor's proposed alternative, the Contractor shall perform the Work using its alternative means, methods, techniques, sequences, or procedures.

§ 3.3.2 The Contractor shall be responsible to the Owner for acts and omissions of the Contractor's employees, Subcontractors and their agents and employees, and other persons or entities performing portions of the Work for, or on behalf of, the Contractor or any of its Subcontractors.

§ 3.3.3 The Contractor shall be responsible for inspection of portions of Work already performed to determine that such portions are in proper condition to receive subsequent Work.

§ 3.4 Labor and Materials

§ 3.4.1 Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary for proper execution and completion of the Work, whether temporary or permanent and whether or not incorporated or to be incorporated in the Work.

- § 3.4.2 Except in the case of minor changes in the Work approved by the Architect in accordance with Section 3.12.8 or ordered by the Architect in accordance with Section 7.4, the Contractor may make substitutions only with the consent of the Owner, after evaluation by the Architect and in accordance with a Change Order or Construction Change Directive.
- § 3.4.3 The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Work. The Contractor shall not permit employment of unfit persons or persons not properly skilled in tasks assigned to them.

§ 3.5 Warranty

§ 3.5.1 The Contractor warrants to the Owner and Architect that materials and equipment furnished under the Contract will be of good quality and new unless the Contract Documents require or permit otherwise. The Contractor further warrants that the Work will conform to the requirements of the Contract Documents and will be free from defects, except for those inherent in the quality of the Work the Contract Documents require or permit. Work, materials, or equipment not conforming to these requirements may be considered defective. The Contractor's warranty excludes remedy for damage or defect caused by abuse, alterations to the Work not executed by the Contractor, improper or insufficient maintenance, improper operation, or normal wear and tear and normal usage. If required by the Architect, the Contractor shall furnish satisfactory evidence as to the kind and quality of materials and equipment.

§ 3.5.2 All material, equipment, or other special warranties required by the Contract Documents shall be issued in the name of the Owner, or shall be transferable to the Owner, and shall commence in accordance with Section 9.8.4.

§ 3.6 Taxes

The Contractor shall pay sales, consumer, use and similar taxes for the Work provided by the Contractor that are legally enacted when bids are received or negotiations concluded, whether or not yet effective or merely scheduled to go into effect.

§ 3.7 Permits, Fees, Notices and Compliance with Laws

- § 3.7.1 Unless otherwise provided in the Contract Documents, the Contractor shall secure and pay for the building permit as well as for other permits, fees, licenses, and inspections by government agencies necessary for proper execution and completion of the Work that are customarily secured after execution of the Contract and legally required at the time bids are received or negotiations concluded.
- § 3.7.2 The Contractor shall comply with and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities applicable to performance of the Work.
- § 3.7.3 If the Contractor performs Work knowing it to be contrary to applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, the Contractor shall assume appropriate responsibility for such Work and shall bear the costs attributable to correction.

§ 3.7.4 Concealed or Unknown Conditions

If the Contractor encounters conditions at the site that are (1) subsurface or otherwise concealed physical conditions that differ materially from those indicated in the Contract Documents or (2) unknown physical conditions of an unusual nature that differ materially from those ordinarily found to exist and generally recognized as inherent in construction activities of the character provided for in the Contract Documents, the Contractor shall promptly provide notice to the Owner and the Architect before conditions are disturbed and in no event later than 14 days after first observance of the conditions. The Architect will promptly investigate such conditions and, if the Architect determines that they differ materially and cause an increase or decrease in the Contractor's cost of, or time required for, performance of any part of the Work, will recommend that an equitable adjustment be made in the Contract Sum or Contract Time, or both. If the Architect determines that the conditions at the site are not materially different from those indicated in the Contract Documents and that no change in the terms of the Contract is justified, the Architect shall promptly notify the Owner and Contractor, stating the reasons. If either party disputes the Architect's determination or recommendation, that party may submit a Claim as provided in Article 15.

(3B9ADA40)

§ 3.7.5 If, in the course of the Work, the Contractor encounters human remains or recognizes the existence of burial markers, archaeological sites or wetlands not indicated in the Contract Documents, the Contractor shall immediately suspend any operations that would affect them and shall notify the Owner and Architect. Upon receipt of such notice, the Owner shall promptly take any action necessary to obtain governmental authorization required to resume the operations. The Contractor shall continue to suspend such operations until otherwise instructed by the Owner but shall continue with all other operations that do not affect those remains or features. Requests for adjustments in the Contract Sum and Contract Time arising from the existence of such remains or features may be made as provided in Article 15.

§ 3.8 Allowances

§ 3.8.1 The Contractor shall include in the Contract Sum all allowances stated in the Contract Documents. Items covered by allowances shall be supplied for such amounts and by such persons or entities as the Owner may direct, but the Contractor shall not be required to employ persons or entities to whom the Contractor has reasonable objection.

- § 3.8.2 Unless otherwise provided in the Contract Documents,
 - .1 allowances shall cover the cost to the Contractor of materials and equipment delivered at the site and all required taxes, less applicable trade discounts;
 - .2 Contractor's costs for unloading and handling at the site, labor, installation costs, overhead, profit, and other expenses contemplated for stated allowance amounts shall be included in the Contract Sum but not in the allowances; and
 - .3 whenever costs are more than or less than allowances, the Contract Sum shall be adjusted accordingly by Change Order. The amount of the Change Order shall reflect (1) the difference between actual costs and the allowances under Section 3.8.2.1 and (2) changes in Contractor's costs under Section 3.8.2.2.
- § 3.8.3 Materials and equipment under an allowance shall be selected by the Owner with reasonable promptness.

§ 3.9 Superintendent

- § 3.9.1 The Contractor shall employ a competent superintendent and necessary assistants who shall be in attendance at the Project site during performance of the Work. The superintendent shall represent the Contractor, and communications given to the superintendent shall be as binding as if given to the Contractor.
- § 3.9.2 The Contractor, as soon as practicable after award of the Contract, shall notify the Owner and Architect of the name and qualifications of a proposed superintendent. Within 14 days of receipt of the information, the Architect may notify the Contractor, stating whether the Owner or the Architect (1) has reasonable objection to the proposed superintendent or (2) requires additional time for review. Failure of the Architect to provide notice within the 14-day period shall constitute notice of no reasonable objection.
- § 3.9.3 The Contractor shall not employ a proposed superintendent to whom the Owner or Architect has made reasonable and timely objection. The Contractor shall not change the superintendent without the Owner's consent, which shall not unreasonably be withheld or delayed.

§ 3.10 Contractor's Construction and Submittal Schedules

- § 3.10.1 The Contractor, promptly after being awarded the Contract, shall submit for the Owner's and Architect's information a Contractor's construction schedule for the Work. The schedule shall contain detail appropriate for the Project, including (1) the date of commencement of the Work, interim schedule milestone dates, and the date of Substantial Completion; (2) an apportionment of the Work by construction activity; and (3) the time required for completion of each portion of the Work. The schedule shall provide for the orderly progression of the Work to completion and shall not exceed time limits current under the Contract Documents. The schedule shall be revised at appropriate intervals as required by the conditions of the Work and Project.
- § 3.10.2 The Contractor, promptly after being awarded the Contract and thereafter as necessary to maintain a current submittal schedule, shall submit a submittal schedule for the Architect's approval. The Architect's approval shall not be unreasonably delayed or withheld. The submittal schedule shall (1) be coordinated with the Contractor's construction schedule, and (2) allow the Architect reasonable time to review submittals. If the Contractor fails to submit a submittal schedule, or fails to provide submittals in accordance with the approved submittal schedule, the

Contractor shall not be entitled to any increase in Contract Sum or extension of Contract Time based on the time required for review of submittals.

§ 3.10.3 The Contractor shall perform the Work in general accordance with the most recent schedules submitted to the Owner and Architect.

§ 3.11 Documents and Samples at the Site

The Contractor shall make available, at the Project site, the Contract Documents, including Change Orders, Construction Change Directives, and other Modifications, in good order and marked currently to indicate field changes and selections made during construction, and the approved Shop Drawings, Product Data, Samples, and similar required submittals. These shall be in electronic form or paper copy, available to the Architect and Owner, and delivered to the Architect for submittal to the Owner upon completion of the Work as a record of the Work as constructed.

§ 3.12 Shop Drawings, Product Data and Samples

- § 3.12.1 Shop Drawings are drawings, diagrams, schedules, and other data specially prepared for the Work by the Contractor or a Subcontractor, Sub-subcontractor, manufacturer, supplier, or distributor to illustrate some portion of the Work.
- § 3.12.2 Product Data are illustrations, standard schedules, performance charts, instructions, brochures, diagrams, and other information furnished by the Contractor to illustrate materials or equipment for some portion of the Work.
- § 3.12.3 Samples are physical examples that illustrate materials, equipment, or workmanship, and establish standards by which the Work will be judged.
- § 3.12.4 Shop Drawings, Product Data, Samples, and similar submittals are not Contract Documents. Their purpose is to demonstrate how the Contractor proposes to conform to the information given and the design concept expressed in the Contract Documents for those portions of the Work for which the Contract Documents require submittals. Review by the Architect is subject to the limitations of Section 4.2.7. Informational submittals upon which the Architect is not expected to take responsive action may be so identified in the Contract Documents. Submittals that are not required by the Contract Documents may be returned by the Architect without action.
- § 3.12.5 The Contractor shall review for compliance with the Contract Documents, approve, and submit to the Architect, Shop Drawings, Product Data, Samples, and similar submittals required by the Contract Documents, in accordance with the submittal schedule approved by the Architect or, in the absence of an approved submittal schedule, with reasonable promptness and in such sequence as to cause no delay in the Work or in the activities of the Owner or of Separate Contractors.
- § 3.12.6 By submitting Shop Drawings, Product Data, Samples, and similar submittals, the Contractor represents to the Owner and Architect that the Contractor has (1) reviewed and approved them, (2) determined and verified materials, field measurements and field construction criteria related thereto, or will do so, and (3) checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents.
- § 3.12.7 The Contractor shall perform no portion of the Work for which the Contract Documents require submittal and review of Shop Drawings, Product Data, Samples, or similar submittals, until the respective submittal has been approved by the Architect.
- § 3.12.8 The Work shall be in accordance with approved submittals except that the Contractor shall not be relieved of responsibility for deviations from the requirements of the Contract Documents by the Architect's approval of Shop Drawings, Product Data, Samples, or similar submittals, unless the Contractor has specifically notified the Architect of such deviation at the time of submittal and (1) the Architect has given written approval to the specific deviation as a minor change in the Work, or (2) a Change Order or Construction Change Directive has been issued authorizing the deviation. The Contractor shall not be relieved of responsibility for errors or omissions in Shop Drawings, Product Data, Samples, or similar submittals, by the Architect's approval thereof.

- § 3.12.9 The Contractor shall direct specific attention, in writing or on resubmitted Shop Drawings, Product Data, Samples, or similar submittals, to revisions other than those requested by the Architect on previous submittals. In the absence of such notice, the Architect's approval of a resubmission shall not apply to such revisions.
- § 3.12.10 The Contractor shall not be required to provide professional services that constitute the practice of architecture or engineering unless such services are specifically required by the Contract Documents for a portion of the Work or unless the Contractor needs to provide such services in order to carry out the Contractor's responsibilities for construction means, methods, techniques, sequences, and procedures. The Contractor shall not be required to provide professional services in violation of applicable law.
- § 3.12.10.1 If professional design services or certifications by a design professional related to systems, materials, or equipment are specifically required of the Contractor by the Contract Documents, the Owner and the Architect will specify all performance and design criteria that such services must satisfy. The Contractor shall be entitled to rely upon the adequacy and accuracy of the performance and design criteria provided in the Contract Documents. The Contractor shall cause such services or certifications to be provided by an appropriately licensed design professional, whose signature and seal shall appear on all drawings, calculations, specifications, certifications, Shop Drawings, and other submittals prepared by such professional. Shop Drawings, and other submittals related to the Work, designed or certified by such professional, if prepared by others, shall bear such professional's written approval when submitted to the Architect. The Owner and the Architect shall be entitled to rely upon the adequacy and accuracy of the services, certifications, and approvals performed or provided by such design professionals, provided the Owner and Architect have specified to the Contractor the performance and design criteria that such services must satisfy. Pursuant to this Section 3.12.10, the Architect will review and approve or take other appropriate action on submittals only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents.
- § 3.12.10.2 If the Contract Documents require the Contractor's design professional to certify that the Work has been performed in accordance with the design criteria, the Contractor shall furnish such certifications to the Architect at the time and in the form specified by the Architect.

§ 3.13 Use of Site

The Contractor shall confine operations at the site to areas permitted by applicable laws, statutes, ordinances, codes, rules and regulations, lawful orders of public authorities, and the Contract Documents and shall not unreasonably encumber the site with materials or equipment.

§ 3.14 Cutting and Patching

- § 3.14.1 The Contractor shall be responsible for cutting, fitting, or patching required to complete the Work or to make its parts fit together properly. All areas requiring cutting, fitting, or patching shall be restored to the condition existing prior to the cutting, fitting, or patching, unless otherwise required by the Contract Documents.
- § 3.14.2 The Contractor shall not damage or endanger a portion of the Work or fully or partially completed construction of the Owner or Separate Contractors by cutting, patching, or otherwise altering such construction, or by excavation. The Contractor shall not cut or otherwise alter construction by the Owner or a Separate Contractor except with written consent of the Owner and of the Separate Contractor. Consent shall not be unreasonably withheld. The Contractor shall not unreasonably withhold, from the Owner or a Separate Contractor, its consent to cutting or otherwise altering the Work.

§ 3.15 Cleaning Up

- § 3.15.1 The Contractor shall keep the premises and surrounding area free from accumulation of waste materials and rubbish caused by operations under the Contract. At completion of the Work, the Contractor shall remove waste materials, rubbish, the Contractor's tools, construction equipment, machinery, and surplus materials from and about the Project.
- § 3.15.2 If the Contractor fails to clean up as provided in the Contract Documents, the Owner may do so and the Owner shall be entitled to reimbursement from the Contractor.

§ 3.16 Access to Work

The Contractor shall provide the Owner and Architect with access to the Work in preparation and progress wherever located.

§ 3.17 Royalties, Patents and Copyrights

The Contractor shall pay all royalties and license fees. The Contractor shall defend suits or claims for infringement of copyrights and patent rights and shall hold the Owner and Architect harmless from loss on account thereof, but shall not be responsible for defense or loss when a particular design, process, or product of a particular manufacturer or manufacturers is required by the Contract Documents, or where the copyright violations are contained in Drawings, Specifications, or other documents prepared by the Owner or Architect. However, if an infringement of a copyright or patent is discovered by, or made known to, the Contractor, the Contractor shall be responsible for the loss unless the information is promptly furnished to the Architect.

§ 3.18 Indemnification

§ 3.18.1 To the fullest extent permitted by law, the Contractor shall indemnify and hold harmless the Owner, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses, and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work, provided that such claim, damage, loss, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), but only to the extent caused by the negligent acts or omissions of the Contractor, a Subcontractor, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, regardless of whether or not such claim, damage, loss, or expense is caused in part by a party indemnified hereunder. Such obligation shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity that would otherwise exist as to a party or person described in this Section 3.18.

§ 3.18.2 In claims against any person or entity indemnified under this Section 3.18 by an employee of the Contractor, a Subcontractor, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, the indemnification obligation under Section 3.18.1 shall not be limited by a limitation on amount or type of damages, compensation, or benefits payable by or for the Contractor or a Subcontractor under workers' compensation acts, disability benefit acts, or other employee benefit acts.

ARTICLE 4 ARCHITECT

§ 4.1 General

§ 4.1.1 The Architect is the person or entity retained by the Owner pursuant to Section 2.3.2 and identified as such in the Agreement.

§ 4.1.2 Duties, responsibilities, and limitations of authority of the Architect as set forth in the Contract Documents shall not be restricted, modified, or extended without written consent of the Owner, Contractor, and Architect. Consent shall not be unreasonably withheld.

§ 4.2 Administration of the Contract

§ 4.2.1 The Architect will provide administration of the Contract as described in the Contract Documents and will be an Owner's representative during construction until the date the Architect issues the final Certificate for Payment. The Architect will have authority to act on behalf of the Owner only to the extent provided in the Contract Documents.

§ 4.2.2 The Architect will visit the site at intervals appropriate to the stage of construction, or as otherwise agreed with the Owner, to become generally familiar with the progress and quality of the portion of the Work completed, and to determine in general if the Work observed is being performed in a manner indicating that the Work, when fully completed, will be in accordance with the Contract Documents. However, the Architect will not be required to make exhaustive or continuous on-site inspections to check the quality or quantity of the Work. The Architect will not have control over, charge of, or responsibility for the construction means, methods, techniques, sequences or procedures, or for the safety precautions and programs in connection with the Work, since these are solely the Contractor's rights and responsibilities under the Contract Documents.

§ 4.2.3 On the basis of the site visits, the Architect will keep the Owner reasonably informed about the progress and quality of the portion of the Work completed, and promptly report to the Owner (1) known deviations from the

(3B9ADA40)

18

Contract Documents, (2) known deviations from the most recent construction schedule submitted by the Contractor, and (3) defects and deficiencies observed in the Work. The Architect will not be responsible for the Contractor's failure to perform the Work in accordance with the requirements of the Contract Documents. The Architect will not have control over or charge of, and will not be responsible for acts or omissions of, the Contractor, Subcontractors, or their agents or employees, or any other persons or entities performing portions of the Work.

§ 4.2.4 Communications

The Owner and Contractor shall include the Architect in all communications that relate to or affect the Architect's services or professional responsibilities. The Owner shall promptly notify the Architect of the substance of any direct communications between the Owner and the Contractor otherwise relating to the Project. Communications by and with the Architect's consultants shall be through the Architect. Communications by and with Subcontractors and suppliers shall be through the Contractor. Communications by and with Separate Contractors shall be through the Owner. The Contract Documents may specify other communication protocols.

- § 4.2.5 Based on the Architect's evaluations of the Contractor's Applications for Payment, the Architect will review and certify the amounts due the Contractor and will issue Certificates for Payment in such amounts.
- § 4.2.6 The Architect has authority to reject Work that does not conform to the Contract Documents. Whenever the Architect considers it necessary or advisable, the Architect will have authority to require inspection or testing of the Work in accordance with Sections 13.4.2 and 13.4.3, whether or not the Work is fabricated, installed or completed. However, neither this authority of the Architect nor a decision made in good faith either to exercise or not to exercise such authority shall give rise to a duty or responsibility of the Architect to the Contractor, Subcontractors, suppliers, their agents or employees, or other persons or entities performing portions of the Work.
- § 4.2.7 The Architect will review and approve, or take other appropriate action upon, the Contractor's submittals such as Shop Drawings, Product Data, and Samples, but only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents. The Architect's action will be taken in accordance with the submittal schedule approved by the Architect or, in the absence of an approved submittal schedule, with reasonable promptness while allowing sufficient time in the Architect's professional judgment to permit adequate review. Review of such submittals is not conducted for the purpose of determining the accuracy and completeness of other details such as dimensions and quantities, or for substantiating instructions for installation or performance of equipment or systems, all of which remain the responsibility of the Contractor as required by the Contract Documents. The Architect's review of the Contractor's submittals shall not relieve the Contractor of the obligations under Sections 3.3, 3.5, and 3.12. The Architect's review shall not constitute approval of safety precautions or of any construction means, methods, techniques, sequences, or procedures. The Architect's approval of a specific item shall not indicate approval of an assembly of which the item is a component.
- § 4.2.8 The Architect will prepare Change Orders and Construction Change Directives, and may order minor changes in the Work as provided in Section 7.4. The Architect will investigate and make determinations and recommendations regarding concealed and unknown conditions as provided in Section 3.7.4.
- § 4.2.9 The Architect will conduct inspections to determine the date or dates of Substantial Completion and the date of final completion; issue Certificates of Substantial Completion pursuant to Section 9.8; receive and forward to the Owner, for the Owner's review and records, written warranties and related documents required by the Contract and assembled by the Contractor pursuant to Section 9.10; and issue a final Certificate for Payment pursuant to Section 9.10.
- § 4.2.10 If the Owner and Architect agree, the Architect will provide one or more Project representatives to assist in carrying out the Architect's responsibilities at the site. The Owner shall notify the Contractor of any change in the duties, responsibilities and limitations of authority of the Project representatives.
- § 4.2.11 The Architect will interpret and decide matters concerning performance under, and requirements of, the Contract Documents on written request of either the Owner or Contractor. The Architect's response to such requests will be made in writing within any time limits agreed upon or otherwise with reasonable promptness.
- § 4.2.12 Interpretations and decisions of the Architect will be consistent with the intent of, and reasonably inferable from, the Contract Documents and will be in writing or in the form of drawings. When making such interpretations

and decisions, the Architect will endeavor to secure faithful performance by both Owner and Contractor, will not show partiality to either, and will not be liable for results of interpretations or decisions rendered in good faith.

§ 4.2.13 The Architect's decisions on matters relating to aesthetic effect will be final if consistent with the intent expressed in the Contract Documents.

§ 4.2.14 The Architect will review and respond to requests for information about the Contract Documents. The Architect's response to such requests will be made in writing within any time limits agreed upon or otherwise with reasonable promptness. If appropriate, the Architect will prepare and issue supplemental Drawings and Specifications in response to the requests for information.

ARTICLE 5 SUBCONTRACTORS

§ 5.1 Definitions

§ 5.1.1 A Subcontractor is a person or entity who has a direct contract with the Contractor to perform a portion of the Work at the site. The term "Subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Subcontractor or an authorized representative of the Subcontractor. The term "Subcontractor" does not include a Separate Contractor or the subcontractors of a Separate Contractor.

§ 5.1.2 A Sub-subcontractor is a person or entity who has a direct or indirect contract with a Subcontractor to perform a portion of the Work at the site. The term "Sub-subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Sub-subcontractor or an authorized representative of the Sub-subcontractor.

§ 5.2 Award of Subcontracts and Other Contracts for Portions of the Work

§ 5.2.1 Unless otherwise stated in the Contract Documents, the Contractor, as soon as practicable after award of the Contract, shall notify the Owner and Architect of the persons or entities proposed for each principal portion of the Work, including those who are to furnish materials or equipment fabricated to a special design. Within 14 days of receipt of the information, the Architect may notify the Contractor whether the Owner or the Architect (1) has reasonable objection to any such proposed person or entity or (2) requires additional time for review. Failure of the Architect to provide notice within the 14-day period shall constitute notice of no reasonable objection.

§ 5.2.2 The Contractor shall not contract with a proposed person or entity to whom the Owner or Architect has made reasonable and timely objection. The Contractor shall not be required to contract with anyone to whom the Contractor has made reasonable objection.

§ 5.2.3 If the Owner or Architect has reasonable objection to a person or entity proposed by the Contractor, the Contractor shall propose another to whom the Owner or Architect has no reasonable objection. If the proposed but rejected Subcontractor was reasonably capable of performing the Work, the Contract Sum and Contract Time shall be increased or decreased by the difference, if any, occasioned by such change, and an appropriate Change Order shall be issued before commencement of the substitute Subcontractor's Work. However, no increase in the Contract Sum or Contract Time shall be allowed for such change unless the Contractor has acted promptly and responsively in submitting names as required.

§ 5.2.4 The Contractor shall not substitute a Subcontractor, person, or entity for one previously selected if the Owner or Architect makes reasonable objection to such substitution.

§ 5.3 Subcontractual Relations

By appropriate written agreement, the Contractor shall require each Subcontractor, to the extent of the Work to be performed by the Subcontractor, to be bound to the Contractor by terms of the Contract Documents, and to assume toward the Contractor all the obligations and responsibilities, including the responsibility for safety of the Subcontractor's Work that the Contractor, by these Contract Documents, assumes toward the Owner and Architect. Each subcontract agreement shall preserve and protect the rights of the Owner and Architect under the Contract Documents with respect to the Work to be performed by the Subcontractor so that subcontracting thereof will not prejudice such rights, and shall allow to the Subcontractor, unless specifically provided otherwise in the subcontract agreement, the benefit of all rights, remedies, and redress against the Contractor that the Contractor, by the Contract Documents, has against the Owner. Where appropriate, the Contractor shall require each Subcontractor to enter into similar agreements with Sub-subcontractors. The Contractor shall make available to each proposed Subcontractor,

User Notes:

prior to the execution of the subcontract agreement, copies of the Contract Documents to which the Subcontractor will be bound, and, upon written request of the Subcontractor, identify to the Subcontractor terms and conditions of the proposed subcontract agreement that may be at variance with the Contract Documents. Subcontractors will similarly make copies of applicable portions of such documents available to their respective proposed Subsubcontractors.

§ 5.4 Contingent Assignment of Subcontracts

- § 5.4.1 Each subcontract agreement for a portion of the Work is assigned by the Contractor to the Owner, provided that
 - .1 assignment is effective only after termination of the Contract by the Owner for cause pursuant to Section 14.2 and only for those subcontract agreements that the Owner accepts by notifying the Subcontractor and Contractor; and
 - .2 assignment is subject to the prior rights of the surety, if any, obligated under bond relating to the Contract.

When the Owner accepts the assignment of a subcontract agreement, the Owner assumes the Contractor's rights and obligations under the subcontract.

- § 5.4.2 Upon such assignment, if the Work has been suspended for more than 30 days, the Subcontractor's compensation shall be equitably adjusted for increases in cost resulting from the suspension.
- § 5.4.3 Upon assignment to the Owner under this Section 5.4, the Owner may further assign the subcontract to a successor contractor or other entity. If the Owner assigns the subcontract to a successor contractor or other entity, the Owner shall nevertheless remain legally responsible for all of the successor contractor's obligations under the subcontract.

ARTICLE 6 CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

- § 6.1 Owner's Right to Perform Construction and to Award Separate Contracts
- § 6.1.1 The term "Separate Contractor(s)" shall mean other contractors retained by the Owner under separate agreements. The Owner reserves the right to perform construction or operations related to the Project with the Owner's own forces, and with Separate Contractors retained under Conditions of the Contract substantially similar to those of this Contract, including those provisions of the Conditions of the Contract related to insurance and waiver of subrogation.
- § 6.1.2 When separate contracts are awarded for different portions of the Project or other construction or operations on the site, the term "Contractor" in the Contract Documents in each case shall mean the Contractor who executes each separate Owner-Contractor Agreement.
- § 6.1.3 The Owner shall provide for coordination of the activities of the Owner's own forces and of each Separate Contractor with the Work of the Contractor, who shall cooperate with them. The Contractor shall participate with any Separate Contractors and the Owner in reviewing their construction schedules. The Contractor shall make any revisions to its construction schedule deemed necessary after a joint review and mutual agreement. The construction schedules shall then constitute the schedules to be used by the Contractor, Separate Contractors, and the Owner until subsequently revised.
- § 6.1.4 Unless otherwise provided in the Contract Documents, when the Owner performs construction or operations related to the Project with the Owner's own forces or with Separate Contractors, the Owner or its Separate Contractors shall have the same obligations and rights that the Contractor has under the Conditions of the Contract, including, without excluding others, those stated in Article 3, this Article 6, and Articles 10, 11, and 12.

§ 6.2 Mutual Responsibility

- § 6.2.1 The Contractor shall afford the Owner and Separate Contractors reasonable opportunity for introduction and storage of their materials and equipment and performance of their activities, and shall connect and coordinate the Contractor's construction and operations with theirs as required by the Contract Documents.
- § 6.2.2 If part of the Contractor's Work depends for proper execution or results upon construction or operations by the Owner or a Separate Contractor, the Contractor shall, prior to proceeding with that portion of the Work,

User Notes:

promptly notify the Architect of apparent discrepancies or defects in the construction or operations by the Owner or Separate Contractor that would render it unsuitable for proper execution and results of the Contractor's Work. Failure of the Contractor to notify the Architect of apparent discrepancies or defects prior to proceeding with the Work shall constitute an acknowledgment that the Owner's or Separate Contractor's completed or partially completed construction is fit and proper to receive the Contractor's Work. The Contractor shall not be responsible for discrepancies or defects in the construction or operations by the Owner or Separate Contractor that are not apparent.

- § 6.2.3 The Contractor shall reimburse the Owner for costs the Owner incurs that are payable to a Separate Contractor because of the Contractor's delays, improperly timed activities or defective construction. The Owner shall be responsible to the Contractor for costs the Contractor incurs because of a Separate Contractor's delays, improperly timed activities, damage to the Work or defective construction.
- § 6.2.4 The Contractor shall promptly remedy damage that the Contractor wrongfully causes to completed or partially completed construction or to property of the Owner or Separate Contractor as provided in Section 10.2.5.
- **§ 6.2.5** The Owner and each Separate Contractor shall have the same responsibilities for cutting and patching as are described for the Contractor in Section 3.14.

§ 6.3 Owner's Right to Clean Up

If a dispute arises among the Contractor, Separate Contractors, and the Owner as to the responsibility under their respective contracts for maintaining the premises and surrounding area free from waste materials and rubbish, the Owner may clean up and the Architect will allocate the cost among those responsible.

ARTICLE 7 CHANGES IN THE WORK

§ 7.1 General

- § 7.1.1 Changes in the Work may be accomplished after execution of the Contract, and without invalidating the Contract, by Change Order, Construction Change Directive or order for a minor change in the Work, subject to the limitations stated in this Article 7 and elsewhere in the Contract Documents.
- § 7.1.2 A Change Order shall be based upon agreement among the Owner, Contractor, and Architect. A Construction Change Directive requires agreement by the Owner and Architect and may or may not be agreed to by the Contractor. An order for a minor change in the Work may be issued by the Architect alone.
- § 7.1.3 Changes in the Work shall be performed under applicable provisions of the Contract Documents. The Contractor shall proceed promptly with changes in the Work, unless otherwise provided in the Change Order, Construction Change Directive, or order for a minor change in the Work.

§ 7.2 Change Orders

- § 7.2.1 A Change Order is a written instrument prepared by the Architect and signed by the Owner, Contractor, and Architect stating their agreement upon all of the following:
 - .1 The change in the Work;
 - .2 The amount of the adjustment, if any, in the Contract Sum; and
 - .3 The extent of the adjustment, if any, in the Contract Time.

§ 7.3 Construction Change Directives

- § 7.3.1 A Construction Change Directive is a written order prepared by the Architect and signed by the Owner and Architect, directing a change in the Work prior to agreement on adjustment, if any, in the Contract Sum or Contract Time, or both. The Owner may by Construction Change Directive, without invalidating the Contract, order changes in the Work within the general scope of the Contract consisting of additions, deletions, or other revisions, the Contract Sum and Contract Time being adjusted accordingly.
- § 7.3.2 A Construction Change Directive shall be used in the absence of total agreement on the terms of a Change Order.
- § 7.3.3 If the Construction Change Directive provides for an adjustment to the Contract Sum, the adjustment shall be based on one of the following methods:

User Notes:

- .1 Mutual acceptance of a lump sum properly itemized and supported by sufficient substantiating data to permit evaluation;
- .2 Unit prices stated in the Contract Documents or subsequently agreed upon;
- .3 Cost to be determined in a manner agreed upon by the parties and a mutually acceptable fixed or percentage fee; or
- .4 As provided in Section 7.3.4.
- § 7.3.4 If the Contractor does not respond promptly or disagrees with the method for adjustment in the Contract Sum, the Architect shall determine the adjustment on the basis of reasonable expenditures and savings of those performing the Work attributable to the change, including, in case of an increase in the Contract Sum, an amount for overhead and profit as set forth in the Agreement, or if no such amount is set forth in the Agreement, a reasonable amount. In such case, and also under Section 7.3.3.3, the Contractor shall keep and present, in such form as the Architect may prescribe, an itemized accounting together with appropriate supporting data. Unless otherwise provided in the Contract Documents, costs for the purposes of this Section 7.3.4 shall be limited to the following:
 - .1 Costs of labor, including applicable payroll taxes, fringe benefits required by agreement or custom, workers' compensation insurance, and other employee costs approved by the Architect;
 - .2 Costs of materials, supplies, and equipment, including cost of transportation, whether incorporated or consumed:
 - .3 Rental costs of machinery and equipment, exclusive of hand tools, whether rented from the Contractor or others:
 - .4 Costs of premiums for all bonds and insurance, permit fees, and sales, use, or similar taxes, directly related to the change; and
 - .5 Costs of supervision and field office personnel directly attributable to the change.
- § 7.3.5 If the Contractor disagrees with the adjustment in the Contract Time, the Contractor may make a Claim in accordance with applicable provisions of Article 15.
- § 7.3.6 Upon receipt of a Construction Change Directive, the Contractor shall promptly proceed with the change in the Work involved and advise the Architect of the Contractor's agreement or disagreement with the method, if any, provided in the Construction Change Directive for determining the proposed adjustment in the Contract Sum or Contract Time.
- § 7.3.7 A Construction Change Directive signed by the Contractor indicates the Contractor's agreement therewith, including adjustment in Contract Sum and Contract Time or the method for determining them. Such agreement shall be effective immediately and shall be recorded as a Change Order.
- § 7.3.8 The amount of credit to be allowed by the Contractor to the Owner for a deletion or change that results in a net decrease in the Contract Sum shall be actual net cost as confirmed by the Architect. When both additions and credits covering related Work or substitutions are involved in a change, the allowance for overhead and profit shall be figured on the basis of net increase, if any, with respect to that change.
- § 7.3.9 Pending final determination of the total cost of a Construction Change Directive to the Owner, the Contractor may request payment for Work completed under the Construction Change Directive in Applications for Payment. The Architect will make an interim determination for purposes of monthly certification for payment for those costs and certify for payment the amount that the Architect determines, in the Architect's professional judgment, to be reasonably justified. The Architect's interim determination of cost shall adjust the Contract Sum on the same basis as a Change Order, subject to the right of either party to disagree and assert a Claim in accordance with Article 15.
- § 7.3.10 When the Owner and Contractor agree with a determination made by the Architect concerning the adjustments in the Contract Sum and Contract Time, or otherwise reach agreement upon the adjustments, such agreement shall be effective immediately and the Architect will prepare a Change Order. Change Orders may be issued for all or any part of a Construction Change Directive.

§ 7.4 Minor Changes in the Work

The Architect may order minor changes in the Work that are consistent with the intent of the Contract Documents and do not involve an adjustment in the Contract Sum or an extension of the Contract Time. The Architect's order for minor changes shall be in writing. If the Contractor believes that the proposed minor change in the Work will

User Notes:

affect the Contract Sum or Contract Time, the Contractor shall notify the Architect and shall not proceed to implement the change in the Work. If the Contractor performs the Work set forth in the Architect's order for a minor change without prior notice to the Architect that such change will affect the Contract Sum or Contract Time, the Contractor waives any adjustment to the Contract Sum or extension of the Contract Time.

ARTICLE 8 TIME

§ 8.1 Definitions

- § 8.1.1 Unless otherwise provided, Contract Time is the period of time, including authorized adjustments, allotted in the Contract Documents for Substantial Completion of the Work.
- § 8.1.2 The date of commencement of the Work is the date established in the Agreement.
- § 8.1.3 The date of Substantial Completion is the date certified by the Architect in accordance with Section 9.8.
- § 8.1.4 The term "day" as used in the Contract Documents shall mean calendar day unless otherwise specifically defined.

§ 8.2 Progress and Completion

- § 8.2.1 Time limits stated in the Contract Documents are of the essence of the Contract. By executing the Agreement, the Contractor confirms that the Contract Time is a reasonable period for performing the Work.
- § 8.2.2 The Contractor shall not knowingly, except by agreement or instruction of the Owner in writing, commence the Work prior to the effective date of insurance required to be furnished by the Contractor and Owner.
- § 8.2.3 The Contractor shall proceed expeditiously with adequate forces and shall achieve Substantial Completion within the Contract Time.

§ 8.3 Delays and Extensions of Time

- § 8.3.1 If the Contractor is delayed at any time in the commencement or progress of the Work by (1) an act or neglect of the Owner or Architect, of an employee of either, or of a Separate Contractor; (2) by changes ordered in the Work; (3) by labor disputes, fire, unusual delay in deliveries, unavoidable casualties, adverse weather conditions documented in accordance with Section 15.1.6.2, or other causes beyond the Contractor's control; (4) by delay authorized by the Owner pending mediation and binding dispute resolution; or (5) by other causes that the Contractor asserts, and the Architect determines, justify delay, then the Contract Time shall be extended for such reasonable time as the Architect may determine.
- § 8.3.2 Claims relating to time shall be made in accordance with applicable provisions of Article 15.
- § 8.3.3 This Section 8.3 does not preclude recovery of damages for delay by either party under other provisions of the Contract Documents.

ARTICLE 9 PAYMENTS AND COMPLETION

§ 9.1 Contract Sum

- § 9.1.1 The Contract Sum is stated in the Agreement and, including authorized adjustments, is the total amount payable by the Owner to the Contractor for performance of the Work under the Contract Documents.
- § 9.1.2 If unit prices are stated in the Contract Documents or subsequently agreed upon, and if quantities originally contemplated are materially changed so that application of such unit prices to the actual quantities causes substantial inequity to the Owner or Contractor, the applicable unit prices shall be equitably adjusted.

§ 9.2 Schedule of Values

User Notes:

Where the Contract is based on a stipulated sum or Guaranteed Maximum Price, the Contractor shall submit a schedule of values to the Architect before the first Application for Payment, allocating the entire Contract Sum to the various portions of the Work. The schedule of values shall be prepared in the form, and supported by the data to substantiate its accuracy, required by the Architect. This schedule, unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's Applications for Payment. Any changes to the schedule of values shall be submitted to the Architect and supported by such data to substantiate its accuracy as the Architect may require, and

unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's subsequent Applications for Payment.

§ 9.3 Applications for Payment

- § 9.3.1 At least ten days before the date established for each progress payment, the Contractor shall submit to the Architect an itemized Application for Payment prepared in accordance with the schedule of values, if required under Section 9.2, for completed portions of the Work. The application shall be notarized, if required, and supported by all data substantiating the Contractor's right to payment that the Owner or Architect require, such as copies of requisitions, and releases and waivers of liens from Subcontractors and suppliers, and shall reflect retainage if provided for in the Contract Documents.
- § 9.3.1.1 As provided in Section 7.3.9, such applications may include requests for payment on account of changes in the Work that have been properly authorized by Construction Change Directives, or by interim determinations of the Architect, but not yet included in Change Orders.
- § 9.3.1.2 Applications for Payment shall not include requests for payment for portions of the Work for which the Contractor does not intend to pay a Subcontractor or supplier, unless such Work has been performed by others whom the Contractor intends to pay.
- § 9.3.2 Unless otherwise provided in the Contract Documents, payments shall be made on account of materials and equipment delivered and suitably stored at the site for subsequent incorporation in the Work. If approved in advance by the Owner, payment may similarly be made for materials and equipment suitably stored off the site at a location agreed upon in writing. Payment for materials and equipment stored on or off the site shall be conditioned upon compliance by the Contractor with procedures satisfactory to the Owner to establish the Owner's title to such materials and equipment or otherwise protect the Owner's interest, and shall include the costs of applicable insurance, storage, and transportation to the site, for such materials and equipment stored off the site.
- § 9.3.3 The Contractor warrants that title to all Work covered by an Application for Payment will pass to the Owner no later than the time of payment. The Contractor further warrants that upon submittal of an Application for Payment all Work for which Certificates for Payment have been previously issued and payments received from the Owner shall, to the best of the Contractor's knowledge, information, and belief, be free and clear of liens, claims, security interests, or encumbrances, in favor of the Contractor, Subcontractors, suppliers, or other persons or entities that provided labor, materials, and equipment relating to the Work.

§ 9.4 Certificates for Payment

- § 9.4.1 The Architect will, within seven days after receipt of the Contractor's Application for Payment, either (1) issue to the Owner a Certificate for Payment in the full amount of the Application for Payment, with a copy to the Contractor; or (2) issue to the Owner a Certificate for Payment for such amount as the Architect determines is properly due, and notify the Contractor and Owner of the Architect's reasons for withholding certification in part as provided in Section 9.5.1; or (3) withhold certification of the entire Application for Payment, and notify the Contractor and Owner of the Architect's reason for withholding certification in whole as provided in Section 9.5.1.
- § 9.4.2 The issuance of a Certificate for Payment will constitute a representation by the Architect to the Owner, based on the Architect's evaluation of the Work and the data in the Application for Payment, that, to the best of the Architect's knowledge, information, and belief, the Work has progressed to the point indicated, the quality of the Work is in accordance with the Contract Documents, and that the Contractor is entitled to payment in the amount certified. The foregoing representations are subject to an evaluation of the Work for conformance with the Contract Documents upon Substantial Completion, to results of subsequent tests and inspections, to correction of minor deviations from the Contract Documents prior to completion, and to specific qualifications expressed by the Architect. However, the issuance of a Certificate for Payment will not be a representation that the Architect has (1) made exhaustive or continuous on-site inspections to check the quality or quantity of the Work; (2) reviewed construction means, methods, techniques, sequences, or procedures; (3) reviewed copies of requisitions received from Subcontractors and suppliers and other data requested by the Owner to substantiate the Contractor's right to payment; or (4) made examination to ascertain how or for what purpose the Contractor has used money previously paid on account of the Contract Sum.

(3B9ADA40)

§ 9.5 Decisions to Withhold Certification

§ 9.5.1 The Architect may withhold a Certificate for Payment in whole or in part, to the extent reasonably necessary to protect the Owner, if in the Architect's opinion the representations to the Owner required by Section 9.4.2 cannot be made. If the Architect is unable to certify payment in the amount of the Application, the Architect will notify the Contractor and Owner as provided in Section 9.4.1. If the Contractor and Architect cannot agree on a revised amount, the Architect will promptly issue a Certificate for Payment for the amount for which the Architect is able to make such representations to the Owner. The Architect may also withhold a Certificate for Payment or, because of subsequently discovered evidence, may nullify the whole or a part of a Certificate for Payment previously issued, to such extent as may be necessary in the Architect's opinion to protect the Owner from loss for which the Contractor is responsible, including loss resulting from acts and omissions described in Section 3.3.2, because of

- .1 defective Work not remedied;
- .2 third party claims filed or reasonable evidence indicating probable filing of such claims, unless security acceptable to the Owner is provided by the Contractor;
- .3 failure of the Contractor to make payments properly to Subcontractors or suppliers for labor, materials or equipment;
- 4 reasonable evidence that the Work cannot be completed for the unpaid balance of the Contract Sum;
- .5 damage to the Owner or a Separate Contractor;
- .6 reasonable evidence that the Work will not be completed within the Contract Time, and that the unpaid balance would not be adequate to cover actual or liquidated damages for the anticipated delay; or
- .7 repeated failure to carry out the Work in accordance with the Contract Documents.
- § 9.5.2 When either party disputes the Architect's decision regarding a Certificate for Payment under Section 9.5.1, in whole or in part, that party may submit a Claim in accordance with Article 15.
- § 9.5.3 When the reasons for withholding certification are removed, certification will be made for amounts previously withheld.
- § 9.5.4 If the Architect withholds certification for payment under Section 9.5.1.3, the Owner may, at its sole option, issue joint checks to the Contractor and to any Subcontractor or supplier to whom the Contractor failed to make payment for Work properly performed or material or equipment suitably delivered. If the Owner makes payments by joint check, the Owner shall notify the Architect and the Contractor shall reflect such payment on its next Application for Payment.

§ 9.6 Progress Payments

- § 9.6.1 After the Architect has issued a Certificate for Payment, the Owner shall make payment in the manner and within the time provided in the Contract Documents, and shall so notify the Architect.
- § 9.6.2 The Contractor shall pay each Subcontractor, no later than seven days after receipt of payment from the Owner, the amount to which the Subcontractor is entitled, reflecting percentages actually retained from payments to the Contractor on account of the Subcontractor's portion of the Work. The Contractor shall, by appropriate agreement with each Subcontractor, require each Subcontractor to make payments to Sub-subcontractors in a similar manner.
- § 9.6.3 The Architect will, on request, furnish to a Subcontractor, if practicable, information regarding percentages of completion or amounts applied for by the Contractor and action taken thereon by the Architect and Owner on account of portions of the Work done by such Subcontractor.
- § 9.6.4 The Owner has the right to request written evidence from the Contractor that the Contractor has properly paid Subcontractors and suppliers amounts paid by the Owner to the Contractor for subcontracted Work. If the Contractor fails to furnish such evidence within seven days, the Owner shall have the right to contact Subcontractors and suppliers to ascertain whether they have been properly paid. Neither the Owner nor Architect shall have an obligation to pay, or to see to the payment of money to, a Subcontractor or supplier, except as may otherwise be required by law.
- § 9.6.5 The Contractor's payments to suppliers shall be treated in a manner similar to that provided in Sections 9.6.2, 9.6.3 and 9.6.4.

User Notes:

§ 9.6.6 A Certificate for Payment, a progress payment, or partial or entire use or occupancy of the Project by the Owner shall not constitute acceptance of Work not in accordance with the Contract Documents.

§ 9.6.7 Unless the Contractor provides the Owner with a payment bond in the full penal sum of the Contract Sum, payments received by the Contractor for Work properly performed by Subcontractors or provided by suppliers shall be held by the Contractor for those Subcontractors or suppliers who performed Work or furnished materials, or both, under contract with the Contractor for which payment was made by the Owner. Nothing contained herein shall require money to be placed in a separate account and not commingled with money of the Contractor, create any fiduciary liability or tort liability on the part of the Contractor for breach of trust, or entitle any person or entity to an award of punitive damages against the Contractor for breach of the requirements of this provision.

§ 9.6.8 Provided the Owner has fulfilled its payment obligations under the Contract Documents, the Contractor shall defend and indemnify the Owner from all loss, liability, damage or expense, including reasonable attorney's fees and litigation expenses, arising out of any lien claim or other claim for payment by any Subcontractor or supplier of any tier. Upon receipt of notice of a lien claim or other claim for payment, the Owner shall notify the Contractor. If approved by the applicable court, when required, the Contractor may substitute a surety bond for the property against which the lien or other claim for payment has been asserted.

§ 9.7 Failure of Payment

If the Architect does not issue a Certificate for Payment, through no fault of the Contractor, within seven days after receipt of the Contractor's Application for Payment, or if the Owner does not pay the Contractor within seven days after the date established in the Contract Documents, the amount certified by the Architect or awarded by binding dispute resolution, then the Contractor may, upon seven additional days' notice to the Owner and Architect, stop the Work until payment of the amount owing has been received. The Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shutdown, delay and start-up, plus interest as provided for in the Contract Documents.

§ 9.8 Substantial Completion

§ 9.8.1 Substantial Completion is the stage in the progress of the Work when the Work or designated portion thereof is sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work for its intended use.

§ 9.8.2 When the Contractor considers that the Work, or a portion thereof which the Owner agrees to accept separately, is substantially complete, the Contractor shall prepare and submit to the Architect a comprehensive list of items to be completed or corrected prior to final payment. Failure to include an item on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents.

§ 9.8.3 Upon receipt of the Contractor's list, the Architect will make an inspection to determine whether the Work or designated portion thereof is substantially complete. If the Architect's inspection discloses any item, whether or not included on the Contractor's list, which is not sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work or designated portion thereof for its intended use, the Contractor shall, before issuance of the Certificate of Substantial Completion, complete or correct such item upon notification by the Architect. In such case, the Contractor shall then submit a request for another inspection by the Architect to determine Substantial Completion.

§ 9.8.4 When the Work or designated portion thereof is substantially complete, the Architect will prepare a Certificate of Substantial Completion that shall establish the date of Substantial Completion; establish responsibilities of the Owner and Contractor for security, maintenance, heat, utilities, damage to the Work and insurance; and fix the time within which the Contractor shall finish all items on the list accompanying the Certificate. Warranties required by the Contract Documents shall commence on the date of Substantial Completion of the Work or designated portion thereof unless otherwise provided in the Certificate of Substantial Completion.

§ 9.8.5 The Certificate of Substantial Completion shall be submitted to the Owner and Contractor for their written acceptance of responsibilities assigned to them in the Certificate. Upon such acceptance, and consent of surety if any, the Owner shall make payment of retainage applying to the Work or designated portion thereof. Such payment shall be adjusted for Work that is incomplete or not in accordance with the requirements of the Contract Documents.

§ 9.9 Partial Occupancy or Use

§ 9.9.1 The Owner may occupy or use any completed or partially completed portion of the Work at any stage when such portion is designated by separate agreement with the Contractor, provided such occupancy or use is consented to by the insurer and authorized by public authorities having jurisdiction over the Project. Such partial occupancy or use may commence whether or not the portion is substantially complete, provided the Owner and Contractor have accepted in writing the responsibilities assigned to each of them for payments, retainage, if any, security, maintenance, heat, utilities, damage to the Work and insurance, and have agreed in writing concerning the period for correction of the Work and commencement of warranties required by the Contract Documents. When the Contractor considers a portion substantially complete, the Contractor shall prepare and submit a list to the Architect as provided under Section 9.8.2. Consent of the Contractor to partial occupancy or use shall not be unreasonably withheld. The stage of the progress of the Work shall be determined by written agreement between the Owner and Contractor or, if no agreement is reached, by decision of the Architect.

§ 9.9.2 Immediately prior to such partial occupancy or use, the Owner, Contractor, and Architect shall jointly inspect the area to be occupied or portion of the Work to be used in order to determine and record the condition of the Work.

§ 9.9.3 Unless otherwise agreed upon, partial occupancy or use of a portion or portions of the Work shall not constitute acceptance of Work not complying with the requirements of the Contract Documents.

§ 9.10 Final Completion and Final Payment

§ 9.10.1 Upon receipt of the Contractor's notice that the Work is ready for final inspection and acceptance and upon receipt of a final Application for Payment, the Architect will promptly make such inspection. When the Architect finds the Work acceptable under the Contract Documents and the Contract fully performed, the Architect will promptly issue a final Certificate for Payment stating that to the best of the Architect's knowledge, information and belief, and on the basis of the Architect's on-site visits and inspections, the Work has been completed in accordance with the Contract Documents and that the entire balance found to be due the Contractor and noted in the final Certificate is due and payable. The Architect's final Certificate for Payment will constitute a further representation that conditions listed in Section 9.10.2 as precedent to the Contractor's being entitled to final payment have been fulfilled.

§ 9.10.2 Neither final payment nor any remaining retained percentage shall become due until the Contractor submits to the Architect (1) an affidavit that payrolls, bills for materials and equipment, and other indebtedness connected with the Work for which the Owner or the Owner's property might be responsible or encumbered (less amounts withheld by Owner) have been paid or otherwise satisfied, (2) a certificate evidencing that insurance required by the Contract Documents to remain in force after final payment is currently in effect, (3) a written statement that the Contractor knows of no reason that the insurance will not be renewable to cover the period required by the Contract Documents, (4) consent of surety, if any, to final payment, (5) documentation of any special warranties, such as manufacturers' warranties or specific Subcontractor warranties, and (6) if required by the Owner, other data establishing payment or satisfaction of obligations, such as receipts and releases and waivers of liens, claims, security interests, or encumbrances arising out of the Contract, to the extent and in such form as may be designated by the Owner. If a Subcontractor refuses to furnish a release or waiver required by the Owner, the Contractor may furnish a bond satisfactory to the Owner to indemnify the Owner against such lien, claim, security interest, or encumbrance remains unsatisfied after payments are made, the Contractor shall refund to the Owner all money that the Owner may be compelled to pay in discharging the lien, claim, security interest, or encumbrance, including all costs and reasonable attorneys' fees.

§ 9.10.3 If, after Substantial Completion of the Work, final completion thereof is materially delayed through no fault of the Contractor or by issuance of Change Orders affecting final completion, and the Architect so confirms, the Owner shall, upon application by the Contractor and certification by the Architect, and without terminating the Contract, make payment of the balance due for that portion of the Work fully completed, corrected, and accepted. If the remaining balance for Work not fully completed or corrected is less than retainage stipulated in the Contract Documents, and if bonds have been furnished, the written consent of the surety to payment of the balance due for that portion of the Work fully completed and accepted shall be submitted by the Contractor to the Architect prior to certification of such payment. Such payment shall be made under terms and conditions governing final payment, except that it shall not constitute a waiver of Claims.

- § 9.10.4 The making of final payment shall constitute a waiver of Claims by the Owner except those arising from
 - .1 liens, Claims, security interests, or encumbrances arising out of the Contract and unsettled;
 - .2 failure of the Work to comply with the requirements of the Contract Documents;
 - .3 terms of special warranties required by the Contract Documents; or
 - .4 audits performed by the Owner, if permitted by the Contract Documents, after final payment.
- § 9.10.5 Acceptance of final payment by the Contractor, a Subcontractor, or a supplier, shall constitute a waiver of claims by that payee except those previously made in writing and identified by that payee as unsettled at the time of final Application for Payment.

ARTICLE 10 PROTECTION OF PERSONS AND PROPERTY

§ 10.1 Safety Precautions and Programs

The Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Contract.

§ 10.2 Safety of Persons and Property

- § 10.2.1 The Contractor shall take reasonable precautions for safety of, and shall provide reasonable protection to prevent damage, injury, or loss to
 - .1 employees on the Work and other persons who may be affected thereby;
 - .2 the Work and materials and equipment to be incorporated therein, whether in storage on or off the site, under care, custody, or control of the Contractor, a Subcontractor, or a Sub-subcontractor; and
 - .3 other property at the site or adjacent thereto, such as trees, shrubs, lawns, walks, pavements, roadways, structures, and utilities not designated for removal, relocation, or replacement in the course of construction.
- § 10.2.2 The Contractor shall comply with, and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities, bearing on safety of persons or property or their protection from damage, injury, or loss.
- § 10.2.3 The Contractor shall implement, erect, and maintain, as required by existing conditions and performance of the Contract, reasonable safeguards for safety and protection, including posting danger signs and other warnings against hazards; promulgating safety regulations; and notifying the owners and users of adjacent sites and utilities of the safeguards.
- § 10.2.4 When use or storage of explosives or other hazardous materials or equipment, or unusual methods are necessary for execution of the Work, the Contractor shall exercise utmost care and carry on such activities under supervision of properly qualified personnel.
- § 10.2.5 The Contractor shall promptly remedy damage and loss (other than damage or loss insured under property insurance required by the Contract Documents) to property referred to in Sections 10.2.1.2 and 10.2.1.3 caused in whole or in part by the Contractor, a Sub-subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable and for which the Contractor is responsible under Sections 10.2.1.2 and 10.2.1.3. The Contractor may make a Claim for the cost to remedy the damage or loss to the extent such damage or loss is attributable to acts or omissions of the Owner or Architect or anyone directly or indirectly employed by either of them, or by anyone for whose acts either of them may be liable, and not attributable to the fault or negligence of the Contractor. The foregoing obligations of the Contractor are in addition to the Contractor's obligations under Section 3.18.
- § 10.2.6 The Contractor shall designate a responsible member of the Contractor's organization at the site whose duty shall be the prevention of accidents. This person shall be the Contractor's superintendent unless otherwise designated by the Contractor in writing to the Owner and Architect.
- § 10.2.7 The Contractor shall not permit any part of the construction or site to be loaded so as to cause damage or create an unsafe condition.

User Notes:

§ 10.2.8 Injury or Damage to Person or Property

If either party suffers injury or damage to person or property because of an act or omission of the other party, or of others for whose acts such party is legally responsible, notice of the injury or damage, whether or not insured, shall be given to the other party within a reasonable time not exceeding 21 days after discovery. The notice shall provide sufficient detail to enable the other party to investigate the matter.

§ 10.3 Hazardous Materials and Substances

§ 10.3.1 The Contractor is responsible for compliance with any requirements included in the Contract Documents regarding hazardous materials or substances. If the Contractor encounters a hazardous material or substance not addressed in the Contract Documents and if reasonable precautions will be inadequate to prevent foreseeable bodily injury or death to persons resulting from a material or substance, including but not limited to asbestos or polychlorinated biphenyl (PCB), encountered on the site by the Contractor, the Contractor shall, upon recognizing the condition, immediately stop Work in the affected area and notify the Owner and Architect of the condition.

§ 10.3.2 Upon receipt of the Contractor's notice, the Owner shall obtain the services of a licensed laboratory to verify the presence or absence of the material or substance reported by the Contractor and, in the event such material or substance is found to be present, to cause it to be rendered harmless. Unless otherwise required by the Contract Documents, the Owner shall furnish in writing to the Contractor and Architect the names and qualifications of persons or entities who are to perform tests verifying the presence or absence of the material or substance or who are to perform the task of removal or safe containment of the material or substance. The Contractor and the Architect will promptly reply to the Owner in writing stating whether or not either has reasonable objection to the persons or entities proposed by the Owner. If either the Contractor or Architect has an objection to a person or entity proposed by the Owner, the Owner shall propose another to whom the Contractor and the Architect have no reasonable objection. When the material or substance has been rendered harmless, Work in the affected area shall resume upon written agreement of the Owner and Contractor. By Change Order, the Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable additional costs of shutdown, delay, and start-up.

§ 10.3.3 To the fullest extent permitted by law, the Owner shall indemnify and hold harmless the Contractor, Subcontractors, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses, and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work in the affected area if in fact the material or substance presents the risk of bodily injury or death as described in Section 10.3.1 and has not been rendered harmless, provided that such claim, damage, loss, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), except to the extent that such damage, loss, or expense is due to the fault or negligence of the party seeking indemnity.

§ 10.3.4 The Owner shall not be responsible under this Section 10.3 for hazardous materials or substances the Contractor brings to the site unless such materials or substances are required by the Contract Documents. The Owner shall be responsible for hazardous materials or substances required by the Contract Documents, except to the extent of the Contractor's fault or negligence in the use and handling of such materials or substances.

§ 10.3.5 The Contractor shall reimburse the Owner for the cost and expense the Owner incurs (1) for remediation of hazardous materials or substances the Contractor brings to the site and negligently handles, or (2) where the Contractor fails to perform its obligations under Section 10.3.1, except to the extent that the cost and expense are due to the Owner's fault or negligence.

§ 10.3.6 If, without negligence on the part of the Contractor, the Contractor is held liable by a government agency for the cost of remediation of a hazardous material or substance solely by reason of performing Work as required by the Contract Documents, the Owner shall reimburse the Contractor for all cost and expense thereby incurred.

§ 10.4 Emergencies

In an emergency affecting safety of persons or property, the Contractor shall act, at the Contractor's discretion, to prevent threatened damage, injury, or loss. Additional compensation or extension of time claimed by the Contractor on account of an emergency shall be determined as provided in Article 15 and Article 7.

ARTICLE 11 INSURANCE AND BONDS

§ 11.1 Contractor's Insurance and Bonds

§ 11.1.1 The Contractor shall purchase and maintain insurance of the types and limits of liability, containing the endorsements, and subject to the terms and conditions, as described in the Agreement or elsewhere in the Contract Documents. The Contractor shall purchase and maintain the required insurance from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located. The Owner, Architect, and Architect's consultants shall be named as additional insureds under the Contractor's commercial general liability policy or as otherwise described in the Contract Documents.

§ 11.1.2 The Contractor shall provide surety bonds of the types, for such penal sums, and subject to such terms and conditions as required by the Contract Documents. The Contractor shall purchase and maintain the required bonds from a company or companies lawfully authorized to issue surety bonds in the jurisdiction where the Project is located.

§ 11.1.3 Upon the request of any person or entity appearing to be a potential beneficiary of bonds covering payment of obligations arising under the Contract, the Contractor shall promptly furnish a copy of the bonds or shall authorize a copy to be furnished.

§ 11.1.4 Notice of Cancellation or Expiration of Contractor's Required Insurance. Within three (3) business days of the date the Contractor becomes aware of an impending or actual cancellation or expiration of any insurance required by the Contract Documents, the Contractor shall provide notice to the Owner of such impending or actual cancellation or expiration. Upon receipt of notice from the Contractor, the Owner shall, unless the lapse in coverage arises from an act or omission of the Owner, have the right to stop the Work until the lapse in coverage has been cured by the procurement of replacement coverage by the Contractor. The furnishing of notice by the Contractor shall not relieve the Contractor of any contractual obligation to provide any required coverage.

§ 11.2 Owner's Insurance

§ 11.2.1 The Owner shall purchase and maintain insurance of the types and limits of liability, containing the endorsements, and subject to the terms and conditions, as described in the Agreement or elsewhere in the Contract Documents. The Owner shall purchase and maintain the required insurance from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located.

§ 11.2.2 Failure to Purchase Required Property Insurance. If the Owner fails to purchase and maintain the required property insurance, with all of the coverages and in the amounts described in the Agreement or elsewhere in the Contract Documents, the Owner shall inform the Contractor in writing prior to commencement of the Work. Upon receipt of notice from the Owner, the Contractor may delay commencement of the Work and may obtain insurance that will protect the interests of the Contractor, Subcontractors, and Sub-Subcontractors in the Work. When the failure to provide coverage has been cured or resolved, the Contract Sum and Contract Time shall be equitably adjusted. In the event the Owner fails to procure coverage, the Owner waives all rights against the Contractor, Subcontractors, and Sub-subcontractors to the extent the loss to the Owner would have been covered by the insurance to have been procured by the Owner. The cost of the insurance shall be charged to the Owner by a Change Order. If the Owner does not provide written notice, and the Contractor is damaged by the failure or neglect of the Owner to purchase or maintain the required insurance, the Owner shall reimburse the Contractor for all reasonable costs and damages attributable thereto.

§ 11.2.3 Notice of Cancellation or Expiration of Owner's Required Property Insurance. Within three (3) business days of the date the Owner becomes aware of an impending or actual cancellation or expiration of any property insurance required by the Contract Documents, the Owner shall provide notice to the Contractor of such impending or actual cancellation or expiration. Unless the lapse in coverage arises from an act or omission of the Contractor: (1) the Contractor, upon receipt of notice from the Owner, shall have the right to stop the Work until the lapse in coverage has been cured by the procurement of replacement coverage by either the Owner or the Contractor; (2) the Contract Time and Contract Sum shall be equitably adjusted; and (3) the Owner waives all rights against the Contractor, Subcontractors, and Sub-subcontractors to the extent any loss to the Owner would have been covered by the insurance had it not expired or been cancelled. If the Contractor purchases replacement coverage, the cost of the insurance shall be charged to the Owner by an appropriate Change Order. The furnishing of notice by the Owner shall not relieve the Owner of any contractual obligation to provide required insurance.

(3B9ADA40)

§ 11.3 Waivers of Subrogation

§ 11.3.1 The Owner and Contractor waive all rights against (1) each other and any of their subcontractors, subsubcontractors, agents, and employees, each of the other; (2) the Architect and Architect's consultants; and (3) Separate Contractors, if any, and any of their subcontractors, sub-subcontractors, agents, and employees, for damages caused by fire, or other causes of loss, to the extent those losses are covered by property insurance required by the Agreement or other property insurance applicable to the Project, except such rights as they have to proceeds of such insurance. The Owner or Contractor, as appropriate, shall require similar written waivers in favor of the individuals and entities identified above from the Architect, Architect's consultants, Separate Contractors, subcontractors, and sub-subcontractors. The policies of insurance purchased and maintained by each person or entity agreeing to waive claims pursuant to this section 11.3.1 shall not prohibit this waiver of subrogation. This waiver of subrogation shall be effective as to a person or entity (1) even though that person or entity would otherwise have a duty of indemnification, contractual or otherwise, (2) even though that person or entity did not pay the insurance premium directly or indirectly, or (3) whether or not the person or entity had an insurable interest in the damaged property.

§ 11.3.2 If during the Project construction period the Owner insures properties, real or personal or both, at or adjacent to the site by property insurance under policies separate from those insuring the Project, or if after final payment property insurance is to be provided on the completed Project through a policy or policies other than those insuring the Project during the construction period, to the extent permissible by such policies, the Owner waives all rights in accordance with the terms of Section 11.3.1 for damages caused by fire or other causes of loss covered by this separate property insurance.

§ 11.4 Loss of Use, Business Interruption, and Delay in Completion Insurance

The Owner, at the Owner's option, may purchase and maintain insurance that will protect the Owner against loss of use of the Owner's property, or the inability to conduct normal operations, due to fire or other causes of loss. The Owner waives all rights of action against the Contractor and Architect for loss of use of the Owner's property, due to fire or other hazards however caused.

§11.5 Adjustment and Settlement of Insured Loss

§ 11.5.1 A loss insured under the property insurance required by the Agreement shall be adjusted by the Owner as fiduciary and made payable to the Owner as fiduciary for the insureds, as their interests may appear, subject to requirements of any applicable mortgagee clause and of Section 11.5.2. The Owner shall pay the Architect and Contractor their just shares of insurance proceeds received by the Owner, and by appropriate agreements the Architect and Contractor shall make payments to their consultants and Subcontractors in similar manner.

§ 11.5.2 Prior to settlement of an insured loss, the Owner shall notify the Contractor of the terms of the proposed settlement as well as the proposed allocation of the insurance proceeds. The Contractor shall have 14 days from receipt of notice to object to the proposed settlement or allocation of the proceeds. If the Contractor does not object, the Owner shall settle the loss and the Contractor shall be bound by the settlement and allocation. Upon receipt, the Owner shall deposit the insurance proceeds in a separate account and make the appropriate distributions. Thereafter, if no other agreement is made or the Owner does not terminate the Contract for convenience, the Owner and Contractor shall execute a Change Order for reconstruction of the damaged or destroyed Work in the amount allocated for that purpose. If the Contractor timely objects to either the terms of the proposed settlement or the allocation of the proceeds, the Owner may proceed to settle the insured loss, and any dispute between the Owner and Contractor arising out of the settlement or allocation of the proceeds shall be resolved pursuant to Article 15. Pending resolution of any dispute, the Owner may issue a Construction Change Directive for the reconstruction of the damaged or destroyed Work.

ARTICLE 12 UNCOVERING AND CORRECTION OF WORK

§ 12.1 Uncovering of Work

§ 12.1.1 If a portion of the Work is covered contrary to the Architect's request or to requirements specifically expressed in the Contract Documents, it must, if requested in writing by the Architect, be uncovered for the Architect's examination and be replaced at the Contractor's expense without change in the Contract Time.

§ 12.1.2 If a portion of the Work has been covered that the Architect has not specifically requested to examine prior to its being covered, the Architect may request to see such Work and it shall be uncovered by the Contractor. If such Work is in accordance with the Contract Documents, the Contractor shall be entitled to an equitable adjustment to

Init.

User Notes:

AIA Document A201 – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017. All rights reserved. "The American Institute of Architects," "American Institute of Architects," "AIA," the AIA Logo, and "AIA Contract Documents" are trademarks of The American Institute of Architects. This document was produced at 14:57:08 ET on 05/18/2023 under Order No.4104238150 which expires on 12/07/2023, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail docinfo@aiacontracts.com.

the Contract Sum and Contract Time as may be appropriate. If such Work is not in accordance with the Contract Documents, the costs of uncovering the Work, and the cost of correction, shall be at the Contractor's expense.

§ 12.2 Correction of Work

§ 12.2.1 Before Substantial Completion

The Contractor shall promptly correct Work rejected by the Architect or failing to conform to the requirements of the Contract Documents, discovered before Substantial Completion and whether or not fabricated, installed or completed. Costs of correcting such rejected Work, including additional testing and inspections, the cost of uncovering and replacement, and compensation for the Architect's services and expenses made necessary thereby, shall be at the Contractor's expense.

§ 12.2.2 After Substantial Completion

§ 12.2.2.1 In addition to the Contractor's obligations under Section 3.5, if, within one year after the date of Substantial Completion of the Work or designated portion thereof or after the date for commencement of warranties established under Section 9.9.1, or by terms of any applicable special warranty required by the Contract Documents, any of the Work is found to be not in accordance with the requirements of the Contract Documents, the Contractor shall correct it promptly after receipt of notice from the Owner to do so, unless the Owner has previously given the Contractor a written acceptance of such condition. The Owner shall give such notice promptly after discovery of the condition. During the one-year period for correction of Work, if the Owner fails to notify the Contractor and give the Contractor an opportunity to make the correction, the Owner waives the rights to require correction by the Contractor and to make a claim for breach of warranty. If the Contractor fails to correct nonconforming Work within a reasonable time during that period after receipt of notice from the Owner or Architect, the Owner may correct it in accordance with Section 2.5.

- § 12.2.2.2 The one-year period for correction of Work shall be extended with respect to portions of Work first performed after Substantial Completion by the period of time between Substantial Completion and the actual completion of that portion of the Work.
- § 12.2.2.3 The one-year period for correction of Work shall not be extended by corrective Work performed by the Contractor pursuant to this Section 12.2.
- § 12.2.3 The Contractor shall remove from the site portions of the Work that are not in accordance with the requirements of the Contract Documents and are neither corrected by the Contractor nor accepted by the Owner.
- § 12.2.4 The Contractor shall bear the cost of correcting destroyed or damaged construction of the Owner or Separate Contractors, whether completed or partially completed, caused by the Contractor's correction or removal of Work that is not in accordance with the requirements of the Contract Documents.
- § 12.2.5 Nothing contained in this Section 12.2 shall be construed to establish a period of limitation with respect to other obligations the Contractor has under the Contract Documents. Establishment of the one-year period for correction of Work as described in Section 12.2.2 relates only to the specific obligation of the Contractor to correct the Work, and has no relationship to the time within which the obligation to comply with the Contract Documents may be sought to be enforced, nor to the time within which proceedings may be commenced to establish the Contractor's liability with respect to the Contractor's obligations other than specifically to correct the Work.

§ 12.3 Acceptance of Nonconforming Work

If the Owner prefers to accept Work that is not in accordance with the requirements of the Contract Documents, the Owner may do so instead of requiring its removal and correction, in which case the Contract Sum will be reduced as appropriate and equitable. Such adjustment shall be effected whether or not final payment has been made.

ARTICLE 13 MISCELLANEOUS PROVISIONS

§ 13.1 Governing Law

User Notes:

The Contract shall be governed by the law of the place where the Project is located, excluding that jurisdiction's choice of law rules. If the parties have selected arbitration as the method of binding dispute resolution, the Federal Arbitration Act shall govern Section 15.4.

§ 13.2 Successors and Assigns

§ 13.2.1 The Owner and Contractor respectively bind themselves, their partners, successors, assigns, and legal representatives to covenants, agreements, and obligations contained in the Contract Documents. Except as provided in Section 13.2.2, neither party to the Contract shall assign the Contract as a whole without written consent of the other. If either party attempts to make an assignment without such consent, that party shall nevertheless remain legally responsible for all obligations under the Contract.

§ 13.2.2 The Owner may, without consent of the Contractor, assign the Contract to a lender providing construction financing for the Project, if the lender assumes the Owner's rights and obligations under the Contract Documents. The Contractor shall execute all consents reasonably required to facilitate the assignment.

§ 13.3 Rights and Remedies

§ 13.3.1 Duties and obligations imposed by the Contract Documents and rights and remedies available thereunder shall be in addition to and not a limitation of duties, obligations, rights, and remedies otherwise imposed or available by law.

§ 13.3.2 No action or failure to act by the Owner, Architect, or Contractor shall constitute a waiver of a right or duty afforded them under the Contract, nor shall such action or failure to act constitute approval of or acquiescence in a breach thereunder, except as may be specifically agreed upon in writing.

§ 13.4 Tests and Inspections

§ 13.4.1 Tests, inspections, and approvals of portions of the Work shall be made as required by the Contract Documents and by applicable laws, statutes, ordinances, codes, rules, and regulations or lawful orders of public authorities. Unless otherwise provided, the Contractor shall make arrangements for such tests, inspections, and approvals with an independent testing laboratory or entity acceptable to the Owner, or with the appropriate public authority, and shall bear all related costs of tests, inspections, and approvals. The Contractor shall give the Architect timely notice of when and where tests and inspections are to be made so that the Architect may be present for such procedures. The Owner shall bear costs of tests, inspections, or approvals that do not become requirements until after bids are received or negotiations concluded. The Owner shall directly arrange and pay for tests, inspections, or approvals where building codes or applicable laws or regulations so require.

§ 13.4.2 If the Architect, Owner, or public authorities having jurisdiction determine that portions of the Work require additional testing, inspection, or approval not included under Section 13.4.1, the Architect will, upon written authorization from the Owner, instruct the Contractor to make arrangements for such additional testing, inspection, or approval, by an entity acceptable to the Owner, and the Contractor shall give timely notice to the Architect of when and where tests and inspections are to be made so that the Architect may be present for such procedures. Such costs, except as provided in Section 13.4.3, shall be at the Owner's expense.

§ 13.4.3 If procedures for testing, inspection, or approval under Sections 13.4.1 and 13.4.2 reveal failure of the portions of the Work to comply with requirements established by the Contract Documents, all costs made necessary by such failure, including those of repeated procedures and compensation for the Architect's services and expenses, shall be at the Contractor's expense.

§ 13.4.4 Required certificates of testing, inspection, or approval shall, unless otherwise required by the Contract Documents, be secured by the Contractor and promptly delivered to the Architect.

§ 13.4.5 If the Architect is to observe tests, inspections, or approvals required by the Contract Documents, the Architect will do so promptly and, where practicable, at the normal place of testing.

§ 13.4.6 Tests or inspections conducted pursuant to the Contract Documents shall be made promptly to avoid unreasonable delay in the Work.

§ 13.5 Interest

User Notes:

Payments due and unpaid under the Contract Documents shall bear interest from the date payment is due at the rate the parties agree upon in writing or, in the absence thereof, at the legal rate prevailing from time to time at the place where the Project is located.

(3B9ADA40)

ARTICLE 14 TERMINATION OR SUSPENSION OF THE CONTRACT

§ 14.1 Termination by the Contractor

§ 14.1.1 The Contractor may terminate the Contract if the Work is stopped for a period of 30 consecutive days through no act or fault of the Contractor, a Sub-subcontractor, their agents or employees, or any other persons or entities performing portions of the Work, for any of the following reasons:

- .1 Issuance of an order of a court or other public authority having jurisdiction that requires all Work to be stopped;
- .2 An act of government, such as a declaration of national emergency, that requires all Work to be stopped;
- .3 Because the Architect has not issued a Certificate for Payment and has not notified the Contractor of the reason for withholding certification as provided in Section 9.4.1, or because the Owner has not made payment on a Certificate for Payment within the time stated in the Contract Documents; or
- .4 The Owner has failed to furnish to the Contractor reasonable evidence as required by Section 2.2.

§ 14.1.2 The Contractor may terminate the Contract if, through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, their agents or employees, or any other persons or entities performing portions of the Work, repeated suspensions, delays, or interruptions of the entire Work by the Owner as described in Section 14.3, constitute in the aggregate more than 100 percent of the total number of days scheduled for completion, or 120 days in any 365-day period, whichever is less.

§ 14.1.3 If one of the reasons described in Section 14.1.1 or 14.1.2 exists, the Contractor may, upon seven days' notice to the Owner and Architect, terminate the Contract and recover from the Owner payment for Work executed, as well as reasonable overhead and profit on Work not executed, and costs incurred by reason of such termination.

§ 14.1.4 If the Work is stopped for a period of 60 consecutive days through no act or fault of the Contractor, a Sub-subcontractor, or their agents or employees or any other persons or entities performing portions of the Work because the Owner has repeatedly failed to fulfill the Owner's obligations under the Contract Documents with respect to matters important to the progress of the Work, the Contractor may, upon seven additional days' notice to the Owner and the Architect, terminate the Contract and recover from the Owner as provided in Section 14.1.3.

§ 14.2 Termination by the Owner for Cause

§ 14.2.1 The Owner may terminate the Contract if the Contractor

- .1 repeatedly refuses or fails to supply enough properly skilled workers or proper materials;
- .2 fails to make payment to Subcontractors or suppliers in accordance with the respective agreements between the Contractor and the Subcontractors or suppliers;
- .3 repeatedly disregards applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of a public authority; or
- .4 otherwise is guilty of substantial breach of a provision of the Contract Documents.

§ 14.2.2 When any of the reasons described in Section 14.2.1 exist, and upon certification by the Architect that sufficient cause exists to justify such action, the Owner may, without prejudice to any other rights or remedies of the Owner and after giving the Contractor and the Contractor's surety, if any, seven days' notice, terminate employment of the Contractor and may, subject to any prior rights of the surety:

- .1 Exclude the Contractor from the site and take possession of all materials, equipment, tools, and construction equipment and machinery thereon owned by the Contractor;
- .2 Accept assignment of subcontracts pursuant to Section 5.4; and
- .3 Finish the Work by whatever reasonable method the Owner may deem expedient. Upon written request of the Contractor, the Owner shall furnish to the Contractor a detailed accounting of the costs incurred by the Owner in finishing the Work.

§ 14.2.3 When the Owner terminates the Contract for one of the reasons stated in Section 14.2.1, the Contractor shall not be entitled to receive further payment until the Work is finished.

§ 14.2.4 If the unpaid balance of the Contract Sum exceeds costs of finishing the Work, including compensation for the Architect's services and expenses made necessary thereby, and other damages incurred by the Owner and not expressly waived, such excess shall be paid to the Contractor. If such costs and damages exceed the unpaid balance,

User Notes:

the Contractor shall pay the difference to the Owner. The amount to be paid to the Contractor or Owner, as the case may be, shall be certified by the Initial Decision Maker, upon application, and this obligation for payment shall survive termination of the Contract.

§ 14.3 Suspension by the Owner for Convenience

§ 14.3.1 The Owner may, without cause, order the Contractor in writing to suspend, delay or interrupt the Work, in whole or in part for such period of time as the Owner may determine.

- § 14.3.2 The Contract Sum and Contract Time shall be adjusted for increases in the cost and time caused by suspension, delay, or interruption under Section 14.3.1. Adjustment of the Contract Sum shall include profit. No adjustment shall be made to the extent
 - .1 that performance is, was, or would have been, so suspended, delayed, or interrupted, by another cause for which the Contractor is responsible; or
 - .2 that an equitable adjustment is made or denied under another provision of the Contract.

§ 14.4 Termination by the Owner for Convenience

- § 14.4.1 The Owner may, at any time, terminate the Contract for the Owner's convenience and without cause.
- § 14.4.2 Upon receipt of notice from the Owner of such termination for the Owner's convenience, the Contractor shall
 - .1 cease operations as directed by the Owner in the notice;
 - .2 take actions necessary, or that the Owner may direct, for the protection and preservation of the Work; and
 - .3 except for Work directed to be performed prior to the effective date of termination stated in the notice, terminate all existing subcontracts and purchase orders and enter into no further subcontracts and purchase orders.
- § 14.4.3 In case of such termination for the Owner's convenience, the Owner shall pay the Contractor for Work properly executed; costs incurred by reason of the termination, including costs attributable to termination of Subcontracts; and the termination fee, if any, set forth in the Agreement.

ARTICLE 15 CLAIMS AND DISPUTES

§ 15.1 Claims

§ 15.1.1 Definition

A Claim is a demand or assertion by one of the parties seeking, as a matter of right, payment of money, a change in the Contract Time, or other relief with respect to the terms of the Contract. The term "Claim" also includes other disputes and matters in question between the Owner and Contractor arising out of or relating to the Contract. The responsibility to substantiate Claims shall rest with the party making the Claim. This Section 15.1.1 does not require the Owner to file a Claim in order to impose liquidated damages in accordance with the Contract Documents.

§ 15.1.2 Time Limits on Claims

The Owner and Contractor shall commence all Claims and causes of action against the other and arising out of or related to the Contract, whether in contract, tort, breach of warranty or otherwise, in accordance with the requirements of the binding dispute resolution method selected in the Agreement and within the period specified by applicable law, but in any case not more than 10 years after the date of Substantial Completion of the Work. The Owner and Contractor waive all Claims and causes of action not commenced in accordance with this Section 15.1.2.

§ 15.1.3 Notice of Claims

§ 15.1.3.1 Claims by either the Owner or Contractor, where the condition giving rise to the Claim is first discovered prior to expiration of the period for correction of the Work set forth in Section 12.2.2, shall be initiated by notice to the other party and to the Initial Decision Maker with a copy sent to the Architect, if the Architect is not serving as the Initial Decision Maker. Claims by either party under this Section 15.1.3.1 shall be initiated within 21 days after occurrence of the event giving rise to such Claim or within 21 days after the claimant first recognizes the condition giving rise to the Claim, whichever is later.

§ 15.1.3.2 Claims by either the Owner or Contractor, where the condition giving rise to the Claim is first discovered after expiration of the period for correction of the Work set forth in Section 12.2.2, shall be initiated by notice to the other party. In such event, no decision by the Initial Decision Maker is required.

§ 15.1.4 Continuing Contract Performance

§ 15.1.4.1 Pending final resolution of a Claim, except as otherwise agreed in writing or as provided in Section 9.7 and Article 14, the Contractor shall proceed diligently with performance of the Contract and the Owner shall continue to make payments in accordance with the Contract Documents.

§ 15.1.4.2 The Contract Sum and Contract Time shall be adjusted in accordance with the Initial Decision Maker's decision, subject to the right of either party to proceed in accordance with this Article 15. The Architect will issue Certificates for Payment in accordance with the decision of the Initial Decision Maker.

§ 15.1.5 Claims for Additional Cost

If the Contractor wishes to make a Claim for an increase in the Contract Sum, notice as provided in Section 15.1.3 shall be given before proceeding to execute the portion of the Work that is the subject of the Claim. Prior notice is not required for Claims relating to an emergency endangering life or property arising under Section 10.4.

§ 15.1.6 Claims for Additional Time

§ 15.1.6.1 If the Contractor wishes to make a Claim for an increase in the Contract Time, notice as provided in Section 15.1.3 shall be given. The Contractor's Claim shall include an estimate of cost and of probable effect of delay on progress of the Work. In the case of a continuing delay, only one Claim is necessary.

§ 15.1.6.2 If adverse weather conditions are the basis for a Claim for additional time, such Claim shall be documented by data substantiating that weather conditions were abnormal for the period of time, could not have been reasonably anticipated, and had an adverse effect on the scheduled construction.

§ 15.1.7 Waiver of Claims for Consequential Damages

The Contractor and Owner waive Claims against each other for consequential damages arising out of or relating to this Contract. This mutual waiver includes

- .1 damages incurred by the Owner for rental expenses, for losses of use, income, profit, financing, business and reputation, and for loss of management or employee productivity or of the services of such persons; and
- .2 damages incurred by the Contractor for principal office expenses including the compensation of personnel stationed there, for losses of financing, business and reputation, and for loss of profit, except anticipated profit arising directly from the Work.

This mutual waiver is applicable, without limitation, to all consequential damages due to either party's termination in accordance with Article 14. Nothing contained in this Section 15.1.7 shall be deemed to preclude assessment of liquidated damages, when applicable, in accordance with the requirements of the Contract Documents.

§ 15.2 Initial Decision

§ 15.2.1 Claims, excluding those where the condition giving rise to the Claim is first discovered after expiration of the period for correction of the Work set forth in Section 12.2.2 or arising under Sections 10.3, 10.4, and 11.5, shall be referred to the Initial Decision Maker for initial decision. The Architect will serve as the Initial Decision Maker, unless otherwise indicated in the Agreement. Except for those Claims excluded by this Section 15.2.1, an initial decision shall be required as a condition precedent to mediation of any Claim. If an initial decision has not been rendered within 30 days after the Claim has been referred to the Initial Decision Maker, the party asserting the Claim may demand mediation and binding dispute resolution without a decision having been rendered. Unless the Initial Decision Maker and all affected parties agree, the Initial Decision Maker will not decide disputes between the Contractor and persons or entities other than the Owner.

§ 15.2.2 The Initial Decision Maker will review Claims and within ten days of the receipt of a Claim take one or more of the following actions: (1) request additional supporting data from the claimant or a response with supporting data from the other party, (2) reject the Claim in whole or in part, (3) approve the Claim, (4) suggest a compromise, or (5) advise the parties that the Initial Decision Maker is unable to resolve the Claim if the Initial Decision Maker lacks sufficient information to evaluate the merits of the Claim or if the Initial Decision Maker concludes that, in the

Initial Decision Maker's sole discretion, it would be inappropriate for the Initial Decision Maker to resolve the Claim.

- § 15.2.3 In evaluating Claims, the Initial Decision Maker may, but shall not be obligated to, consult with or seek information from either party or from persons with special knowledge or expertise who may assist the Initial Decision Maker in rendering a decision. The Initial Decision Maker may request the Owner to authorize retention of such persons at the Owner's expense.
- § 15.2.4 If the Initial Decision Maker requests a party to provide a response to a Claim or to furnish additional supporting data, such party shall respond, within ten days after receipt of the request, and shall either (1) provide a response on the requested supporting data, (2) advise the Initial Decision Maker when the response or supporting data will be furnished, or (3) advise the Initial Decision Maker that no supporting data will be furnished. Upon receipt of the response or supporting data, if any, the Initial Decision Maker will either reject or approve the Claim in whole or in part.
- § 15.2.5 The Initial Decision Maker will render an initial decision approving or rejecting the Claim, or indicating that the Initial Decision Maker is unable to resolve the Claim. This initial decision shall (1) be in writing; (2) state the reasons therefor; and (3) notify the parties and the Architect, if the Architect is not serving as the Initial Decision Maker, of any change in the Contract Sum or Contract Time or both. The initial decision shall be final and binding on the parties but subject to mediation and, if the parties fail to resolve their dispute through mediation, to binding dispute resolution.
- § 15.2.6 Either party may file for mediation of an initial decision at any time, subject to the terms of Section 15.2.6.1.
- § 15.2.6.1 Either party may, within 30 days from the date of receipt of an initial decision, demand in writing that the other party file for mediation. If such a demand is made and the party receiving the demand fails to file for mediation within 30 days after receipt thereof, then both parties waive their rights to mediate or pursue binding dispute resolution proceedings with respect to the initial decision.
- § 15.2.7 In the event of a Claim against the Contractor, the Owner may, but is not obligated to, notify the surety, if any, of the nature and amount of the Claim. If the Claim relates to a possibility of a Contractor's default, the Owner may, but is not obligated to, notify the surety and request the surety's assistance in resolving the controversy.
- § 15.2.8 If a Claim relates to or is the subject of a mechanic's lien, the party asserting such Claim may proceed in accordance with applicable law to comply with the lien notice or filing deadlines.

§ 15.3 Mediation

- § 15.3.1 Claims, disputes, or other matters in controversy arising out of or related to the Contract, except those waived as provided for in Sections 9.10.4, 9.10.5, and 15.1.7, shall be subject to mediation as a condition precedent to binding dispute resolution.
- § 15.3.2 The parties shall endeavor to resolve their Claims by mediation which, unless the parties mutually agree otherwise, shall be administered by the American Arbitration Association in accordance with its Construction Industry Mediation Procedures in effect on the date of the Agreement. A request for mediation shall be made in writing, delivered to the other party to the Contract, and filed with the person or entity administering the mediation. The request may be made concurrently with the filing of binding dispute resolution proceedings but, in such event, mediation shall proceed in advance of binding dispute resolution proceedings, which shall be stayed pending mediation for a period of 60 days from the date of filing, unless stayed for a longer period by agreement of the parties or court order. If an arbitration is stayed pursuant to this Section 15.3.2, the parties may nonetheless proceed to the selection of the arbitrator(s) and agree upon a schedule for later proceedings.
- § 15.3.3 Either party may, within 30 days from the date that mediation has been concluded without resolution of the dispute or 60 days after mediation has been demanded without resolution of the dispute, demand in writing that the other party file for binding dispute resolution. If such a demand is made and the party receiving the demand fails to file for binding dispute resolution within 60 days after receipt thereof, then both parties waive their rights to binding dispute resolution proceedings with respect to the initial decision.

§ 15.3.4 The parties shall share the mediator's fee and any filing fees equally. The mediation shall be held in the place where the Project is located, unless another location is mutually agreed upon. Agreements reached in mediation shall be enforceable as settlement agreements in any court having jurisdiction thereof.

§ 15.4 Arbitration

§ 15.4.1 If the parties have selected arbitration as the method for binding dispute resolution in the Agreement, any Claim subject to, but not resolved by, mediation shall be subject to arbitration which, unless the parties mutually agree otherwise, shall be administered by the American Arbitration Association in accordance with its Construction Industry Arbitration Rules in effect on the date of the Agreement. The Arbitration shall be conducted in the place where the Project is located, unless another location is mutually agreed upon. A demand for arbitration shall be made in writing, delivered to the other party to the Contract, and filed with the person or entity administering the arbitration. The party filing a notice of demand for arbitration must assert in the demand all Claims then known to that party on which arbitration is permitted to be demanded.

§ 15.4.1.1 A demand for arbitration shall be made no earlier than concurrently with the filing of a request for mediation, but in no event shall it be made after the date when the institution of legal or equitable proceedings based on the Claim would be barred by the applicable statute of limitations. For statute of limitations purposes, receipt of a written demand for arbitration by the person or entity administering the arbitration shall constitute the institution of legal or equitable proceedings based on the Claim.

§ 15.4.2 The award rendered by the arbitrator or arbitrators shall be final, and judgment may be entered upon it in accordance with applicable law in any court having jurisdiction thereof.

§ 15.4.3 The foregoing agreement to arbitrate and other agreements to arbitrate with an additional person or entity duly consented to by parties to the Agreement, shall be specifically enforceable under applicable law in any court having jurisdiction thereof.

§ 15.4.4 Consolidation or Joinder

§ 15.4.4.1 Subject to the rules of the American Arbitration Association or other applicable arbitration rules, either party may consolidate an arbitration conducted under this Agreement with any other arbitration to which it is a party provided that (1) the arbitration agreement governing the other arbitration permits consolidation, (2) the arbitrations to be consolidated substantially involve common questions of law or fact, and (3) the arbitrations employ materially similar procedural rules and methods for selecting arbitrator(s).

§ 15.4.4.2 Subject to the rules of the American Arbitration Association or other applicable arbitration rules, either party may include by joinder persons or entities substantially involved in a common question of law or fact whose presence is required if complete relief is to be accorded in arbitration, provided that the party sought to be joined consents in writing to such joinder. Consent to arbitration involving an additional person or entity shall not constitute consent to arbitration of any claim, dispute or other matter in question not described in the written consent.

§ 15.4.4.3 The Owner and Contractor grant to any person or entity made a party to an arbitration conducted under this Section 15.4, whether by joinder or consolidation, the same rights of joinder and consolidation as those of the Owner and Contractor under this Agreement.

Payment Bond

| 00 | NITO | A 0.T | OD. | |
|----|------|-------|------|--|
| | NTR | Δ(:Ι | ()K. | |
| | | | | |

SURETY:

(Name, legal status and address)

(Name, legal status and principal place of business)

OWNER:

(Name, legal status and address)
Town of Milton
503 Geyser Road, Ballston Spa, NY 12020

CONSTRUCTION CONTRACT

Date:

Amount: \$ 0.00 Description: (Name and location) Town of Milton

Rowland Street Highway Facility - Cold Storage PEMB

BOND

Date:

(Notearlier than Construction Contract Date)

Amount: \$

Signature:

Modifications to this Bond: None See Section 18

CONTRACTOR AS PRINCIPAL

Company: (Corporate Seal)

SURETY

rporate Seal) Company:

Signature:

Name and

Name and

le: Title:

(Any additional signatures appear on the last page of this Payment Bond.)

(FOR INFORMATION ONLY — Name, address and telephone)

AGENT or **BROKER**:

OWNER'S REPRESENTATIVE:

(Architect, Engineer or other party:)
Scott Ostrander

(Corporate Seal)

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An Additions and Deletions Report that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

(3B9ADA43)

- § 1 The Contractor and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Owner to pay for labor, materials and equipment furnished for use in the performance of the Construction Contract, which is incorporated herein by reference, subject to the following terms.
- § 2 If the Contractor promptly makes payment of all sums due to Claimants, and defends, indemnifies and holds harmless the Owner from claims, demands, liens or suits by any person or entity seeking payment for labor, materials or equipment furnished for use in the performance of the Construction Contract, then the Surety and the Contractor shall have no obligation under this Bond.
- § 3 If there is no Owner Default under the Construction Contract, the Surety's obligation to the Owner under this Bond shall arise after the Owner has promptly notified the Contractor and the Surety (at the address described in Section 13) of claims, demands, liens or suits against the Owner or the Owner's property by any person or entity seeking payment for labor, materials or equipment furnished for use in the performance of the Construction Contract and tendered defense of such claims, demands, liens or suits to the Contractor and the Surety.
- § 4 When the Owner has satisfied the conditions in Section 3, the Surety shall promptly and at the Surety's expense defend, indemnify and hold harmless the Owner against a duly tendered claim, demand, lien or suit.
- § 5 The Surety's obligations to a Claimant under this Bond shall arise after the following:
- § 5.1 Claimants, who do not have a direct contract with the Contractor,
 - have furnished a written notice of non-payment to the Contractor, stating with substantial accuracy the amount claimed and the name of the party to whom the materials were, or equipment was, furnished or supplied or for whom the labor was done or performed, within ninety (90) days after having last performed labor or last furnished materials or equipment included in the Claim; and
 - .2 have sent a Claim to the Surety (at the address described in Section 13).
- § 5.2 Claimants, who are employed by or have a direct contract with the Contractor, have sent a Claim to the Surety (at the address described in Section 13).
- § 6 If a notice of non-payment required by Section 5.1.1 is given by the Owner to the Contractor, that is sufficient to satisfy a Claimant's obligation to furnish a written notice of non-payment under Section 5.1.1.
- § 7 When a Claimant has satisfied the conditions of Sections 5.1 or 5.2, whichever is applicable, the Surety shall promptly and at the Surety's expense take the following actions:
- § 7.1 Send an answer to the Claimant, with a copy to the Owner, within sixty (60) days after receipt of the Claim, stating the amounts that are undisputed and the basis for challenging any amounts that are disputed; and
- § 7.2 Pay or arrange for payment of any undisputed amounts.
- § 7.3 The Surety's failure to discharge its obligations under Section 7.1 or Section 7.2 shall not be deemed to constitute a waiver of defenses the Surety or Contractor may have or acquire as to a Claim, except as to undisputed amounts for which the Surety and Claimant have reached agreement. If, however, the Surety fails to discharge its obligations under Section 7.1 or Section 7.2, the Surety shall indemnify the Claimant for the reasonable attorney's fees the Claimant incurs thereafter to recover any sums found to be due and owing to the Claimant.
- § 8 The Surety's total obligation shall not exceed the amount of this Bond, plus the amount of reasonable attorney's fees provided under Section 7.3, and the amount of this Bond shall be credited for any payments made in good faith by the Surety.
- § 9 Amounts owed by the Owner to the Contractor under the Construction Contract shall be used for the performance of the Construction Contract and to satisfy claims, if any, under any construction performance bond. By the Contractor furnishing and the Owner accepting this Bond, they agree that all funds earned by the Contractor in the performance of the Construction Contract are dedicated to satisfy obligations of the Contractor and Surety under this Bond, subject to the Owner's priority to use the funds for the completion of the work.

- § 10 The Surety shall not be liable to the Owner, Claimants or others for obligations of the Contractor that are unrelated to the Construction Contract. The Owner shall not be liable for the payment of any costs or expenses of any Claimant under this Bond, and shall have under this Bond no obligation to make payments to, or give notice on behalf of, Claimants or otherwise have any obligations to Claimants under this Bond.
- § 11 The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.
- § 12 No suit or action shall be commenced by a Claimant under this Bond other than in a court of competent jurisdiction in the state in which the project that is the subject of the Construction Contract is located or after the expiration of one year from the date (1) on which the Claimant sent a Claim to the Surety pursuant to Section 5.1.2 or 5.2, or (2) on which the last labor or service was performed by anyone or the last materials or equipment were furnished by anyone under the Construction Contract, whichever of (1) or (2) first occurs. If the provisions of this Paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.
- § 13 Notice and Claims to the Surety, the Owner or the Contractor shall be mailed or delivered to the address shown on the page on which their signature appears. Actual receipt of notice or Claims, however accomplished, shall be sufficient compliance as of the date received.
- § 14 When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.
- § 15 Upon request by any person or entity appearing to be a potential beneficiary of this Bond, the Contractor and Owner shall promptly furnish a copy of this Bond or shall permit a copy to be made.

§ 16 Definitions

- § 16.1 Claim. A written statement by the Claimant including at a minimum:
 - .1 the name of the Claimant;
 - .2 the name of the person for whom the labor was done, or materials or equipment furnished;
 - .3 a copy of the agreement or purchase order pursuant to which labor, materials or equipment was furnished for use in the performance of the Construction Contract;
 - .4 a brief description of the labor, materials or equipment furnished;
 - .5 the date on which the Claimant last performed labor or last furnished materials or equipment for use in the performance of the Construction Contract;
 - the total amount earned by the Claimant for labor, materials or equipment furnished as of the date of the Claim:
 - the total amount of previous payments received by the Claimant; and
 - .8 the total amount due and unpaid to the Claimant for labor, materials or equipment furnished as of the date of the Claim.
- § 16.2 Claimant. An individual or entity having a direct contract with the Contractor or with a subcontractor of the Contractor to furnish labor, materials or equipment for use in the performance of the Construction Contract. The term Claimant also includes any individual or entity that has rightfully asserted a claim under an applicable mechanic's lien or similar statute against the real property upon which the Project is located. The intent of this Bond shall be to include without limitation in the terms "labor, materials or equipment" that part of water, gas, power, light, heat, oil, gasoline, telephone service or rental equipment used in the Construction Contract, architectural and engineering services required for performance of the work of the Contractor and the Contractor's subcontractors, and all other items for which a mechanic's lien may be asserted in the jurisdiction where the labor, materials or equipment were furnished.
- § 16.3 Construction Contract. The agreement between the Owner and Contractor identified on the cover page, including all Contract Documents and all changes made to the agreement and the Contract Documents.

§ 16.4 Owner Default. Failure of the Owner, which has not been remedied or waived, to pay the Contractor as required under the Construction Contract or to perform and complete or comply with the other material terms of the Construction Contract.

§ 16.5 Contract Documents. All the documents that comprise the agreement between the Owner and Contractor.

§ 17 If this Bond is issued for an agreement between a Contractor and subcontractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

§ 18 Modifications to this bond are as follows:

| CONTRACTOR AS PRINCIPAL | | SURETY | |
|-------------------------|------------------|-----------------|------------------|
| Company: | (Corporate Seal) | Company: | (Corporate Seal) |
| Signature: | | Signature: | |
| Name and Title: | | Name and Title: | |
| Address: | | Address: | |

Performance Bond

CONTRACTOR:

SURETY:

(Name, legal status and address)

(Name, legal status and principal place of business)

OWNER:

(Name, legal status and address)
Town of Milton
503 Geyser Road, Ballston Spa, NY 12020

CONSTRUCTION CONTRACT

Date:

Amount: \$ 0.00 Description: (Name and location) Town of Milton

Rowland Street Highway Facility - Cold Storage PEMB

BOND

Date:

(Notearlier than Construction Contract Date)

Amount: \$

Modifications to this Bond: None See Section 16

CONTRACTOR AS PRINCIPAL

Company: (Corporate Seal)
Signature:

INCIPAL SURETY
orporate Seal) Company:
Signature:

Nama and

Name and Title:

Name and Title:

(Any additional signatures appear on the last page of this Performance Bond.)

(FOR INFORMATION ONLY — Name, address and telephone)

AGENT or **BROKER**:

OWNER'S REPRESENTATIVE:

(Architect, Engineer or other party:)
Scott Ostrander

(Corporate Seal)

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An Additions and Deletions Report that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

User Notes:

- § 1 The Contractor and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Owner for the performance of the Construction Contract, which is incorporated herein by reference.
- § 2 If the Contractor performs the Construction Contract, the Surety and the Contractor shall have no obligation under this Bond, except when applicable to participate in a conference as provided in Section 3.
- § 3 If there is no Owner Default under the Construction Contract, the Surety's obligation under this Bond shall arise after
 - .1 the Owner first provides notice to the Contractor and the Surety that the Owner is considering declaring a Contractor Default. Such notice shall indicate whether the Owner is requesting a conference among the Owner, Contractor and Surety to discuss the Contractor's performance. If the Owner does not request a conference, the Surety may, within five (5) business days after receipt of the Owner's notice, request such a conference. If the Surety timely requests a conference, the Owner shall attend. Unless the Owner agrees otherwise, any conference requested under this Section 3.1 shall be held within ten (10) business days of the Surety's receipt of the Owner's notice. If the Owner, the Contractor and the Surety agree, the Contractor shall be allowed a reasonable time to perform the Construction Contract, but such an agreement shall not waive the Owner's right, if any, subsequently to declare a Contractor Default;
 - 2 the Owner declares a Contractor Default, terminates the Construction Contract and notifies the Surety; and
 - .3 the Owner has agreed to pay the Balance of the Contract Price in accordance with the terms of the Construction Contract to the Surety or to a contractor selected to perform the Construction Contract.
- § 4 Failure on the part of the Owner to comply with the notice requirement in Section 3.1 shall not constitute a failure to comply with a condition precedent to the Surety's obligations, or release the Surety from its obligations, except to the extent the Surety demonstrates actual prejudice.
- § 5 When the Owner has satisfied the conditions of Section 3, the Surety shall promptly and at the Surety's expense take one of the following actions:
- § 5.1 Arrange for the Contractor, with the consent of the Owner, to perform and complete the Construction Contract;
- § 5.2 Undertake to perform and complete the Construction Contract itself, through its agents or independent contractors;
- § 5.3 Obtain bids or negotiated proposals from qualified contractors acceptable to the Owner for a contract for performance and completion of the Construction Contract, arrange for a contract to be prepared for execution by the Owner and a contractor selected with the Owner's concurrence, to be secured with performance and payment bonds executed by a qualified surety equivalent to the bonds issued on the Construction Contract, and pay to the Owner the amount of damages as described in Section 7 in excess of the Balance of the Contract Price incurred by the Owner as a result of the Contractor Default; or
- § 5.4 Waive its right to perform and complete, arrange for completion, or obtain a new contractor and with reasonable promptness under the circumstances:
 - .1 After investigation, determine the amount for which it may be liable to the Owner and, as soon as practicable after the amount is determined, make payment to the Owner; or
 - .2 Deny liability in whole or in part and notify the Owner, citing the reasons for denial.
- § 6 If the Surety does not proceed as provided in Section 5 with reasonable promptness, the Surety shall be deemed to be in default on this Bond seven days after receipt of an additional written notice from the Owner to the Surety demanding that the Surety perform its obligations under this Bond, and the Owner shall be entitled to enforce any remedy available to the Owner. If the Surety proceeds as provided in Section 5.4, and the Owner refuses the payment or the Surety has denied liability, in whole or in part, without further notice the Owner shall be entitled to enforce any remedy available to the Owner.

- § 7 If the Surety elects to act under Section 5.1, 5.2 or 5.3, then the responsibilities of the Surety to the Owner shall not be greater than those of the Contractor under the Construction Contract, and the responsibilities of the Owner to the Surety shall not be greater than those of the Owner under the Construction Contract. Subject to the commitment by the Owner to pay the Balance of the Contract Price, the Surety is obligated, without duplication, for
 - .1 the responsibilities of the Contractor for correction of defective work and completion of the Construction Contract;
 - .2 additional legal, design professional and delay costs resulting from the Contractor's Default, and resulting from the actions or failure to act of the Surety under Section 5; and
 - 3 liquidated damages, or if no liquidated damages are specified in the Construction Contract, actual damages caused by delayed performance or non-performance of the Contractor.
- § 8 If the Surety elects to act under Section 5.1, 5.3 or 5.4, the Surety's liability is limited to the amount of this Bond.
- § 9 The Surety shall not be liable to the Owner or others for obligations of the Contractor that are unrelated to the Construction Contract, and the Balance of the Contract Price shall not be reduced or set off on account of any such unrelated obligations. No right of action shall accrue on this Bond to any person or entity other than the Owner or its heirs, executors, administrators, successors and assigns.
- § 10 The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.
- § 11 Any proceeding, legal or equitable, under this Bond may be instituted in any court of competent jurisdiction in the location in which the work or part of the work is located and shall be instituted within two years after a declaration of Contractor Default or within two years after the Contractor ceased working or within two years after the Surety refuses or fails to perform its obligations under this Bond, whichever occurs first. If the provisions of this Paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.
- § 12 Notice to the Surety, the Owner or the Contractor shall be mailed or delivered to the address shown on the page on which their signature appears.
- § 13 When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

§ 14 Definitions

- § 14.1 Balance of the Contract Price. The total amount payable by the Owner to the Contractor under the Construction Contract after all proper adjustments have been made, including allowance to the Contractor of any amounts received or to be received by the Owner in settlement of insurance or other claims for damages to which the Contractor is entitled, reduced by all valid and proper payments made to or on behalf of the Contractor under the Construction Contract.
- § 14.2 Construction Contract. The agreement between the Owner and Contractor identified on the cover page, including all Contract Documents and changes made to the agreement and the Contract Documents.
- § 14.3 Contractor Default. Failure of the Contractor, which has not been remedied or waived, to perform or otherwise to comply with a material term of the Construction Contract.
- § 14.4 Owner Default. Failure of the Owner, which has not been remedied or waived, to pay the Contractor as required under the Construction Contract or to perform and complete or comply with the other material terms of the Construction Contract.
- § 14.5 Contract Documents. All the documents that comprise the agreement between the Owner and Contractor.

§ 15 If this Bond is issued for an agreement between a Contractor and subcontractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

§ 16 Modifications to this bond are as follows:

| CONTRACTOR AS PRINCIPAL | | SURETY | |
|-------------------------|------------------|-----------------|------------------|
| Company: | (Corporate Seal) | Company: | (Corporate Seal) |
| Signature: | | Signature: | |
| Name and Title: | | Name and Title: | |
| Address: | | Address: | |
| | | | |

Request for Information ("RFI") TO: FROM: Delaware Engineering, DPC 28 Madison Ave Ext., Albany, NY 12203 PROJECT: **ISSUE DATE:** RFI No. 001 Town of Milton Rowland Street Highway Facility - Cold Storage **PEMB** REQUESTED REPLY DATE: PROJECT NUMBERS: 23-2654 / **COPIES TO: RFI DESCRIPTION:** (Fully describe the question or type of information requested.) REFERENCES/ATTACHMENTS: (List specific documents researched when seeking the information requested.) SPECIFICATIONS: **DRAWINGS:** OTHER: **SENDER'S RECOMMENDATION:** (If RFI concerns a site or construction condition, the sender may provide a recommended solution, including cost and/or schedule considerations.) **RECEIVER'S REPLY:** (Provide answer to RFI, including cost and/or schedule considerations.) BY DATE **COPIES TO**

Note: This reply is not an authorization to proceed with work involving additional cost, time or both. If any reply requires a change to the Contract Documents, a Change Order, Construction Change Directive or a Minor Change in the work must be executed in accordance with the Contract Documents.



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

| PRO | DUC | ER | | | | CONTA NAME: | CT | | | | | | |
|-------------|---|---|--------|--------|--|-------------------------|--|----------------|--|----|--------|--|--|
| | | | | | | | PHONE FAX (A/C, No, Ext): (A/C, No): | | | | | | |
| | | | | | | | E-MAIL ADDRESS: | | | | | | |
| | | | | | | PRODUCER CUSTOMER ID #: | | | | | | | |
| | | | | | | | | URER(S) AFFOR | RDING COVERAGE | | NAIC # | | |
| INSU | JRED | | | | | INSURE | RA: | | | | | | |
| | | | | | | INSURE | RB: | | | | | | |
| | | | | | | INSURE | RC: | | | | | | |
| | | | | | | INSURE | RD: | | | | | | |
| | | | | | | INSURE | RE: | | | | | | |
| | | | | | | | RF: | | | | | | |
| СО | COVERAGES CERTIFICATE NUMBER: REVISION NUMBER: | | | | | | | | | | | | |
| IN C | THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS. | | | | | | | | | | | | |
| INSR LTR | | TYPE OF INSURANCE | ADDI | SUBR | | | POLICY EFF (MM/DD/YYYY) | POLICY EXP | LIMIT | s | | | |
| -:K | GE | NERAL LIABILITY | INOR | **** | I CLIOT NOMBER | | (| (MINICOLL LIT) | EACH OCCURRENCE | \$ | | | |
| | | COMMERCIAL GENERAL LIABILITY | | | | | | | DAMAGE TO RENTED PREMISES (Ea occurrence) | \$ | | | |
| | | CLAIMS-MADE OCCUR | | | | | | | MED EXP (Any one person) | \$ | | | |
| | | CENTING INVEST. | | | | | | | PERSONAL & ADV INJURY | \$ | | | |
| | | | - | | | | | | GENERAL AGGREGATE | \$ | | | |
| | GE |) N'L AGGREGATE LIMIT APPLIES PER: | - | | | | | | PRODUCTS - COMP/OP AGG | \$ | | | |
| | | POLICY PRO- JECT LOC | | | | | | | TROBOUTO COMITOT ACC | \$ | | | |
| | AU. | TOMOBILE LIABILITY | | | | | | | COMBINED SINGLE LIMIT | \$ | | | |
| | | ANY AUTO | | | | | | | (Ea accident) BODILY INJURY (Per person) | \$ | | | |
| | | ALL OWNED AUTOS | | | | | | | BODILY INJURY (Per accident) | \$ | | | |
| | | SCHEDULED AUTOS | | | | | | | PROPERTY DAMAGE | - | | | |
| | | HIRED AUTOS | | | | | | | (Per accident) | \$ | | | |
| | | NON-OWNED AUTOS | | | | | | | | \$ | | | |
| | | | | | | | | | | \$ | | | |
| | | UMBRELLA LIAB OCCUR | | | | | | | EACH OCCURRENCE | \$ | | | |
| | | EXCESS LIAB CLAIMS-MAD | E | | | | | | AGGREGATE | \$ | | | |
| | | DEDUCTIBLE | | | | | | | | \$ | | | |
| | | RETENTION \$ | | | | | | | | \$ | | | |
| | | RKERS COMPENSATION D EMPLOYERS' LIABILITY | . _\ | | | | | | WC STATU- OTH- TORY LIMITS ER | | | | |
| | AN' | Y PROPRIETOR/PARTNER/EXECUTIVE | N/A | | | | | | E.L. EACH ACCIDENT | \$ | | | |
| | (Ma | FICER/MEMBER EXCLUDED? | ٦,,,, | | | | | | E.L. DISEASE - EA EMPLOYEE | \$ | | | |
| | If ye | es, describe under SCRIPTION OF OPERATIONS below | | | | | | | E.L. DISEASE - POLICY LIMIT | \$ | | | |
| _ | _ | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| DES | CRIP. | TION OF OPERATIONS / LOCATIONS / VEH | CLES (| Attach | ACORD 101, Additional Remarks | Schedule | , if more space is | required) | | | | | |
| | Keystone Associates Architects, Engineers and Surveyors, LLC, Their Officers, Directors, Employees, Consultants are added as Additional Insureds on primary and non-contributing basis. | | | | | | | | | | | | |
| CE | CERTIFICATE HOLDER CANCELLATION | | | | | | | | | | | | |
| | | | | | SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS. | | | | | | | | |
| | | | | | | AUTHO | RIZED REPRESE | NTATIVE | | | | | |

Supplemental Attachment for ACORD Certificate of Insurance 25

| PROJECT: (name and address) | | | | CONTRACT INFORMATION: Contract For: Date: | CERTIFICATE INFOI Producer: Insured: Date: | | | |
|-----------------------------|--------|-------|---|--|---|-----------------|-----------------|-----|
| OWN | IER: (| name | e and address) | ARCHITECT: (name and address) | CONTRACTOR: (na. | ne and address) | | |
| | | | | | 4 | | | |
| A. | Ger | eral | Liability | | | Yes | No | N/A |
| | 1. | Do | es this policy include | · · | | _ | \underline{Y} | |
| | | а | | of bodily injury, sickness, or disease, and death of any person? | including occupational | | | |
| | | b | Personal injury and | d advertising injury? | | | | |
| | | C | | of physical damage to or destruction of use of such property? | of tangible property, | | | |
| | | d | Bodily injury or pr | roperty damage arising out of comple | ted operations? | | | |
| | | е | The Contractor's i | ndemnity obligations included in the | Contract Documents? | | | |
| | 2. | Do | es this policy contain | n an exclusion or restriction of covera | ige for: | | | |
| | | а | restrictions is base | ared against another insured, where the double on the fact that the claimant e coverage for the claim? | | | | |
| | | b | Claims for propert products-complete | y damage to the Contractor's Work a d operations hazard where the damage | ged Work or the Work | | | |
| | | | | amage arises was performed by a Sub | | _ | | _ |
| | | C | | injury other than to employees of the | | | Ц | 닏 |
| | | d | Documents arising | ntractor's indemnity obligations inclu s out of injury to employees of the ins | sured? | | | |
| | | е | Claims for loss exc exclusionary langu | cluded under a prior work endorseme lage? | nt or other similar | | | |
| | | f | Claims or loss due similar exclusiona | to physical damage under a prior inj ry language? | ury endorsement or | | | |
| | | g | | esidential, multi-family, or other hab | itational projects? | | | |
| | | h | Claims related to r | | | | | |
| | | i | exterior coatings o | | thetic stucco, or similar | | | |
| | | j | | earth subsistence or movement? | | | | |
| | | k | Claims related to e | explosion, collapse, and underground | hazards? | | | |
| В. | Oth | er In | surance Coverage | | | Yes | No | N/A |
| | 1. | | | ontractor has the following insurance | coverages and, if so, | | | |
| | | ind | licate the coverage li | | | _ | _ | _ |
| | | а | Professional liabili | | | | | |
| | | _ | Coverage limit | | | | | |
| | | b | Pollution liability | | | Ш | | Ш |
| | | | Coverage limit | | | | | |
| | | С | Insurance for mari Coverage limit | time liability risks associated with thes: | e operation of a vessel | Ш | Ш | Ш |

| d Insurance for the use or operation of manned or | unmanned aircraft | |
|---|------------------------------------|-----|
| Coverage limits: • Property insurance | | ппп |
| Coverage limits: | | |
| f Railroad protective liability insurance Coverage limits: | | |
| g Asbestos abatement liability insurance Coverage limits: | | |
| h Insurance for physical damage to property while the construction site Coverage limits: | it is in storage and in transit to | |
| i Other: | | |
| | (Authorized Representative) | |
| | (Humorizea Representative) | |
| | (Date of Issue) | |
| | | |
| | | |
| | | |
| | | |
| | | |

STATE OF NEW YORK WORKERS' COMPENSATION BOARD

CERTIFICATE OF NYS WORKERS' COMPENSATION INSURANCE COVERAGE

| 1a. Legal Name and address of Insured (Use street address only) | 1b. Business Telephone Number of Insured | | | | |
|---|--|--|--|--|--|
| | 1c. NYS Unemployment Insurance Employer Registration Number of Insured | | | | |
| Work Location of Insured (Only required if coverage is specifically limited to certain locations in New York State, i.e. a Wrap-Up Policy) | 1d. Federal Employer Identification Number of Insured or Social Security Number | | | | |
| | | | | | |
| 2. Name and Address of the Entity Requesting Proof of Coverage | 3a. Name of Insurance Carrier | | | | |
| (Entity Being Listed as the Certificate Holder) | SELECTIVE INSURANCE COMPANY OF AMERICA | | | | |
| | □ SELECTIVE WAY INSURANCE COMPANY □ SELECTIVE INSURANCE COMPANY OF SOUTH CAROLINA □ SELECTIVE INSURANCE COMPANY OF NEW YORK | | | | |
| | 3b. Policy Number of entity listed in box "a": | | | | |
| | | | | | |
| | 3c. Policy effective period: | | | | |
| | | | | | |
| | to | | | | |
| | 3d. The Proprietor, Partners or Executive Offices are: | | | | |
| | included. (Only check box if all partners/officers included) all excluded or certain partners/officers excluded. | | | | |
| | an excluded of certain partiters/officers excluded. | | | | |
| | | | | | |
| | | | | | |
| This certifies that the insurance carrier indicated above in box "3" insures the bus New York State Workers' Compensation Law. (To use this form, New York (New York exception insurance policy). The Insurance Carrier or its leabove as the certificate holder in box "2". | (Y) must be listed under <u>Item 3.A.</u> on the INFORMATION PAGE of | | | | |
| The Insurance Carrier will also notify the above certificate holder within 10 days IF there are reasons other than nonpayment of premiums that cancel th Certificate. (These notices may be sent by regular mail.) Otherwise, this Certificarier or its licensed agent or until the policy expiration date listed in box "3c" | e policy or eliminate the insured from the coverage indicated on this icate is valid for one year after this form is approved by the insurance | | | | |
| Please Note: Upon the cancellation of the workers' compensation policy indicated contract issued by a certificate holder, the business must provide that certificate holder, authorized proof that the business is complying with the mandatory coverage requirem | older with a new Certificate of Workers' Compensation Coverage or other | | | | |
| Under penalty of perjury, I certify that I am an authorized representative of the named insured has the coverage as depicted on this form. | or licensed agent of the insurance carrier referenced above and that | | | | |
| Approved by: (Print name of authorized representative or licensed agent of insurance carrier) | | | | | |
| | | | | | |
| Approved by:(Signature) | (Date) | | | | |
| | | | | | |
| Title: | | | | | |
| Telephone Number of authorized representative or licensed agent of insurance carrier: | | | | | |
| Please Note: Only insurance carriers and their licensed agents are authorized to it. | issue the C-105.2 form. Insurance brokers are NOT authorized to issue | | | | |

C-105.2 (09-07) Page 1 of 2

Workers' Compensation Law

Section 57. Restriction on issue of permits and the entering into contracts unless compensation is secured.

- 1. The head of a state or municipal department, board, commission or office authorized or required by law to issue any permit for or in connection with any work involving the employment of employees in a hazardous employment defined by this chapter, and notwithstanding any general or special statute requiring or authorizing the issue of such permits, shall not issue such permit unless proof duly subscribed by an insurance carrier is produced in a form satisfactory to the chair, that compensation for all employees has been secured as provided by this chapter. Nothing herein, however, shall be construed as creating any liability on the part of such state or municipal department, board, commission or office to pay any compensation to any such employee if so employed.
- 2. The head of a state or municipal department, board, commission or office authorized or required by law to enter into any contract for or in connection with any work involving the employment of employees in a hazardous employment defined by this chapter, notwithstanding any general or special statute requiring or authorizing any such contract, shall not enter into any such contract unless proof duly subscribed by an insurance carrier is produced in a form satisfactory to the chair, that compensation for all employees has been secured as provided by this chapter.



C-105.2 (09-07) Page 2 of 2

Supplemental Attachment for ACORD Certificate of Insurance 25

PROJECT: (name and address)

Town of Milton

CONTRACT INFORMATION:

Contract For: Cold Storage PEMB

CERTIFICATE INFORMATION:

Producer:

| Rowland Street Highway Facility - Cold Storage PEMB OWNER: (name and address) Town of Milton 503 Geyser Road, Ballston Spa, NY 12020 | | | Date: | Insured: Date: | | | | |
|---|-----|---|---|---|-------------------------|-----------|----|-----|
| | | me and address) ARCHITECT: (name and address) Delaware Engineering, DPC CONTRACTOR: (name | | ne and a | address | <i>")</i> | | |
| Α. | Ger | | Liability | | | Yes | No | N/A |
| | 1. | | es this policy include c | = | | | | |
| | | a | | bodily injury, sickness, or disease, indudeath of any person? | cluding occupational | | Ш | Ш |
| | | b | Personal injury and a | • • | | | П | |
| | | C | | physical damage to or destruction of | tangible property. | | П | |
| | | | | use of such property? | 8 1 1 77 | | | |
| | | d | Bodily injury or prop | erty damage arising out of completed | operations? | | | |
| | | е | | emnity obligations included in the Co | | | | |
| | 2. | Do | | n exclusion or restriction of coverage | | | | _ |
| | | а | | ed against another insured, where the | | | Ш | |
| | | | | solely on the fact that the claimant is a coverage for the claim? | in insured, and there | | | |
| | | b | | lamage to the Contractor's Work arisi | ing out of the | | П | |
| | | | products-completed | operations hazard where the damaged | Work or the Work | | | |
| | | | | age arises was performed by a Subco | | _ | | _ |
| | | C | | ury other than to employees of the ins | | Ц | Ц | 닏 |
| | | d | | actor's indemnity obligations included ut of injury to employees of the insure | | | | |
| | | е | _ | ded under a prior work endorsement | | | | |
| | | | exclusionary languag | | or other similar | | ш | ш |
| | | f | | physical damage under a prior injury | endorsement or | | | |
| | | | similar exclusionary | | | | | _ |
| | | g | | idential, multi-family, or other habitat | ional projects? | | | |
| | | h | Claims related to roo | _ | | Ц | Ц | 닏 |
| | | i | Claims related to ext exterior coatings or s | erior insulation finish systems, synthe | etic stucco, or similar | | Ш | Ш |
| | | i | _ | th subsistence or movement? | | | П | |
| | | k | | plosion, collapse, and underground has | zards? | | П | П |
| | | | | , 1 , | | | | _ |
| В. | Oth | er In | surance Coverage | | | Yes | No | N/A |
| | 1. | | licate whether the Cont licate the coverage limi | ractor has the following insurance covts for each. | verages and, if so, | | | |
| | | а | Professional liability | | | | | |
| | | | Coverage limits: | | | | _ | _ |
| | | b | Pollution liability ins | urance | | | | |
| | | | Coverage limits: | | | | | |
| | | С | Insurance for maritin | ne liability risks associated with the o | peration of a vessel | | | |

AIA Document G715 – 2017. Copyright © 1991 and 2017. All rights reserved. "The American Institute of Architects," "American Institute of Architects," "American Institute of Architects," "All," the AIA Logo, and "AIA Contract Documents" are trademarks of The American Institute of Architects. This document was produced at 15:02:49 ET on 05/18/2023 under Order No.4104238150 which expires on 12/07/2023, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail docinfo@aiacontracts.com. **User Notes:**

(3B9ADA47)

| | Coverage limits: | | | | |
|--|--|-----------------------------|---|---|---|
| d | Insurance for the use or operation of manned or | unmanned aircraft | | | |
| | Coverage limits: | | | | |
| е | Property insurance | | Ш | Ш | Ш |
| f | Coverage limits: Railroad protective liability insurance | | | | |
| 1 | Coverage limits: | | Ш | Ш | |
| g | Asbestos abatement liability insurance Coverage limits: | | | | |
| h Insurance for physical damage to property while it is in storage and in transit to the construction site | | | | | |
| | Coverage limits: | | | | |
| ı | Other: | | | Ш | |
| | | | | | |
| | | | | | |
| | | (Authorized Representative) | | | |
| | | (Date of Issue) | | | |
| | | | | | |
| | | | | | |

STATE OF NEW YORK WORKERS' COMPENSATION BOARD

CERTIFICATE OF NYS WORKERS' COMPENSATION INSURANCE COVERAGE

| 1a. Legal Name and address of Insured (Use street address only) | 1b. Business Telephone Number of Insured | | | | | |
|---|--|--|--|--|--|--|
| | 1c. NYS Unemployment Insurance Employer Registration Number of Insured | | | | | |
| Work Location of Insured (Only required if coverage is specifically limited to certain locations in New York State, i.e. a Wrap-Up Policy) | 1d. Federal Employer Identification Number of Insured or Social Security Number | | | | | |
| | | | | | | |
| 2. Name and Address of the Entity Requesting Proof of Coverage | 3a. Name of Insurance Carrier | | | | | |
| (Entity Being Listed as the Certificate Holder) | SELECTIVE INSURANCE COMPANY OF AMERICA | | | | | |
| | SELECTIVE WAY INSURANCE COMPANY SELECTIVE INSURANCE COMPANY OF SOUTH CAROLINA SELECTIVE INSURANCE COMPANY OF NEW YORK | | | | | |
| | 3b. Policy Number of entity listed in box "a": | | | | | |
| | | | | | | |
| | 3c. Policy effective period: | | | | | |
| | | | | | | |
| | to | | | | | |
| | 3d. The Proprietor, Partners or Executive Offices are: | | | | | |
| | included. (Only check box if all partners/officers included) all excluded or certain partners/officers excluded. | | | | | |
| | an excluded of certain partners/officers excluded. | | | | | |
| | | | | | | |
| | | | | | | |
| This certifies that the insurance carrier indicated above in box "3" insures the business referenced above in box "1a" for workers' compensation under the New York State Workers' Compensation Law. (To use this form, New York (NY) must be listed under Item 3.A. on the INFORMATION PAGE of the workers' compensation insurance policy). The Insurance Carrier or its licensed agent will send this Certificate of Insurance to the entity listed above as the certificate holder in box "2". | | | | | | |
| The Insurance Carrier will also notify the above certificate holder within 10 days days IF there are reasons other than nonpayment of premiums that cancel the Certificate. (These notices may be sent by regular mail.) Otherwise, this Certific carrier or its licensed agent or until the policy expiration date listed in box "3c", | policy or eliminate the insured from the coverage indicated on this ate is valid for one year after this form is approved by the insurance | | | | | |
| Please Note: Upon the cancellation of the workers' compensation policy indicated or contract issued by a certificate holder, the business must provide that certificate hold authorized proof that the business is complying with the mandatory coverage requirements. | der with a new Certificate of Workers' Compensation Coverage or other | | | | | |
| Under penalty of perjury, I certify that I am an authorized representative or the named insured has the coverage as depicted on this form. | licensed agent of the insurance carrier referenced above and that | | | | | |
| Approved by: | | | | | | |
| | | | | | | |
| Approved by:(Signature) | (Date) | | | | | |
| | | | | | | |
| Title: | | | | | | |
| Telephone Number of authorized representative or licensed agent of insurance carrier: | | | | | | |
| Please Note: Only insurance carriers and their licensed agents are authorized to it. | ssue the C-105.2 form. Insurance brokers are NOT authorized to issue | | | | | |

C-105.2 (09-07) Page 1 of 2

Workers' Compensation Law

Section 57. Restriction on issue of permits and the entering into contracts unless compensation is secured.

- 1. The head of a state or municipal department, board, commission or office authorized or required by law to issue any permit for or in connection with any work involving the employment of employees in a hazardous employment defined by this chapter, and notwithstanding any general or special statute requiring or authorizing the issue of such permits, shall not issue such permit unless proof duly subscribed by an insurance carrier is produced in a form satisfactory to the chair, that compensation for all employees has been secured as provided by this chapter. Nothing herein, however, shall be construed as creating any liability on the part of such state or municipal department, board, commission or office to pay any compensation to any such employee if so employed.
- 2. The head of a state or municipal department, board, commission or office authorized or required by law to enter into any contract for or in connection with any work involving the employment of employees in a hazardous employment defined by this chapter, notwithstanding any general or special statute requiring or authorizing any such contract, shall not enter into any such contract unless proof duly subscribed by an insurance carrier is produced in a form satisfactory to the chair, that compensation for all employees has been secured as provided by this chapter.



C-105.2 (09-07) Page 2 of 2

Contractor's Affidavit of Release of Liens

| Town Rowl Cold TO ON Town | IECT: (Name and address) In of Milton In of | ARCHITECT'S PRO 23-2654 CONTRACT FOR: O PEMB CONTRACT DATED | Cold Storage | OWNER: ARCHITECT: CONTRACTOR: SURETY: OTHER: |
|---------------------------|---|---|-----------------------------------|--|
| STAT | E OF: NTY OF: | | | |
| below and e assert | v, the Releases or Waivers of Lier quipment, and all performers of V | n attached hereto inclu Vork, labor or services | de the Contracto who have or m | dge, information and belief, except as listed or, all Subcontractors, all suppliers of materials ay have liens or encumbrances or the right to y manner out of the performance of the Contract |
| EXCE | PTIONS: | | | |
| SUPI 1. | PORTING DOCUMENTS ATTA Contractor's Release or Waive conditional upon receipt of fin | er of Liens, | CONTRACT | OR: (Name and address) |
| 2. | Separate Releases or Waivers | of Liens from | BY: | |
| | Subcontractors and material a suppliers, to the extent require accompanied by a list thereof. | required by the Owner, | | (Signature of authorized representative) |
| | | | | (Printed name and title) |
| | | | Subscribed | and sworn to before me on this date: |
| | | | Notary Pub | lic: |

My Commission Expires:

DOCUMENT 007343 WAGE RATE REQUIREMENTS

1.01 PREVAILING WAGE RATES

- A. Prospective bidders shall note that the applicable prevailing wage rates, as determined by the New York State Bureau of Public Works Labor Department, are applicable for all phases of the work on this project.
- B. The Prevailing Wage Rates attached are hereby made a part of this contract, in accordance with Section 220 of the Labor Law. All prospective bidders shall adhere to this documentation when preparing their bids.
- C. All prospective bidders shall adhere to this documentation when preparing their bids.

1.02 LABOR LAW 220-H – OSHA – 10 COMPLIANCE

- A. All laborers, workers, and mechanics working on a public works project valued at \$250,000 or more must be certified as having successfully completed the OSHA 10-hour Construction Safety and Health Course. Only those people working under the Prevailing Wage Standards are required to have the training.
- B. DOL requires all contractors and subcontractors to attach a copy of proof of completion of the OSHA 10-hour course with the first certified payroll submitted to the contracting agency and on each succeeding payroll where any new or additional employee is first listed.
 - a. Proof of completion may include but not limited to:
 - i. Copies of bona fide course completion card;
 - ii. Training roster, attendance record, or other documentation from the certified trainer pending the issuance of the card;
 - iii. Other valid proof (although, no example of other valid proof was offered).
 - b. A certification by the employer attesting that all employees have completed such a course is not sufficient proof that the course has been completed.

END OF DOCUMENT 007343

| Kathy Hochul, Governor | |
|-------------------------|---------|
| Talify Hoonal, Governor | MENT OF |

Roberta Reardon, Commissioner

Town of Milton

Cody Messier, Project Manager 28 Madison Ave Ext Albany NY 12203 Schedule Year
Date Requested
PRC#

2022 through 2023 05/24/2023 2023005977

Location

Rowland Street

Project ID#

Project Type New cold storage pre-engineered metal building

PREVAILING WAGE SCHEDULE FOR ARTICLE 8 PUBLIC WORK PROJECT

Attached is the current schedule(s) of the prevailing wage rates and prevailing hourly supplements for the project referenced above. A unique Prevailing Wage Case Number (PRC#) has been assigned to the schedule(s) for your project.

The schedule is effective from July 2022 through June 2023. All updates, corrections, posted on the 1st business day of each month, and future copies of the annual determination are available on the Department's website www.labor.ny.gov. Updated PDF copies of your schedule can be accessed by entering your assigned PRC# at the proper location on the website.

It is the responsibility of the contracting agency or its agent to annex and make part, the attached schedule, to the specifications for this project, when it is advertised for bids and /or to forward said schedules to the successful bidder(s), immediately upon receipt, in order to insure the proper payment of wages.

Please refer to the "General Provisions of Laws Covering Workers on Public Work Contracts" provided with this schedule, for the specific details relating to other responsibilities of the Department of Jurisdiction.

Upon completion or cancellation of this project, enter the required information and mail **OR** fax this form to the office shown at the bottom of this notice, **OR** fill out the electronic version via the NYSDOL website.

| NOTICE OF COMPLETION / CANCELLATION OF PROJECT | | | |
|--|-----------------|--|--|
| Date Completed: | Date Cancelled: | | |
| Name & Title of Representative: | | | |

Phone: (518) 457-5589 Fax: (518) 485-1870 W. Averell Harriman State Office Campus, Bldg. 12, Room 130, Albany, NY 12240

General Provisions of Laws Covering Workers on Article 8 Public Work Contracts

Introduction

The Labor Law requires public work contractors and subcontractors to pay laborers, workers, or mechanics employed in the performance of a public work contract not less than the prevailing rate of wage and supplements (fringe benefits) in the locality where the work is performed.

Responsibilities of the Department of Jurisdiction

A Department of Jurisdiction (Contracting Agency) includes a state department, agency, board or commission: a county, city, town or village; a school district, board of education or board of cooperative educational services; a sewer, water, fire, improvement and other district corporation; a public benefit corporation; and a public authority awarding a public work contract.

The Department of Jurisdiction (Contracting Agency) awarding a public work contract MUST obtain a Prevailing Rate Schedule listing the hourly rates of wages and supplements due the workers to be employed on a public work project. This schedule may be obtained by completing and forwarding a "Request for wage and Supplement Information" form (PW 39) to the Bureau of Public Work. The Prevailing Rate Schedule MUST be included in the specifications for the contract to be awarded and is deemed part of the public work contract.

Upon the awarding of the contract, the law requires that the Department of Jurisdiction (Contracting Agency) furnish the following information to the Bureau: the name and address of the contractor, the date the contract was let and the approximate dollar value of the contract. To facilitate compliance with this provision of the Labor Law, a copy of the Department's "Notice of Contract Award" form (PW 16) is provided with the original Prevailing Rate Schedule.

The Department of Jurisdiction (Contracting Agency) is required to notify the Bureau of the completion or cancellation of any public work project. The Department's PW 200 form is provided for that purpose.

Both the PW 16 and PW 200 forms are available for completion online.

Hours

No laborer, worker, or mechanic in the employ of a contractor or subcontractor engaged in the performance of any public work project shall be permitted to work more than eight hours in any day or more than five days in any week, except in cases of extraordinary emergency. The contractor and the Department of Jurisdiction (Contracting Agency) may apply to the Bureau of Public Work for a dispensation permitting workers to work additional hours or days per week on a particular public work project.

There are very few exceptions to this rule. Complete information regarding these exceptions is available on the "Request for a dispensation to work overtime" form (PW30) and "4 Day / 10 Hour Work Schedule" form (PW 30.1).

Wages and Supplements

The wages and supplements to be paid and/or provided to laborers, workers, and mechanics employed on a public work project shall be not less than those listed in the current Prevailing Rate Schedule for the locality where the work is performed. If a prime contractor on a public work project has not been provided with a Prevailing Rate Schedule, the contractor must notify the Department of Jurisdiction (Contracting Agency) who in turn must request an original Prevailing Rate Schedule form the Bureau of Public Work. Requests may be submitted by: mail to NYSDOL, Bureau of Public Work, State Office Bldg. Campus, Bldg. 12, Rm. 130, Albany, NY 12240; Fax to Bureau of Public Work (518) 485-1870; or electronically at the NYSDOL website www.labor.ny.gov.

Upon receiving the original schedule, the Department of Jurisdiction (Contracting Agency) is REQUIRED to provide complete copies to all prime contractors who in turn MUST, by law, provide copies of all applicable county schedules to each subcontractor and obtain from each subcontractor, an affidavit certifying such schedules were received. If the original schedule expired, the contractor may obtain a copy of the new annual determination from the NYSDOL website www.labor.ny.gov.

The Commissioner of Labor makes an annual determination of the prevailing rates. This determination is in effect from July 1st through June 30th of the following year. The annual determination is available on the NYSDOL website www.labor.ny.gov.

Payrolls and Payroll Records

Every contractor and subcontractor MUST keep original payrolls or transcripts subscribed and affirmed as true under penalty of perjury. As per Article 6 of the Labor law, contractors and subcontractors are required to establish, maintain, and preserve for not less than six (6) years, contemperaneous, true, and accurate payroll records. At a minimum, payrolls must show the following information for each person employed on a public work project: Name, Address, Last 4 Digits of Social Security Number, Classification(s) in which the worker was employed, Hourly wage rate(s) paid, Supplements paid

or provided, and Daily and weekly number of hours worked in each classification.

The filing of payrolls to the Department of Jurisdiction is a condition of payment. Every contractor and subcontractor shall submit to the Department of Jurisdiction (Contracting Agency), within thirty (30) days after issuance of its first payroll and every thirty (30) days thereafter, a transcript of the original payrolls, subscribed and affirmed as true under penalty of perjury. The Department of Jurisdiction (Contracting Agency) shall collect, review for facial validity, and maintain such payrolls.

In addition, the Commissioner of Labor may require contractors to furnish, with ten (10) days of a request, payroll records sworn to as their validity and accuracy for public work and private work. Payroll records include, but are not limited to time cards, work description sheets, proof that supplements were provided, cancelled payroll checks and payrolls. Failure to provide the requested information within the allotted ten (10) days will result in the withholding of up to 25% of the contract, not to exceed \$100,000.00. If the contractor or subcontractor does not maintain a place of business in New York State and the amount of the contract exceeds \$25,000.00, payroll records and certifications must be kept on the project worksite.

The prime contractor is responsible for any underpayments of prevailing wages or supplements by any subcontractor.

All contractors or their subcontractors shall provide to their subcontractors a copy of the Prevailing Rate Schedule specified in the public work contract as well as any subsequently issued schedules. A failure to provide these schedules by a contractor or subcontractor is a violation of Article 8, Section 220-a of the Labor Law.

All subcontractors engaged by a public work project contractor or its subcontractor, upon receipt of the original schedule and any subsequently issued schedules, shall provide to such contractor a verified statement attesting that the subcontractor has received the Prevailing Rate Schedule and will pay or provide the applicable rates of wages and supplements specified therein. (See NYS Labor Laws, Article 8 . Section 220-a).

Determination of Prevailing Wage and Supplement Rate Updates Applicable to All Counties

The wages and supplements contained in the annual determination become effective July 1st whether or not the new determination has been received by a given contractor. Care should be taken to review the rates for obvious errors. Any corrections should be brought to the Department's attention immediately. It is the responsibility of the public work contractor to use the proper rates. If there is a question on the proper classification to be used, please call the district office located nearest the project. Any errors in the annual determination will be corrected and posted to the NYSDOL website on the first business day of each month. Contractors are responsible for paying these updated rates as well, retroactive to July 1st.

When you review the schedule for a particular occupation, your attention should be directed to the dates above the column of rates. These are the dates for which a given set of rates is effective. To the extent possible, the Department posts rates in its possession that cover periods of time beyond the July 1st to June 30th time frame covered by a particular annual determination. Rates that extend beyond that instant time period are informational ONLY and may be updated in future annual determinations that actually cover the then appropriate July 1st to June 30th time period.

Withholding of Payments

When a complaint is filed with the Commissioner of Labor alleging the failure of a contractor or subcontractor to pay or provide the prevailing wages or supplements, or when the Commissioner of Labor believes that unpaid wages or supplements may be due, payments on the public work contract shall be withheld from the prime contractor in a sufficient amount to satisfy the alleged unpaid wages and supplements, including interest and civil penalty, pending a final determination.

When the Bureau of Public Work finds that a contractor or subcontractor on a public work project failed to pay or provide the requisite prevailing wages or supplements, the Bureau is authorized by Sections 220-b and 235.2 of the Labor Law to so notify the financial officer of the Department of Jurisdiction (Contracting Agency) that awarded the public work contract. Such officer MUST then withhold or cause to be withheld from any payment due the prime contractor on account of such contract the amount indicated by the Bureau as sufficient to satisfy the unpaid wages and supplements, including interest and any civil penalty that may be assessed by the Commissioner of Labor. The withholding continues until there is a final determination of the underpayment by the Commissioner of Labor or by the court in the event a legal proceeding is instituted for review of the determination of the Commissioner of Labor.

The Department of Jurisdiction (Contracting Agency) shall comply with this order of the Commissioner of Labor or of the court with respect to the release of the funds so withheld.

Summary of Notice Posting Requirements

The current Prevailing Rate Schedule must be posted in a prominent and accessible place on the site of the public work project. The prevailing wage schedule must be encased in, or constructed of, materials capable of withstanding adverse weather conditions and be titled "PREVAILING RATE OF WAGES" in letters no smaller than two (2) inches by two (2) inches.

The "Public Work Project" notice must be posted at the beginning of the performance of every public work contract, on each job site.

Every employer providing workers. compensation insurance and disability benefits must post notices of such coverage in the format prescribed by the Workers. Compensation Board in a conspicuous place on the jobsite.

Every employer subject to the NYS Human Rights Law must conspicuously post at its offices, places of employment, or employment training centers, notices furnished by the State Division of Human Rights.

Employers liable for contributions under the Unemployment Insurance Law must conspicuously post on the jobsite notices furnished by the NYS Department of Labor.

Apprentices

Employees cannot be paid apprentice rates unless they are individually registered in a program registered with the NYS Commissioner of Labor. The allowable ratio of apprentices to journeyworkers in any craft classification can be no greater than the statewide building trade ratios promulgated by the Department of Labor and included with the Prevailing Rate Schedule. An employee listed on a payroll as an apprentice who is not registered as above or is performing work outside the classification of work for which the apprentice is indentured, must be paid the prevailing journeyworker's wage rate for the classification of work the employee is actually performing.

NYSDOL Labor Law, Article 8, Section 220-3, require that only apprentices individually registered with the NYS Department of Labor may be paid apprenticeship rates on a public work project. No other Federal or State Agency of office registers apprentices in New York State.

Persons wishing to verify the apprentice registration of any person must do so in writing by mail, to the NYSDOL Office of Employability Development / Apprenticeship Training, State Office Bldg. Campus, Bldg. 12, Albany, NY 12240 or by Fax to NYSDOL Apprenticeship Training (518) 457-7154. All requests for verification must include the name and social security number of the person for whom the information is requested.

The only conclusive proof of individual apprentice registration is written verification from the NYSDOL Apprenticeship Training Albany Central office. Neither Federal nor State Apprenticeship Training offices outside of Albany can provide conclusive registration information.

It should be noted that the existence of a registered apprenticeship program is not conclusive proof that any person is registered in that program. Furthermore, the existence or possession of wallet cards, identification cards, or copies of state forms is not conclusive proof of the registration of any person as an apprentice.

Interest and Penalties

In the event that an underpayment of wages and/or supplements is found:

- Interest shall be assessed at the rate then in effect as prescribed by the Superintendent of Banks pursuant to section 14-a of the Banking Law, per annum from the date of underpayment to the date restitution is made.
- A Civil Penalty may also be assessed, not to exceed 25% of the total of wages, supplements, and interest due.

Debarment

Any contractor or subcontractor and/or its successor shall be ineligible to submit a bid on or be awarded any public work contract or subcontract with any state, municipal corporation or public body for a period of five (5) years when:

- Two (2) willful determinations have been rendered against that contractor or subcontractor and/or its successor within any consecutive six (6) year period.
- There is any willful determination that involves the falsification of payroll records or the kickback of wages or supplements.

Criminal Sanctions

Willful violations of the Prevailing Wage Law (Article 8 of the Labor Law) may be a felony punishable by fine or imprisonment of up to 15 years, or both.

Discrimination

No employee or applicant for employment may be discriminated against on account of age, race, creed, color, national origin, sex, disability or marital status.

No contractor, subcontractor nor any person acting on its behalf, shall by reason of race, creed, color, disability, sex or national origin discriminate against any citizen of the State of New York who is qualified and available to perform the work to which the employment relates (NYS Labor Law, Article 8, Section 220-e(a)).

No contractor, subcontractor, nor any person acting on its behalf, shall in any manner, discriminate against or intimidate any employee on account of race, creed, color, disability, sex, or national origin (NYS Labor Law, Article 8, Section 220-e(b)).

The Human Rights Law also prohibits discrimination in employment because of age, marital status, or religion.

There may be deducted from the amount payable to the contractor under the contract a penalty of \$50.00 for each calendar day during which such person was discriminated against or intimidated in violation of the provision of the contract (NYS Labor Law, Article 8, Section 220-e(c)).

The contract may be cancelled or terminated by the State or municipality. All monies due or to become due thereunder may be forfeited for a second or any subsequent violation of the terms or conditions of the anti-discrimination sections of the contract (NYS Labor Law, Article 8, Section 220-e(d)).

Every employer subject to the New York State Human Rights Law must conspicuously post at its offices, places of employment, or employment training centers notices furnished by the State Division of Human Rights.

Workers' Compensation

In accordance with Section 142 of the State Finance Law, the contractor shall maintain coverage during the life of the contract for the benefit of such employees as required by the provisions of the New York State Workers' Compensation Law.

A contractor who is awarded a public work contract must provide proof of workers' compensation coverage prior to being allowed to begin work.

The insurance policy must be issued by a company authorized to provide workers' compensation coverage in New York State. Proof of coverage must be on form C-105.2 (Certificate of Workers' Compensation Insurance) and must name this agency as a certificate holder.

If New York State coverage is added to an existing out-of-state policy, it can only be added to a policy from a company authorized to write workers' compensation coverage in this state. The coverage must be listed under item 3A of the information page.

The contractor must maintain proof that subcontractors doing work covered under this contract secured and maintained a workers' compensation policy for all employees working in New York State.

Every employer providing worker's compensation insurance and disability benefits must post notices of such coverage in the format prescribed by the Workers' Compensation Board in a conspicuous place on the jobsite.

Unemployment Insurance

Employers liable for contributions under the Unemployment Insurance Law must conspicuously post on the jobsite notices furnished by the New York State Department of Labor.

| Kathy Hochul, Governor | |
|------------------------|---------|
| | MENT OF |

Roberta Reardon, Commissioner

Town of Milton

Cody Messier, Project Manager 28 Madison Ave Ext Albany NY 12203 Schedule Year Date Requested PRC# 2022 through 2023 05/24/2023 2023005977

Location

Rowland Street

Project ID#

Project Type New cold storage pre-engineered metal building

Notice of Contract Award

New York State Labor Law, Article 8, Section 220.3a requires that certain information regarding the awarding of public work contracts, be furnished to the Commissioner of Labor. One "Notice of Contract Award" (PW 16, which may be photocopied), **MUST** be completed for **EACH** prime contractor on the above referenced project.

Upon notifying the successful bidder(s) of this contract, enter the required information and mail **OR** fax this form to the office shown at the bottom of this notice, **OR** fill out the electronic version via the NYSDOL website.

Contractor Information All information must be supplied

| Federal Employer Identification N | | |
|--|--------------|--|
| Address: | | |
| City: Amount of Contract: | \$ State: | Zip: |
| Approximate Starting Date: Approximate Completion Date: | | [] (01) General Construction [] (02) Heating/Ventilation [] (03) Electrical [] (04) Plumbing |
| | | [] (05) Other : |

Phone: (518) 457-5589 Fax: (518) 485-1870 W. Averell Harriman State Office Campus, Bldg. 12, Room 130, Albany, NY 12240

Social Security Numbers on Certified Payrolls:

The Department of Labor is cognizant of the concerns of the potential for misuse or inadvertent disclosure of social security numbers. Identity theft is a growing problem and we are sympathetic to contractors' concern regarding inclusion of this information on payrolls if another identifier will suffice.

For these reasons, the substitution of the use of the last four digits of the social security number on certified payrolls submitted to contracting agencies on public work projects is now acceptable to the Department of Labor. This change does not affect the Department's ability to request and receive the entire social security number from employers during its public work/ prevailing wage investigations.

Construction Industry Fair Play Act: Required Posting for Labor Law Article 25-B § 861-d

Construction industry employers must post the "Construction Industry Fair Play Act" notice in a prominent and accessible place on the job site. Failure to post the notice can result in penalties of up to \$1,500 for a first offense and up to \$5,000 for a second offense. The posting is included as part of this wage schedule. Additional copies may be obtained from the NYS DOL website, https://dol.ny.gov/public-work-and-prevailing-wage

If you have any questions concerning the Fair Play Act, please call the State Labor Department toll-free at 1-866-435-1499 or email us at: dol.misclassified@labor.ny.gov.

Worker Notification: (Labor Law §220, paragraph a of subdivision 3-a)

Effective June 23, 2020

This provision is an addition to the existing wage rate law, Labor Law §220, paragraph a of subdivision 3-a. It requires contractors and subcontractors to provide written notice to all laborers, workers or mechanics of the *prevailing wage and supplement rate* for their particular job classification *on each pay stub**. It also requires contractors and subcontractors to *post a notice* at the beginning of the performance of every public work contract *on each job site* that includes the telephone number and address for the Department of Labor and a statement informing laborers, workers or mechanics of their right to contact the Department of Labor if he/she is not receiving the proper prevailing rate of wages and/or supplements for his/her job classification. The required notification will be provided with each wage schedule, may be downloaded from our website *www.labor.ny.gov* or be made available upon request by contacting the Bureau of Public Work at 518-457-5589. *In the event the required information will not fit on the pay stub, an accompanying sheet or attachment of the information will suffice.

(12.20)

To all State Departments, Agency Heads and Public Benefit Corporations IMPORTANT NOTICE REGARDING PUBLIC WORK ENFORCEMENT FUND

Budget Policy & Reporting Manual

B-610

Public Work Enforcement Fund

effective date December 7, 2005

1. Purpose and Scope:

This Item describes the Public Work Enforcement Fund (the Fund, PWEF) and its relevance to State agencies and public benefit corporations engaged in construction or reconstruction contracts, maintenance and repair, and announces the recently-enacted increase to the percentage of the dollar value of such contracts that must be deposited into the Fund. This item also describes the roles of the following entities with respect to the Fund:

- New York State Department of Labor (DOL),
- The Office of the State of Comptroller (OSC), and
- State agencies and public benefit corporations.

2. Background and Statutory References:

DOL uses the Fund to enforce the State's Labor Law as it relates to contracts for construction or reconstruction, maintenance and repair, as defined in subdivision two of Section 220 of the Labor Law. State agencies and public benefit corporations participating in such contracts are required to make payments to the Fund.

Chapter 511 of the Laws of 1995 (as amended by Chapter 513 of the Laws of 1997, Chapter 655 of the Laws of 1999, Chapter 376 of the Laws of 2003 and Chapter 407 of the Laws of 2005) established the Fund.

3. Procedures and Agency Responsibilities:

The Fund is supported by transfers and deposits based on the value of contracts for construction and reconstruction, maintenance and repair, as defined in subdivision two of Section 220 of the Labor Law, into which all State agencies and public benefit corporations enter.

Chapter 407 of the Laws of 2005 increased the amount required to be provided to this fund to .10 of one-percent of the total cost of each such contract, to be calculated at the time agencies or public benefit corporations enter into a new contract or if a contract is amended. The provisions of this bill became effective August 2, 2005.

To all State Departments, Agency Heads and Public Benefit Corporations IMPORTANT NOTICE REGARDING PUBLIC WORK ENFORCEMENT FUND

OSC will report to DOL on all construction-related ("D") contracts approved during the month, including contract amendments, and then DOL will bill agencies the appropriate assessment monthly. An agency may then make a determination if any of the billed contracts are exempt and so note on the bill submitted back to DOL. For any instance where an agency is unsure if a contract is or is not exempt, they can call the Bureau of Public Work at the number noted below for a determination. Payment by check or journal voucher is due to DOL within thirty days from the date of the billing. DOL will verify the amounts and forward them to OSC for processing.

For those contracts which are not approved or administered by the Comptroller, monthly reports and payments for deposit into the Public Work Enforcement Fund must be provided to the Administrative Finance Bureau at the DOL within 30 days of the end of each month or on a payment schedule mutually agreed upon with DOL.

Reports should contain the following information:

- Name and billing address of State agency or public benefit corporation;
- State agency or public benefit corporation contact and phone number;
- Name and address of contractor receiving the award;
- Contract number and effective dates;
- Contract amount and PWEF assessment charge (if contract amount has been amended, reflect increase or decrease to original contract and the adjustment in the PWEF charge); and
- Brief description of the work to be performed under each contract.

Checks and Journal Vouchers, payable to the "New York State Department of Labor" should be sent to:

Department of Labor Administrative Finance Bureau-PWEF Unit Building 12, Room 464 State Office Campus Albany, NY 12240

Any questions regarding billing should be directed to NYSDOL's Administrative Finance Bureau-PWEF Unit at (518) 457-3624 and any questions regarding Public Work Contracts should be directed to the Bureau of Public Work at (518) 457-5589.



Required Notice under Article 25-B of the Labor Law

Attention All Employees, Contractors and Subcontractors: You are Covered by the Construction Industry Fair Play Act

The law says that you are an employee unless:

- You are free from direction and control in performing your job, and
- You perform work that is not part of the usual work done by the business that hired you, and
- You have an independently established business.

Your employer cannot consider you to be an independent contractor unless all three of these facts apply to your work.

It is against the law for an employer to misclassify employees as independent contractors or pay employees off the books.

Employee Rights: If you are an employee, you are entitled to state and federal worker protections. These include:

- Unemployment Insurance benefits, if you are unemployed through no fault of your own, able to work, and otherwise qualified,
- Workers' compensation benefits for on-the-job injuries,
- Payment for wages earned, minimum wage, and overtime (under certain conditions),
- Prevailing wages on public work projects,
- The provisions of the National Labor Relations Act, and
- A safe work environment.

It is a violation of this law for employers to retaliate against anyone who asserts their rights under the law. Retaliation subjects an employer to civil penalties, a private lawsuit or both.

Independent Contractors: If you are an independent contractor, you must pay all taxes and Unemployment Insurance contributions required by New York State and Federal Law.

Penalties for paying workers off the books or improperly treating employees as independent contractors:

• **Civil Penalty** First offense: Up to \$2,500 per employee

Subsequent offense(s): Up to \$5,000 per employee

• Criminal Penalty First offense: Misdemeanor - up to 30 days in jail, up to a \$25,000 fine

and debarment from performing public work for up to one year.

Subsequent offense(s): Misdemeanor - up to 60 days in jail or up to a \$50,000 fine and debarment from performing public work for up to 5

years.

If you have questions about your employment status or believe that your employer may have violated your rights and you want to file a complaint, call the Department of Labor at (866) 435-1499 or send an email to dol.misclassified@labor.ny.gov. All complaints of fraud and violations are taken seriously. You can remain anonymous.

Employer Name:

New York State Department of Labor Bureau of Public Work

Attention Employees

THIS IS A: PUBLIC WORK PROJECT

If you are employed on this project as a worker, laborer, or mechanic you are entitled to receive the prevailing wage and supplements rate for the classification at which you are working.

Chapter 629 of the Labor Laws of 2007: These wages are set by law and must be posted at the work site. They can also be found at:

https://dol.ny.gov/public-work-and-prevailing-wage

If you feel that you have not received proper wages or benefits, please call our nearest office.*

| Albany | (518) 457-2744 | Patchogue | (631) 687-4882 |
|---------------|----------------|--------------|----------------|
| Binghamton | (607) 721-8005 | Rochester | (585) 258-4505 |
| Buffalo | (716) 847-7159 | Syracuse | (315) 428-4056 |
| Garden City | (516) 228-3915 | Utica | (315) 793-2314 |
| New York City | (212) 932-2419 | White Plains | (914) 997-9507 |
| Newburgh | (845) 568-5156 | | |

* For New York City government agency construction projects, please contact the Office of the NYC Comptroller at (212) 669-4443, or www.comptroller.nyc.gov – click on Bureau of Labor Law.

| Contractor Name: | | |
|-------------------|--|--|
| Project Location: | | |

Requirements for OSHA 10 Compliance

Article 8 §220-h requires that when the advertised specifications, for every contract for public work, is \$250,000.00 or more the contract must contain a provision requiring that every worker employed in the performance of a public work contract shall be certified as having completed an OSHA 10 safety training course. The clear intent of this provision is to require that all employees of public work contractors, required to be paid prevailing rates, receive such training "prior to the performing any work on the project."

The Bureau will enforce the statute as follows:

All contractors and sub contractors must attach a copy of proof of completion of the OSHA 10 course to the first certified payroll submitted to the contracting agency and on each succeeding payroll where any new or additional employee is first listed.

Proof of completion may include but is not limited to:

- Copies of bona fide course completion card (Note: Completion cards do not have an expiration date.)
- Training roster, attendance record of other documentation from the certified trainer pending the issuance of the card.
- Other valid proof

**A certification by the employer attesting that all employees have completed such a course is not sufficient proof that the course has been completed.

Any questions regarding this statute may be directed to the New York State Department of Labor, Bureau of Public Work at 518-457-5589.

WICKS

Public work projects are subject to the Wicks Law requiring separate specifications and bidding for the plumbing, heating and electrical work, when the total project's threshold is \$3 million in Bronx, Kings, New York, Queens and, Richmond counties; \$1.5 million in Nassau, Suffolk and Westchester counties; and \$500,000 in all other counties.

For projects below the monetary threshold, bidders must submit a sealed list naming each subcontractor for the plumbing, HVAC and electrical and the amount to be paid to each. The list may not be changed unless the public owner finds a legitimate construction need, including a change in specifications or costs or the use of a Project Labor Agreement (PLA), and must be open to public inspection.

Allows the state and local agencies and authorities to waive the Wicks Law and use a PLA if it will provide the best work at the lowest possible price. If a PLA is used, all contractors shall participate in apprentice training programs in the trades of work it employs that have been approved by the Department of Labor (DOL) for not less than three years. They shall also have at least one graduate in the last three years and use affirmative efforts to retain minority apprentices. PLA's would be exempt from Wicks, but deemed to be public work subject to prevailing wage enforcement.

The Commissioner of Labor shall have the power to enforce separate specification requirement s on projects, and may issue stop-bid orders against public owners for non-compliance.

Other new monetary thresholds, and similar sealed bidding for non-Wicks projects, would apply to certain public authorities including municipal housing authorities, NYC Construction Fund, Yonkers Educational Construction Fund, NYC Municipal Water Finance Authority, Buffalo Municipal Water Finance Authority, Westchester County Health Care Association, Nassau County Health Care Corp., Clifton-Fine Health Care Corp., Erie County Medical Center Corp., NYC Solid Waste Management Facilities, and the Dormitory Authority.

Contractors must pay subcontractors within a 7 days period.

(07.19)

Introduction to the Prevailing Rate Schedule

Information About Prevailing Rate Schedule

This information is provided to assist you in the interpretation of particular requirements for each classification of worker contained in the attached Schedule of Prevailing Rates.

Classification

It is the duty of the Commissioner of Labor to make the proper classification of workers taking into account whether the work is heavy and highway, building, sewer and water, tunnel work, or residential, and to make a determination of wages and supplements to be paid or provided. It is the responsibility of the public work contractor to use the proper rate. If there is a question on the proper classification to be used, please call the district office located nearest the project. District office locations and phone numbers are listed below.

Prevailing Wage Schedules are issued separately for "General Construction Projects" and "Residential Construction Projects" on a county-by-county basis.

General Construction Rates apply to projects such as: Buildings, Heavy & Highway, and Tunnel and Water & Sewer rates.

Residential Construction Rates generally apply to construction, reconstruction, repair, alteration, or demolition of one family, two family, row housing, or rental type units intended for residential use.

Some rates listed in the Residential Construction Rate Schedule have a very limited applicability listed along with the rate. Rates for occupations or locations not shown on the residential schedule must be obtained from the General Construction Rate Schedule. Please contact the local Bureau of Public Work office before using Residential Rate Schedules, to ensure that the project meets the required criteria.

Payrolls and Payroll Records

Contractors and subcontractors are required to establish, maintain, and preserve for not less that six (6) years, contemporaneous, true, and accurate payroll records.

Every contractor and subcontractor shall submit to the Department of Jurisdiction (Contracting Agency), within thirty (30) days after issuance of its first payroll and every thirty (30) days thereafter, a transcript of the original payrolls, subscribed and affirmed as true under penalty of perjury.

Paid Holidays

Paid Holidays are days for which an eligible employee receives a regular day's pay, but is not required to perform work. If an employee works on a day listed as a paid holiday, this remuneration is in addition to payment of the required prevailing rate for the work actually performed.

Overtime

At a minimum, all work performed on a public work project in excess of eight hours in any one day or more than five days in any workweek is overtime. However, the specific overtime requirements for each trade or occupation on a public work project may differ. Specific overtime requirements for each trade or occupation are contained in the prevailing rate schedules.

Overtime holiday pay is the premium pay that is required for work performed on specified holidays. It is only required where the employee actually performs work on such holidays.

The applicable holidays are listed under HOLIDAYS: OVERTIME. The required rate of pay for these covered holidays can be found in the OVERTIME PAY section listings for each classification.

Supplemental Benefits

Particular attention should be given to the supplemental benefit requirements. Although in most cases the payment or provision of supplements is straight time for all hours worked, some classifications require the payment or provision of supplements, or a portion of the supplements, to be paid or provided at a premium rate for premium hours worked. Supplements may also be required to be paid or provided on paid holidays, regardless of whether the day is worked. The Overtime Codes and Notes listed on the particular wage classification will indicate these conditions as required.

Effective Dates

When you review the schedule for a particular occupation, your attention should be directed to the dates above the column of rates. These are the dates for which a given set of rates is effective. The rate listed is valid until the next effective rate change or until the new annual determination which takes effect on July 1 of each year. All contractors and subcontractors are required to pay the current prevailing rates of wages and supplements. If you have any questions please contact the Bureau of Public Work or visit the New York State Department of Labor website (www.labor.ny.gov) for current wage rate information.

Apprentice Training Ratios

The following are the allowable ratios of registered Apprentices to Journey-workers.

For example, the ratio 1:1,1:3 indicates the allowable initial ratio is one Apprentice to one Journeyworker. The Journeyworker must be in place on the project before an Apprentice is allowed. Then three additional Journeyworkers are needed before a second Apprentice is allowed. The last ratio repeats indefinitely. Therefore, three more Journeyworkers must be present before a third Apprentice can be hired, and so on.

Please call Apprentice Training Central Office at (518) 457-6820 if you have any questions.

| Title (Trade) | Ratio |
|--|---------|
| Boilermaker (Construction) | 1:1,1:4 |
| Boilermaker (Shop) | 1:1,1:3 |
| Carpenter (Bldg.,H&H, Pile Driver/Dockbuilder) | 1:1,1:4 |
| Carpenter (Residential) | 1:1,1:3 |
| Electrical (Outside) Lineman | 1:1,1:2 |
| Electrician (Inside) | 1:1,1:3 |
| Elevator/Escalator Construction & Modernizer | 1:1,1:2 |
| Glazier | 1:1,1:3 |
| Insulation & Asbestos Worker | 1:1,1:3 |
| Iron Worker | 1:1,1:4 |
| Laborer | 1:1,1:3 |
| Mason | 1:1,1:4 |
| Millwright | 1:1,1:4 |
| Op Engineer | 1:1,1:5 |
| Painter | 1:1,1:3 |
| Plumber & Steamfitter | 1:1,1:3 |
| Roofer | 1:1,1:2 |
| Sheet Metal Worker | 1:1,1:3 |
| Sprinkler Fitter | 1:1,1:2 |
| | |

If you have any questions concerning the attached schedule or would like additional information, please contact the nearest BUREAU of PUBLIC WORK District Office or write to:

New York State Department of Labor Bureau of Public Work State Office Campus, Bldg. 12 Albany, NY 12240

| Telephone # | FAX# |
|--------------|--|
| 518-457-2744 | 518-485-0240 |
| 607-721-8005 | 607-721-8004 |
| 716-847-7159 | 716-847-7650 |
| 516-228-3915 | 516-794-3518 |
| 845-568-5287 | 845-568-5332 |
| 212-932-2419 | 212-775-3579 |
| 631-687-4882 | 631-687-4902 |
| 585-258-4505 | 585-258-4708 |
| 315-428-4056 | 315-428-4671 |
| 315-793-2314 | 315-793-2514 |
| 914-997-9507 | 914-997-9523 |
| 518-457-5589 | 518-485-1870 |
| | 518-457-2744 607-721-8005 716-847-7159 516-228-3915 845-568-5287 212-932-2419 631-687-4882 585-258-4505 315-428-4056 315-793-2314 914-997-9507 |

Saratoga County General Construction

Boilermaker 05/01/2023

JOB DESCRIPTION Boilermaker

DISTRICT 1

ENTIRE COUNTIES

Albany, Broome, Chenango, Columbia, Delaware, Essex, Fulton, Greene, Hamilton, Herkimer, Montgomery, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Tioga, Warren, Washington

WAGES

Per hour

07/01/2022 01/01/2023 01/01/2024 Additional Boilermaker \$ 39.34 \$ 40.09 + \$1.30

SUPPLEMENTAL BENEFITS

Per hour

Journeyperson \$ 25.65 \$25.95 + 1.24* + 1.49*

1th

OVERTIME PAY

See (B, E, Q, V) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE

Overtime: See (5, 6, 15, 25) on HOLIDAY PAGE

Note: When a holiday falls on Sunday, the day observed by the State or Nation shall be observed, and when Christmas Day and New Year's fall on Saturday, Friday will be observed as the holiday.

6th

7th

Qth

REGISTERED APPRENTICES

2nd

Wages per hour

(1/2) year terms at the following percentage of Journeyman's wage.

3rd

| 65% | 65% | 70% | 75% | 80% | 85% | 90% | 95% | |
|-------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|
| Supplementa | ıl Benefits per | hour | | | | | | |
| 07/01/2022 | 1st | 2nd | 3rd | 4th | 5th | 6th | 7th | 8th |
| 0170172022 | 19.15 +1.24* | 19.15 +1.24* | 20.08 +1.24* | 21.00 +1.24* | 21.93 +1.24* | 22.87 +1.24* | 23.79 +1.24* | 24.72 +1.24* |
| 01/01/2023 | 19.35 | 19.35 | 20.29 | 21.23 | 22.17 | 23.13 | 24.06 | 25.01 |
| | +1 49* | +1 49* | +1 49* | +1 49* | +1 49* | +1 49* | +1 49* | +1 49* |

5th

1-197

Carpenter - Building 05/01/2023

JOB DESCRIPTION Carpenter - Building

DISTRICT 2

ENTIRE COUNTIES

Albany, Fulton, Greene, Montgomery, Rensselaer, Saratoga, Schenectady, Schoharie

WAGES

| Per hour: | 07/01/2022 | 07/01/2023 | 07/01/2024 | 07/01/2025 |
|---------------|------------|------------|------------|------------|
| | | Additional | Additional | Additional |
| Carpenter | \$ 34.00 | \$ 1.25 | \$ 1.25 | \$ 1.25 |
| Floor Coverer | 34.00 | 1.25 | 1.25 | 1.25 |
| Carpet Layer | 34.00 | 1.25 | 1.25 | 1.25 |
| Dry-Wall | 34.00 | 1.25 | 1.25 | 1.25 |
| Diver-Wet Day | 61.25 | 0.00 | 0.00 | 0.00 |
| Diver-Dry Day | 35.00 | 1.25 | 1.25 | 1.25 |
| Diver Tender | 35.00 | 1.25 | 1.25 | 1.25 |

NOTE ADDITIONAL AMOUNTS PAID FOR THE FOLLOWING WORK LISTED BELOW (per hour worked):

^{*} This portion of the benefit is NOT subject to the SAME PREMIUM as shown for overtime.

^{*} This portion of the benefit is NOT subject to the SAME PREMIUM as shown for overtime.

⁻ Pile Drivers/Dock Builders shall receive \$0.25 per hour over the journeyman's rate of pay when performing piledriving/dock building work.

- Certified welders shall receive \$1.00 per hour over the journeyman's rate of pay when the employee is required to be certified and performs DOT or ABS specified welding work
- When an employee performs work within a contaminated area on a State and/or Federally designated hazardous waste site, and where relevant State and/or Federal regulations require employees to be furnished and use or wear required forms of personal protection, then the employee shall receive his regular hourly rate plus \$1.50 per hour.
- Depth pay for Divers based upon deepest depth on the day of the dive (per diem payment):

0' to 80' no additional fee

81' to 100' additional \$.50 per foot 101' to 150' additional \$0.75 per foot

151' and deeper additional \$1.25 per foot

- Penetration pay for Divers based upon deepest penetration on the day of the dive (per diem payment):

0' to 50' no additional fee

51' to 100' additional \$.75 per foot

101' and deeper additional \$1.00 per foot

- Diver rates applies to all hours worked on dive day.

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day.

NOTE - In order to use the '4 Day/10 Hour Work schedule', as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour:

Journeyman \$ 23.47

OVERTIME PAY

See (B, E, *E2, Q) on OVERTIME PAGE

* Note - Saturday is also payable at straight time if the employee misses work, except where a doctor's or hospital verification of illness is produced Monday through Friday when work was available to the employee.

HOLIDAY

Paid: See (1) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

Note: Any holiday which occurs on Sunday shall be observed the following Monday. If Christmas falls on a Saturday, it shall be observed on the prior Friday.

REGISTERED APPRENTICES

CARPENTER APPRENTICES

Wages per hour (1040 hour terms at the following percentage of journeyman's base wage):

1st 2nd 3rd 4th 5th 55% 60% 65% 70% 80%

Supplemental Benefits per hour:

\$ 12.31 \$ 12.31 \$ 14.96 \$ 14.96 \$ 14.96

PILEDRIVER/DOCK BUILDER APPRENTICES

Wages per hour (1300 hour terms at the following percentage of journeyman's base wage):

1st 2nd 3rd 4th 55%* 60%* 70%* 80%*

*Pile Driver/Dock Builder apprentices shall receive an additional \$0.25 per hour worked when performing piledriving/dock building work. Supplemental Benefits per hour:

\$ 12.31 \$ 12.31 \$ 14.96 \$ 14.96

LINOLEUM, RESILIENT TILE, AND CARPET LAYER APPRENTICES

Wages per hour (1300 hour terms at the following percentage of journeyman's base wage):

 1st
 2nd
 3rd
 4th

 55%
 60%
 70%
 80%

 Supplemental Benefits per hour:

\$ 12.31 \$ 12.31 \$ 14.96 \$ 14.96

ADDITIONAL AMOUNTS PAID PER HOUR WORKED TO APPRENTICES FOR SPECIFIC TYPES OF WORK PERFORMED:

- Certified welders shall receive \$1.00 per hour over the apprentices rate of pay when the apprentice is required to be certified and performs DOT or ABS specified welding work
- When an apprentice performs work within a contaminated area on a State and/or Federally designated hazardous waste site, and where relevant State and/or Federal regulations require the apprentice to be furnished and use or wear required forms of personal protection, then the apprentice shall receive his regular hourly rate plus \$1.50 per hour.

2-291B-Alb

JOB DESCRIPTION Carpenter - Building / Heavy&Highway

DISTRICT 2

DISTRICT 2

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orleans, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Wyoming, Yates

PARTIAL COUNTIES

Orange: The area lying on Northern side of Orange County demarcated by a line drawn from the Bear Mountain Bridge continuing west to the Bear Mountain Circle, continue North on 9W to the town of Cornwall where County Road 107 (also known as Quaker Rd) crosses under 9W, then east on County Road 107 to Route 32, then north on Route 32 to Orrs Mills Rd, then west on Orrs Mills Rd to Route 94, continue west and south on Route 94 to the Town of Chester, to the intersection of Kings Highway, continue south on Kings Highway to Bellvale Rd, west on Bellvale Rd to Bellvale Lakes Rd, then south on Bellvale Lakes Rd to Kain Rd, southeast on Kain Rd to Route 17A, then north and southeast along Route 17A to Route 210, then follow Route 210 to NJ Border.

WAGES

 Wages per hour:
 07/01/2022
 07/01/2023
 07/01/2024

 Additional
 Additional

 Carpenter - ONLY for Artificial Turf/Synthetic
 \$ 33.08
 \$ 2.25*

 Sport Surface
 \$ 33.08
 \$ 2.25*

Note - Does not include the operation of equipment. Please see Operating Engineers rates.

SUPPLEMENTAL BENEFITS

Per hour:

Journeyman \$ 25.45

OVERTIME PAY

See (B, E, Q, X) on OVERTIME PAGE

HOLIDAY

Paid: See (5) on HOLIDAY PAGE
Overtime: See (5, 6, 16) on HOLIDAY PAGE

Notes:

When a holiday falls upon a Saturday, it shall be observed on the preceding Friday. Whan a holiday falls upon a Sunday, it shall be observed on the following Monday.

An employee taking an unexcused day off the regularly scheduled day before or after a paid Holiday shall not receive Holiday pay.

REGISTERED APPRENTICES

Wages per hour (1300 hour terms at the following percentage of Journeyman's wage):

1st 2nd 3rd 4th 65% 70% 75% 80%

Supplemental Benefits per hour:

 1st term
 \$ 16.97

 2nd term
 17.41

 3rd term
 19.40

 4th term
 19.84

2-42AtSS

Carpenter - Heavy&Highway

05/01/2023

JOB DESCRIPTION Carpenter - Heavy&Highway

ENTIRE COUNTIES

Albany, Fulton, Greene, Montgomery, Rensselaer, Saratoga, Schenectady, Schoharie, Warren, Washington

WAGES

| Per hour | 07/01/2022 | 07/01/2023 | 07/01/2024 |
|---------------|------------|------------|------------|
| | | Additional | Additional |
| Carpenter | \$ 37.52 | \$ 3.75* | \$ 4.00* |
| Piledriver | 37.52 | 3.75* | 4.00* |
| Diver-Wet Day | 62.52 | 3.75* | 4.00* |
| Diver-Dry Day | 38.52 | 3.75* | 4.00* |
| Diver-Tender | 38.52 | 3.75* | 4.00* |

^{*}To be allocated at a later date.

NOTE ADDITIONAL AMOUNTS PAID FOR THE FOLLOWING WORK LISTED BELOW (per hour worked):

^{*}To be allocated at a later date

- When project owner mandates a single irregular work shift, the employee will receive an additional \$3.00 per hour. A single irregular work shift can start any time from 5:00 p.m. to 1:00 a.m.
- State or Federal designated hazardous site, requiring protective gear shall be an additional \$2.50 per hour.
- Certified welders when required to perform welding work will receive an additional \$2.50 per hour.

ADDITIONAL NOTES PERTAINING TO DIVERS/TENDERS:

- Divers and Tenders shall receive one and one half (1 1/2) times their regular diver and tender rate of pay for Effluent and Slurry diving.
- Divers and tenders being paid at the specified rate for Effluent and Slurry diving shall have all overtime rates based on the specified rate plus the appropriate overtime rates (one and one half or two times the specified rate for Slurry and Effluent divers and tenders).
- The pilot of an ADS or submersible will receive one and one-half (1 1/2) times the Diver-Wet Day Rate for time submerged.
- All crew members aboard a submersible shall receive the Diver-Wet Day rate.
- Depth pay for Divers based upon deepest depth on the day of the dive (per diem payment):

0' to 50' no additional fee

51'to 100' additional \$.50 per foot 101'to 150' additional \$0.75 per foot 151'and deeper additional \$1.25 per foot

- Penetration pay for Divers based upon deepest penetration on the day of the dive (per diem payment):

0' to 50' no additional fee

51' to 100' additional \$.75 per foot

101' and deeper additional \$1.00 per foot

- Diver rates applies to all hours worked on dive day.

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Friday, provided the project duration is more than forty (40) hours.

NOTE - In order to use the '4 Day/10 Hour Work schedule', as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour:

Journeyman \$ 23.80

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

- In the event a Holiday falls on a Saturday, the Friday before will be observed as a Holiday. If a Holiday falls on a Sunday, then Monday will be observed as a Holiday. Employee must work scheduled work day before and after the Holiday.
- The employee must work their scheduled workday before and their scheduled workday after the holiday to receive holiday pay.

REGISTERED APPRENTICES

CAPRENTER APPRENTICES

Wages per hour (1040 hour terms at the following percentage of journeyman's base wage):

1st 2nd 3rd 4th 5th 65% 70% 75% 80% 85%

Supplemental Benefits per hour:

\$ 18.11 \$ 18.65 \$ 20.73 \$ 21.27 \$ 21.81

PILEDRIVER/DOCKBUILDER APPRENTICES

Wages per hour (1300 hour terms at the following percentage of journeyman's base wage):

1st 2nd 3rd 4th 65% 70% 80% 85% Supplemental Benefits per hour:

\$ 18.11 \$ 18.65 \$ 21.27 \$ 21.81

NOTE ADDITIONAL AMOUNTS PAID PER HOUR WORKED TO APPRENTICES FOR SPECIFIC TYPES OF WORK PERFORMED:

- When project owner mandates a single irregular work shift, the employee will receive an additional \$3.00 per hour. A single irregular work shift can start any time from 5:00 p.m. to 1:00 a.m.
- State or Federal designated hazardous site, requiring protective gear shall be an additional \$2.50 per hour.
- Certified welders when required to perform welding work will receive an additional \$2.50 per hour.

2-291HH-Alb

Electrician 05/01/2023

JOB DESCRIPTION Electrician

DISTRICT 1

ENTIRE COUNTIES

Albany, Columbia, Fulton, Hamilton, Montgomery, Rensselaer, Saratoga, Schenectady, Schoharie, Warren, Washington

PARTIAL COUNTIES

Greene: Portion of the County North of a line following the South limits of the City of Catskill in a westerly direction from the Hudson River to State Highway 23A. Then continuing on 23A to the road following the Little West Kill and continuing along this road to Delaware County. Otsego: Only the Towns of Decatur and Worchester

WAGES

Per hour

| 07/01/2022 | 06/01/2023 |
|------------|-------------------------|
| \$ 45.00 | \$ 47.12 |
| 45.00 | 47.12 |
| 45.00 | 47.12 |
| 45.00 | 47.12 |
| 45.00 | 47.12 |
| | 45.00 45.00 45.00 |

Notes: An additional 5% above rate for work over 30' above floor and requires use of a safety harness when working on tooth picks, structural steel, temporary platforms, swing scaffolds & boatswain chairs. All OSHA approved lifts are excluded.

An additional 10% above rate on towers & smoke stacks over 100' high.

An additional 20% above rate in shafts over 25' deep or tunnels over 50' long that are under construction.

An additional 5% above rate when Journeymen are required to work as Lead(Pb) cable splicers.

An additional 10% above rate when Journeymen Welders are required to have ASME verification.

SUPPLEMENTAL BENEFITS

Per hour

Journeyman \$ 29.24 \$ 29.29 +3% of wage +3% of wage

OVERTIME PAY

See (B, *E, Q) on OVERTIME PAGE

For Projects Bid on or Prior to 05/31/2019

NOTE: THE FOLLOWING RATES WILL APPLY ON ALL CONTRACTING AGENCY MANDATED SHIFTS OF AT LEAST A FIVE (5) DAY DURATION WORKED BETWEEN THE HOURS LISTED BELOW:

WORKED BETWEEN THE HOURS LISTED BELOW.

 1st Shift
 8:00 AM to 4:30 PM
 REGULAR RATE

 2nd Shift
 4:30 PM to 1:00 AM
 REGULAR RATE PLUS 10%

2nd Shift 4:30 PM to 1:00 AM REGULAR RATE PLUS 10% 3rd Shift 12:30 AM to 9:00 AM REGULAR RATE PLUS 15%

For Projects Bid on or After 06/01/2019

1st Shift 8:00 AM to 4:30 PM REGULAR RATE

2nd Shift 4:30 PM to 1:00 AM REGULAR RATE PLUS 17.3% 3rd Shift 12:30 AM to 9:00 AM REGULAR RATE PLUS 31.4%

For Projects Bid on or After 09/01/2019

NOTE: THE FOLLOWING RATES WILL APPLY ON ALL CONTRACTING AGENCY MANDATED SINGLE IRREGULAR SHIFTS OF AT LEAST A FIVE (5) DAY DURATION WORKED BETWEEN THE HOURS LISTED BELOW:

1st Shift 8:00 AM to 4:30 PM REGULAR RATE

 2nd Shift
 4:30 PM to 1:00 AM
 REGULAR RATE PLUS 17.3%

 3rd Shift
 12:30 AM to 9:00 AM
 REGULAR RATE PLUS 31.4%

HOLIDAY

Paid: See (1) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

Note: If the holiday falls on Saturday, it shall be celebrated on Friday. If the holiday falls on Sunday, it shall be celebrated on Monday.

REGISTERED APPRENTICES

Wages per hour

Terms at the following percentage of Journeyman's wage.

0-6mo 6-12mo 2nd yr 3rd yr 4th yr 5th yr 40% 45% 50% 60% 70% 80%

Notes: An additional 5% above rate for work over 30' above floor and requires use of a safety harness when working on tooth picks, structural steel, temporary platforms, swing scaffolds & boatswain chairs. All OSHA approved lifts are excluded.

An additional 10% above rate on towers & smoke stacks over 100' high.

An additional 20% above rate in shafts over 25' deep or tunnels over 50' long that are under construction.

Supplemental Benefits per hour worked

Apprentices indentured on or before 12/31/2018

^{*} DOUBLE TIME AFTER 10 HOURS ON SATURDAY

0-12 month term \$ 14.66* 2-5th year term \$ 29.24*

Apprentices indentured on or after 01/01/2019

 0-12 month term
 \$ 14.66*

 2nd year term
 23.52*

 3rd year term
 24.66*

 4th year term
 25.81*

 5th year term
 29.24*

*Plus additional 3% of wage

1-236

Elevator Constructor 05/01/2023

JOB DESCRIPTION Elevator Constructor

DISTRICT 1

ENTIRE COUNTIES

Albany, Clinton, Essex, Fulton, Hamilton, Herkimer, Montgomery, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Warren, Washington

PARTIAL COUNTIES

Madison: Madison Only the towns of: Brookfield, Hamilton, Lincoln, Madison, Smithfield, Stockbridge and the City of Oneida Oneida: Entire county except the towns of: Camden, Florence, and Vienna.

WAGES

Per hour

07/01/2022 01/01/2023

Mechanic \$50.78 \$53.02

Helper 70% of Mechanic 70% of Mechanic Wage Rate Wage Rate

Four (4), ten (10) hour days may be worked for New Construction and Modernization Work at straight time during a week, Monday thru Thursday or Tuesday thru Friday.

NOTE - In order to use the '4 Day/10 Hour Work schedule', as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour

07/01/2022 01/01/2023

Journeyperson/Helper

(*)Plus 6% of hourly rate, if less than 5 years of service. Plus 8% of hourly rate, if more than 5 years of service.

OVERTIME PAY

See (D, O) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6, 15, 16) on HOLIDAY PAGE Overtime: See (5, 6, 15, 16) on HOLIDAY PAGE

Note: When a paid holiday falls on Saturday, it shall be observed on Friday. When a paid holiday falls on Sunday, it shall be observed on

Monday.

REGISTERED APPRENTICES

Wages per hour:

0-6 mo* 6-12 mo 2nd yr 3rd yr 4th yr 50% 55 % 65 % 70 % 80 %

(*)Plus 6% of the hourly rate, no additional supplemental benefits.

Supplemental Benefits - per hour worked:

Same as Journeyperson/Helper

^{***}Four (4), ten (10) hour days are not permitted for Contract Work/Repair Work

Glazier 05/01/2023

JOB DESCRIPTION Glazier

DISTRICT 1

ENTIRE COUNTIES

Albany, Clinton, Columbia, Essex, Franklin, Fulton, Greene, Hamilton, Montgomery, Rensselaer, Saratoga, Schenectady, Schoharie, Warren, Washington

WAGES

Per hour

07/01/2022 05/01/2023 07/01/2023 Additional

Glazier Base Wage \$ 31.86* \$ 32.16**

*plus additional \$4.05 per hour for all hours worked, not subject to overtime/premium
**plus additional \$4.10 per hour for all hours worked, not subject to overtime/premium

High Work Base Wage*** 34.01 +\$1.55

+ additional \$4.05 per hour for all hours worked, not subject to overtime/premium

(***)When working on Swing Stage or Lift 100 feet or more in height, measured from the ground level up.

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day. NOTE - In order to use the 4 Day/10 Hour Work schedule, as your normal schedule, you must submit an Employer Registration for Use of 4 Day/10 Hour Work Schedule, form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour

 Journeyman
 \$ 21.75
 \$ 22.65

 Journeyman High Work
 27.65
 27.65

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

Premium is applied to the respective base wage only.

THE FOLLOWING RATES WILL APPLY ON ALL CONTRACTING AGENCY MANDATED SHIFT WORK OR SINGLE IRREGULAR SHIFTS STARTING BETWEEN THE HOURS LISTED BELOW:

4:00pm to 6:30am: ADDITIONAL 12.5% TO APPLICABLE WAGE RATE

AND SUPPLEMENTAL BENEFIT

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

Note: If any of the holidays are designated by federal law to be celebrated on a day other than that on which they regularly fall, then the holiday shall be celebrated on the day set by said federal law as if the day on which the holiday is celebrated was actually the holiday date.

REGISTERED APPRENTICES

Wages per hour

Apprentice Glazier 1500 hr. terms at the following percentage of Journeymans base wage.

1st 2nd 3rd 4th 50% 65% 75% 90%

+ additional \$4.10 per hour for all hours worked for all terms

Apprentice Glazier Hi-Work 1500 hr. terms at the following percentage of Journeymans Hi-Work base wage.

1st 2nd 3rd 4th 50% 65% 75% 90%

+ additional \$4.05 per hour for all hours worked for all terms

Supplemental Benefits per hour worked

Apprentice

| 1st term | \$ 18.08 | \$ 18.98 |
|----------------------|----------|----------|
| 2nd-4th term | 21.75 | 22.65 |
| Apprentice High Work | | |
| 1st term | 21.28 | 21.28 |
| 2nd-4th term | 27.65 | 27.65 |

1-201

Insulator - Heat & Frost 05/01/2023

JOB DESCRIPTION Insulator - Heat & Frost

DISTRICT 1

ENTIRE COUNTIES

Albany, Columbia, Delaware, Essex, Fulton, Greene, Hamilton, Montgomery, Rensselaer, Saratoga, Schenectady, Schoharie, Sullivan, Ulster, Warren, Washington

WAGES

| Wages per hour | 07/01/2022 | 05/01/2023 | 05/01/2024 Additional |
|----------------------|------------|------------|--------------------------|
| Asbestos Worker* | \$ 38.40 | \$ 39.68 | +\$2.00 |
| Insulator* | 38.40 | 39.68 | |
| Firestopping Worker* | 32.64 | 33.73 | |

(*)On Mechanical Systems only.

On government mandated shift work additional 12% of wage for all shifts starting after 3:30 P.M.

SUPPLEMENTAL BENEFITS

Per hour

Journeyperson \$ 24.42 \$ 25.64

OVERTIME PAY

See (*B1, **Q) on OVERTIME PAGE

*B1=Double time begins after 10 hours on Saturday

HOLIDAY

Paid: See (1) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

When a holiday falls on Sunday the following Monday shall be observed as the holiday.

REGISTERED APPRENTICES

Wages per hour

one year terms at the following percentage of Journeyperson's wage.

1st 2nd 3rd 4th 60 % 70 % 80 % 90 %

Supplemental Benefits per hour worked:

Apprentices \$ 24.42 \$ 25.64

1-40

Ironworker 05/01/2023

JOB DESCRIPTION Ironworker

DISTRICT 1

ENTIRE COUNTIES

Albany, Clinton, Columbia, Delaware, Essex, Greene, Rensselaer, Saratoga, Schenectady, Schoharie, Warren, Washington

PARTIAL COUNTIES

Fulton: Only the Townships of Broadalbin, Mayfield, Northampton, Bleecker and Johnstown.

Hamilton: Ónly the Townships of Hope, Benson and Wells.

Montgomery: Only the Townships of Florida, Amsterdam, Charleston, Glen, Mohawk and Root.

Otsego: Only the Towns of Unadilla, Butternuts, Morris, Otego, Oneonta, Laurens, Millford, Maryland and Worchester.

WAGES

| Wages Per hour | 07/01/2022 |
|------------------------|------------|
| Ornamental | \$ 33.50 |
| Reinforcing | 33.50 |
| Rodman | 33.50 |
| Structural & Precast | 33.50 |
| Mover/Rigger | 33.50 |
| Fence Erector | 33.50 |
| Stone Derrickman | 33.50 |
| Sheeter | 33.75 |
| Curtain Wall Installer | 33.50 |

^{**}Q=Triple time on Labor Day if worked.

1-12

Metal Window Installer 33.50

SUPPLEMENTAL BENEFITS

Per hour

JOURNEYPERSON \$31.14

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

THE FOLLOWING RATES WILL APPLY ON ALL CONTRACTING AGENCY MANDATED MULTIPLE SHIFTWORK:

1st Shift 6:00 AM to 4:30 PM REGULAR RATE

2nd Shift 2:00 PM to 7:00 PM REGULAR RATE PLUS 10% 3rd Shift 7:00 PM to 12:00 AM REGULAR RATE PLUS 15%

THE FOLLOWING RATE WILL APPLY ON ALL CONTRACTING AGENCY MANDATED SINGLE IRREGULAR SHIFTS:

Shift Starting 4:30 PM to 12:00 AM REGULAR RATE PLUS 10%

HOLIDAY

Paid: See (1) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

Note: Any holiday which occurs on Sunday shall be observed the following Monday.

REGISTERED APPRENTICES

Wages per hour

ONE YEAR TERMS AT THE FOLLOWING WAGE RATES:

| | 07/01/2022 |
|--|-------------------------------------|
| 1st year 2nd year 3rd year 4th year | \$ 19.50 21.50 23.50 25.50 |
| Supplemental Benefits per hour worked | |
| 1st year | \$ 11.78 |
| 2nd year | 23.73 |
| 3rd year | 25.42 |
| 4th year | 27.13 |

Laborer - Building 05/01/2023

JOB DESCRIPTION Laborer - Building DISTRICT 1

ENTIRE COUNTIES

Albany, Rensselaer, Washington

PARTIAL COUNTIES

Columbia: Only the Townships of Stuyvesant, Stockport, Kinderhook, New Lebanon, Canaan, Ghent, Chatham and Austerlitz.

Greene: Entire county except the Township of Catskill

Saratoga: Only the Townships of Halfmoon, Saratoga, Stillwater, Waterford, and the City of Mechanicville.

WAGES

Per hour

07/01/2022 07/01/2023 Additional

Group #1:

All Classifications \$ 32.86 +\$2.35

except as noted in Groups 2 & 3

Group #2:

Blaster, Drilling Equipment Only Where a Separate Air Compressor Unit Supplies Power, Metal Formsetter sidewalk), Well Pointing

& Laser Operator 33.36

Group #3:

Handling of Asbestos

or Toxic Materials 34.21

SUPPLEMENTAL BENEFITS

Per hour

\$ 24.87 Journeyman

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE See (5, 6) on HOLIDAY PAGE Overtime:

REGISTERED APPRENTICES

Wages per hour

1000 Hour terms at the following percentage of Journeyman's basic hourly wage.

1st 2nd 3rd 4th 70 % 80 % 80 % 65 %

Supplemental Benefits per hour worked

Apprentices \$ 24.87

1-190

05/01/2023 **Laborer - Building**

JOB DESCRIPTION Laborer - Building

ENTIRE COUNTIES Schenectady, Schoharie

PARTIAL COUNTIES

Fulton: Only the Townships of Bleeker, Mayfield, Northampton, Johnstown, Broadalbin and Perth.

Montgomery: Only the Townships of Mohawk, Glen, Charleston, Amsterdam, and Florida.

Saratoga: Only the Townships of Day, Hadley, Edinburg, Corinth, Moreau, South Glens Falls, Providence, Greenfield, Wilton, Galway, Northumberland, Milton, Saratoga Springs, Charlton, Ballston, Malta and Clifton Park.

WAGES

Per hour

07/01/2022 07/01/2023

Additional

Group #1:

All Classifications \$ 34.54 + \$2.35

except as noted in Groups 2 & 3

Group #2:

Blaster, Drilling equipment only where a separate air compressor unit supplies power, Metal formsetter (sidewalk),

Well pointing & Laser

operator \$ 35.04

Group #3:

Handling of Asbestos

or Toxic Materials \$35.89

SUPPLEMENTAL BENEFITS

Per hour

Journeyman \$23.11

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

See (1) on HOLIDAY PAGE Paid: See (5, 6) on HOLIDAY PAGE Overtime:

REGISTERED APPRENTICES

Wages per hour

1000 Hour terms at the following percentage of Journeyman's basic hourly wage.

1st 2nd 3rd 4th 65 % 70 % 80 % 80 %

Supplemental Benefits per hour worked

07/01/2022

Apprentices \$ 23.11

1-157

Laborer - Heavy&Highway

05/01/2023

JOB DESCRIPTION Laborer - Heavy&Highway

DISTRICT 1

ENTIRE COUNTIES

Albany, Rensselaer, Washington

PARTIAL COUNTIES

Columbia: Only the Townships of Stuyvesant, Stockport, Kinderhook, New Lebanon, Canaan, Ghent, Chatham, and Austerlitz

Greene: Entire county except the Township of Catskill.

Saratoga: Only the Townships of Halfmoon, Saratoga, Stillwater, Waterford, and the City of Mechanicville.

WAGES

GROUP # A:

Basic, Drill Helper, Flagman, Outboard and Hand Boats

GROUP # B:

Chain Saw, Concrete Aggregate Bin, Concrete Bootmen, Gin Buggy, Hand or Machine Vibrator, Jack Hammer, Mason Tender, Mortar Mixer, Pavement Breaker, Handlers of Steelmesh, Small Generators for Laborers' Tools, Installation of Bridge Drainage Pipe, Pipe Layers, Vibrator Type Rollers, Tamper, Drill Doctor, Tail or Screw Operator on Asphalt Paver, Water Pump Operators(1-1/2" and Single Diaphragm) Nozzle (Asphalt, Gunite, Seeding and Sand Blasting), Laborers on Chain Link Fence. Rock Splitter and Power Unit, Pusher Type Concrete Saw and all other Gas, Electric, Oil and Air Tool Operators, Wrecking Laborer.

GROUP # C:

Drilling Equipment Only Where a Separate Air Compressor Unit Supplies Power, Acetylene Torch Operators, Asphalt Raker and Powderman.

GROUP # D:

Blasters, Metal Form Setters(sidewalk), Stone or Granite Curb Setters.

GROUP # E:

Employees performing hazardous waste removal, lead abatement and removal, or asbestos abatement and removal on a State and/or Federally designated waste site & where relevant State or Federal regulations require employees to use or wear forms of personal protection.

WAGES per hour

| · | 07/01/2022 | 07/01/2023 Additional |
|-----------|------------|--------------------------|
| Group # A | \$ 37.19 | \$ 3.50 |
| Group # B | 37.39 | |
| Group # C | 37.59 | |
| Group # D | 37.79 | |
| Group # E | 39.69 | |

All employees who work a single irregular work day that starts from 5:00 pm to 1:00 am on a governmental mandated night shift shall be paid an additional \$5.00 per hour.

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day.

NOTE - In order to use the '4 Day/10 Hour Work schedule', as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour

Journeyman \$ 25.40

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

Note: If the holiday falls on Sunday, it will be celebrated on Monday. If the Holiday falls on a Saturday employer can choose to celebrate Saturday or give Friday off with pay.

REGISTERED APPRENTICES

Wages per hour

1000 hour terms at the following percentage of Journeyman's wage

3rd 4th 1st 2nd 65% 70% 80% 80%

Supplemental Benefits per hour worked

Apprentices \$ 25.40

1-190 h/h

Laborer - Heavy&Highway

05/01/2023

JOB DESCRIPTION Laborer - Heavy&Highway

DISTRICT 1

ENTIRE COUNTIES

Schenectady, Schoharie

PARTIAL COUNTIES

Fulton: Only the Townships of Bleeker, Mayfield, Northampton, Johnstown, Broadalbin and Perth. Montgomery: Only the Townships of Mohawk, Glen, Charleston, Amsterdam, and Florida.

Saratoga: Only the Townships of Day, Hadley, Edinburg, Corinth, Moreau,South Glens Falls, Providence, Greenfield, Wilton, Galaway,

Northumberland, Milton, Saratoga Springs, Charlton, Ballston, Malta and Clifton Park

WAGES

GROUP # A:

Basic, Drill Helper, Flagman, Outboard and Hand Boats.

GROUP # B:

Chain Saw, Concrete Aggregate Bin, Concrete Bootmen, Gin Buggy, Hand or Machine Vibrator, Jack Hammer, Mason Tender, Mortar Mixer, Pavement Breaker, Handlers of Steelmesh, Small Generators for Laborers, Tools Installation of Bridge Drainage Pipe, Pipe Layers, Vibrator Type Rollers, Tamper, Drill Doctor, Tail or Screw Operator on Asphalt Paver, Water Pump Operators(1-1/2" and Single Diaphragm) Nozzle (Asphalt, Gunite, Seeding, and Sand Blasting), Laborers on Chain Link Fence, Rock Splitter and Power Unit, Pusher Type Concrete Saw and all other Gas, Electric, Oil and Air Tool Operators, Wrecking Laborer.

GROUP # C:

Drilling Equipment Only Where a Separate Air Compressor Unit Supplies Power, Acetylene Torch Operators, Asphalt Paver/Raker and Powderman.

GROUP # D:

Blasters, Metal Form Setters (sidewalk), Stone or Granite Curb Setters.

GROUP # E:

Employees performing hazardous waste removal, lead abatement and removal, or asbestos abatement and removal on a State and/or Federally designated waste site & where relevant State or Federal regulations require employees to use or wear forms of personal protection.

| WAGES per hour | 07/01/2022 | 07/01/2023 Additional |
|------------------------|----------------|--------------------------|
| Group # A | \$ 36.60 | \$ 3.50 |
| Group # B | 36.80 | |
| Group # C | 37.00 | |
| Group # D | 37.20 | |
| Group # E | 39.10 | |
| Group # C Group # D | 37.00 37.20 | |

All employees who work a single irregular work day that starts from 5:00 pm to 1:00 am on a governmental mandated night shift shall be paid an additional \$5.00 per hour.

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day.

NOTE - In order to use the '4 Day/10 Hour Work schedule', as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour

Journeyman \$ 25.99

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

Note: If the holiday falls on Sunday, it will be celebrated on Monday. If the Holiday falls on a Saturday employer can choose to celebrate

Saturday or give Friday off with pay.

REGISTERED APPRENTICES

Wages per hour

1000 HOUR TERMS AT THE FOLLOWING PERCENTAGE OF JOURNEYMAN'S BASE WAGE

1ST 2ND 3RD 4TH 65 % 70 % 80 % 80 %

Supplemental Benefits per hour worked

07/01/2022

Apprentices \$ 25.99

1-157h/h

Laborer - Tunnel 05/01/2023

JOB DESCRIPTION Laborer - Tunnel

ENTIRE COUNTIES

Albany, Fulton, Hamilton, Herkimer, Madison, Montgomery, Oneida, Rensselaer, Saratoga, Schenectady, Schoharie, Washington

WAGES

Class 1: All support laborers/sandhogs working above the shaft or tunnel

Class 2: All laborers/sandhogs working in the shaft or tunnel

Class 4: Safety Miners

Class 5: Site work related to Shaft/Tunnel

Class A: Mole nipper, powder handler, changehouse attendant and top laborer, Air spade, jackhammer, pavement breaker, Top bell, Bottom bell, side or roofbelt driller, maintenance men, burners, block layers, rodmen, caulkers, miners helper, trackmen, nippers, derailmen, electrical cablemen, hosemen, groutmen, gravelmen, form workers, movers and shaftmen, conveyor men.

Class B: Powder monkey, Blasters, ironmen and cement worker, miner, welder, heading driller, steel erectors, piledriver, rigger

Per Hour

07/01/2022

*For projects bid on or after May 1, 2019

Class 1 \$ 43.50 Class 2 45.50 Class 4 47.75 Class 5 38.25

Toxic and hazardous waste, lead abatement and asbestos abatement work will be paid an additional \$ 3.00 an hour.

*For projects bid on or before April 30, 2019

Class A \$ 40.80 Class B 41.80

Toxic and hazardous waste, lead abatement and asbestos abatement work will be paid an additional \$ 2.00 an hour.

SUPPLEMENTAL BENEFITS

Per hour

*For projects bid on or after May 1, 2019

Journeyman \$ 27.50

*For projects bid on or before April 30, 2019

Journeyman \$ 26.75

OVERTIME PAY

See (B, E, Q, V, X) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6, 15, 25) on HOLIDAY PAGE
Overtime: See (5, 6, 15, 16, 25) on HOLIDAY PAGE
Note: If the holiday falls on a Sunday, it will be celebrated on Monday.
If the holiday falls on a Saturday, it will be celebrated on Friday.

REGISTERED APPRENTICES

FOR APPRENTICE RATES, refer to the appropriate Laborer Heavy & Highway wage rate contained in the wage schedule for the County and Location where the work is to be performed.

1-190/157T

Lineman Electrician 05/01/2023

JOB DESCRIPTION Lineman Electrician

DISTRICT 6

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Dutchess, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orange, Orleans, Oswego, Otsego, Putnam, Rensselaer, Rockland, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Wyoming, Yates

WAGES

A Lineman/Technician shall perform all overhead aerial work. A Lineman/Technician on the ground will install all electrical panels, connect all grounds, install and connect all electrical conductors, assembly of all electrical materials, conduit, pipe, or raceway; placing of fish wire; pulling of cables, wires or fiber optic cable through such raceways; splicing of conductors; dismantling of such structures, lines or equipment.

A Groundman/Truck Driver shall: Build and set concrete forms, handle steel mesh, set footer cages, transport concrete in a wheelbarrow, hand or machine concrete vibrator, finish concrete footers, mix mortar, grout pole bases, cover and maintain footers while curing in cold weather, operate jack hammer, operate hand pavement breaker, tamper, concrete and other motorized saws, as a drill helper, operate and maintain generators, water pumps, chainsaws, sand blasting, operate mulching and seeding machine, air tools, electric tools, gas tools, load and unload materials, hand shovel and/or broom, prepare and pour mastic and other fillers, assist digger operator/equipment operator in ground excavation and restoration, landscape work and painting. Only when assisting a lineman technician, a groundman/truck driver may assist in installing conduit, pipe, cables and equipment.

NOTE: Includes Teledata Work within ten (10) feet of High Voltage Transmission Lines. Also includes digging of holes for poles, anchors, footer, and foundations for electrical equipment.

Below rates applicable on all overhead and underground distribution and maintenance work, and all overhead and underground transmission line work and the installation of fiber optic cable where no other construction trades are or have been involved. (Ref #14.01.01)

| Per hour: | 07/01/2022 | 05/01/2023 | 05/06/2024 |
|-------------------------|------------|------------|------------|
| Lineman, Technician | \$ 56.00 | \$ 57.40 | \$ 58.90 |
| Crane, Crawler Backhoe | 56.00 | 57.40 | 58.90 |
| Welder, Cable Splicer | 56.00 | 57.40 | 58.90 |
| Digging Mach. Operator | 50.40 | 51.66 | 53.01 |
| Tractor Trailer Driver | 47.60 | 48.79 | 50.07 |
| Groundman, Truck Driver | 44.80 | 45.92 | 47.12 |
| Equipment Mechanic | 44.80 | 45.92 | 47.12 |
| Flagman | 33.60 | 34.44 | 35.34 |

Additional \$1.00 per hour for entire crew when a helicopter is used.

Below rates applicable on all electrical sub-stations, switching structures, fiber optic cable and all other work not defined as "Utility outside electrical work". (Ref #14.02.01-A)

| Lineman, Technician | \$ 56.00 | \$ 57.40 | \$ 58.90 |
|-------------------------|----------|----------|----------|
| Crane, Crawler Backhoe | 56.00 | 57.40 | 58.90 |
| Cable Splicer | 61.60 | 63.14 | 64.79 |
| Certified Welder - | | | |
| Pipe Type Cable | 58.80 | 60.27 | 61.85 |
| Digging Mach. Operator | 50.40 | 51.66 | 53.01 |
| Tractor Trailer Driver | 47.60 | 48.79 | 50.07 |
| Groundman, Truck Driver | 44.80 | 45.92 | 47.12 |
| Equipment Mechanic | 44.80 | 45.92 | 47.12 |

Flagman 33.60 34.44 35.34

Additional \$1.00 per hour for entire crew when a helicopter is used.

Below rates apply on switching structures, maintenance projects, railroad catenary install/maintenance third rail installation, bonding of rails and pipe type cable and installation of fiber optic cable. (Ref #14.02.01-B)

| Lineman, Tech, Welder | \$ 57.32 | \$ 58.72 | \$ 60.22 |
|-------------------------|----------|----------|----------|
| Crane, Crawler Backhoe | 57.32 | 58.72 | 60.22 |
| Cable Splicer | 63.05 | 64.59 | 66.24 |
| Certified Welder - | | | |
| Pipe Type Cable | 60.19 | 61.66 | 63.23 |
| Digging Mach. Operator | 51.59 | 52.85 | 54.20 |
| Tractor Trailer Driver | 48.72 | 49.91 | 51.19 |
| Groundman, Truck Driver | 45.86 | 46.98 | 48.18 |
| Equipment Mechanic | 45.86 | 46.98 | 48.18 |
| Flagman | 34.39 | 35.23 | 36.13 |

Additional \$1.00 per hour for entire crew when a helicopter is used.

Below rates applicable on all overhead and underground transmission line work & fiber optic cable where other construction trades are or have been involved. This applies to transmission line work only, not other construction. (Ref #14.03.01)

| Lineman, Tech, Welder | \$ 58.51 | \$ 59.91 | \$ 61.41 |
|-------------------------|----------|----------|----------|
| Crane, Crawler Backhoe | 58.51 | 59.91 | 61.41 |
| Cable Splicer | 58.51 | 59.91 | 61.41 |
| Digging Mach. Operator | 52.66 | 53.92 | 55.27 |
| Tractor Trailer Driver | 49.73 | 50.92 | 52.20 |
| Groundman, Truck Driver | 46.81 | 47.93 | 49.13 |
| Equipment Mechanic | 46.81 | 47.93 | 49.13 |
| Flagman | 35.11 | 35.95 | 36.85 |

Additional \$1.00 per hour for entire crew when a helicopter is used.

NOTE: THE FOLLOWING RATES WILL APPLY ON ALL CONTRACTING AGENCY MANDATED MULTIPLE SHIFTS OF AT LEAST FIVE (5) DAYS DURATION WORKED BETWEEN THE HOURS LISTED BELOW:

1ST SHIFT 8:00 AM to 4:30 PM REGULAR RATE

2ND SHIFT 4:30 PM to 1:00 AM REGULAR RATE PLUS 17.3 % 3RD SHIFT 12:30 AM to 9:00 AM REGULAR RATE PLUS 31.4 %

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day. Tuesday thru Friday may be worked with no make-up day.

NOTE - In order to use the '4 Day/10 Hour Work schedule', as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour worked (but also required on non-worked holidays):

| | 07/01/2022 | 05/01/2023 | 05/06/2024 |
|--|--|--|--|
| Journeyman | \$ 25.90 *plus 7% of the hourly wage paid | \$ 26.40 *plus 7% of the hourly wage paid | \$ 26.90 *plus 7% of the hourly wage paid |
| Journeyman Lineman or Equipment Operators with Crane License | \$ 27.90 *plus 7% of the hourly wage paid | \$ 29.40 *plus 7% of the hourly wage paid | \$ 30.90 *plus 7% of the hourly wage paid |

^{*}The 7% is based on the hourly wage paid, straight time or premium time.

OVERTIME PAY

See (B, E, Q,) on OVERTIME PAGE. *Note* Double time for all emergency work designated by the Dept. of Jurisdiction.

NOTE: WAGE CAP - Double the straight time hourly base wage shall be the maximum hourly wage compensation for any hour worked. Contractor is still responsible to pay the hourly benefit amount for each hour worked.

HOLIDAY

Paid See (5, 6, 8, 13, 25) on HOLIDAY PAGE plus Governor of NYS Election Day.

Overtime See (5, 6, 8, 13, 25) on HOLIDAY PAGE plus Governor of NYS Election Day.

NOTE: All paid holidays falling on Saturday shall be observed on the preceding Friday. All paid holidays falling on Sunday shall be observed on the following Monday. Supplements for holidays paid at straight time.

REGISTERED APPRENTICES

WAGES per hour: 1000 hour terms at the following percentage of the applicable Journeyman Lineman wage.

| 1st | 2nd | 3rd | 4th | 5th | 6th | 7th | |
|-------|--------------|---------------|-----------|----------|----------|-----|-------------|
| 60% | 65% | 70% | 75% | 80% | 85% | 90% | |
| SUPPL | LEMENTAL BEN | EFITS per hou | ır: | | | | |
| | | · | 07/01/20 | 022 | 05/01/2 | 023 | 05/06/2024 |
| | | | \$ 25.90 |) | \$ 26.4 | 0 | \$ 26.90 |
| | | | *plus 7% | of | *plus 7% | of | *plus 7% of |
| | | | the hourl | V | the hour | lv. | the hourly |

wage paid

6-1249a

Lineman Electrician - Teledata 05/01/2023

wage paid

JOB DESCRIPTION Lineman Electrician - Teledata

DISTRICT 6

wage paid

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Dutchess, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orange, Orleans, Oswego, Otsego, Putnam, Rensselaer, Rockland, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Westchester, Wyoming, Yates

WAGES

Per hour:

For outside work, stopping at first point of attachment (demarcation).

| | 07/01/2022 | 01/01/2023 | 01/01/2024 | 01/01/2025 |
|------------------------|------------|------------|------------|------------|
| Cable Splicer | \$ 36.28 | \$ 37.73 | \$ 39.24 | \$ 40.81 |
| Installer, Repairman | \$ 34.43 | \$ 35.81 | \$ 37.24 | \$ 38.73 |
| Teledata Lineman | \$ 34.43 | \$ 35.81 | \$ 37.24 | \$ 38.73 |
| Tech., Equip. Operator | \$ 34.43 | \$ 35.81 | \$ 37.24 | \$ 38.73 |
| Groundman | \$ 18.25 | \$ 18.98 | \$ 19.74 | \$ 20.53 |

NOTE: EXCLUDES Teledata work within ten (10) feet of High Voltage (600 volts and over) transmission lines. For this work please see LINEMAN.

NOTE: THE FOLLOWING RATES WILL APPLY ON ALL CONTRACTING AGENCY MANDATED MULTIPLE SHIFTS OF AT LEAST FIVE (5) DAYS DURATION WORKED:

1ST SHIFT REGULAR RATE

2ND SHIFT REGULAR RATE PLUS 10% 3RD SHIFT REGULAR RATE PLUS 15%

SUPPLEMENTAL BENEFITS

| Per hour: | 07/01/2022 | 01/01/2023 | 01/01/2024 | 01/01/2025 |
|------------|------------------------|------------------------|------------------------|------------------------|
| Journeyman | \$ 5.14 *plus 3% of |
| | the hourly | the hourly | the hourly | the hourly |
| | wage paid | wage paid | wage paid | wage paid |

^{*}The 3% is based on the hourly wage paid, straight time rate or premium rate.

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

NOTE: WAGE CAP - Double the straight time hourly base wage shall be the maximum hourly wage compensation for any hour worked. Contractor is still responsible to pay the hourly benefit amount for each hour worked.

^{*}The 7% is based on the hourly wage paid, straight time or premium time.

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6, 16) on HOLIDAY PAGE

6-1249LT - Teledata

Lineman Electrician - Traffic Signal, Lighting

05/01/2023

JOB DESCRIPTION Lineman Electrician - Traffic Signal, Lighting

DISTRICT 6

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Cortland, Delaware, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orleans, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Warren, Washington, Wayne, Wyoming, Yates

WAGES

Lineman/Technician shall perform all overhead aerial work. A Lineman/Technician on the ground will install all electrical panels, connect all grounds, install and connect all electrical conductors which includes, but is not limited to road loop wires; conduit and plastic or other type pipes that carry conductors, flex cables and connectors, and to oversee the encasement or burial of such conduits or pipes.

A Groundman/Truck Driver shall: Build and set concrete forms, handle steel mesh, set footer cages, transport concrete in a wheelbarrow, hand or machine concrete vibrator, finish concrete footers, mix mortar, grout pole bases, cover and maintain footers while curing in cold weather, operate jack hammer, operate hand pavement breaker, tamper, concrete and other motorized saws, as a drill helper, operate and maintain generators, water pumps, chainsaws, sand blasting, operate mulching and seeding machine, air tools, electric tools, gas tools, load and unload materials, hand shovel and/or broom, prepare and pour mastic and other fillers, assist digger operator/equipment operator in ground excavation and restoration, landscape work and painting. Only when assisting a lineman technician, a groundman/truck driver may assist in installing conduit, pipe, cables and equipment.

A flagger's duties shall consist of traffic control only. (Ref #14.01.01)

| Per hour: | 07/01/2022 | 05/01/2023 | 05/06/2024 |
|-------------------------|------------|------------|------------|
| Lineman, Technician | \$ 48.19 | \$ 49.32 | \$ 50.54 |
| Crane, Crawler Backhoe | 48.19 | 49.32 | 50.54 |
| Certified Welder | 50.60 | 51.79 | 53.07 |
| Digging Machine | 43.37 | 44.39 | 45.49 |
| Tractor Trailer Driver | 40.96 | 41.92 | 42.96 |
| Groundman, Truck Driver | 38.55 | 39.46 | 40.43 |
| Equipment Mechanic | 38.55 | 39.46 | 40.43 |
| Flagman | 28.91 | 29.59 | 30.32 |

Above rates are applicable for installation, testing, operation, maintenance and repair on all Traffic Control (Signal) and Illumination (Lighting) projects, Traffic Monitoring Systems, and Road Weather Information Systems. Includes digging of holes for poles, anchors, footer foundations for electrical equipment; assembly of all electrical materials or raceway; placing of fish wire; pulling of cables, wires or fiber optic cable through such raceways; splicing of conductors; dismantling of such structures, lines or equipment.

NOTE: THE FOLLOWING RATES WILL APPLY ON ALL CONTRACTING AGENCY MANDATED MULTIPLE SHIFTS OF AT LEAST FIVE (5) DAYS DURATION WORKED BETWEEN THE HOURS LISTED BELOW:

1ST SHIFT 8:00 AM TO 4:30 PM REGULAR RATE

2ND SHIFT 4:30 PM TO 1:00 AM REGULAR RATE PLUS 17.3% 3RD SHIFT 12:30 AM TO 9:00 AM REGULAR RATE PLUS 31.4%

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day. Tuesday thru Friday may be worked with no make-up day.

NOTE - In order to use the '4 Day/10 Hour Work schedule', as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour worked (but also required on non-worked holidays):

| | 07/01/2022 | 05/01/2023 | 05/06/2024 |
|------------|-------------|-------------|-------------|
| Journeyman | \$ 25.90 | \$ 26.40 | \$ 26.90 |
| | *plus 7% of | *plus 7% of | *plus 7% of |
| | the hourly | the hourly | the hourly |
| | wage paid | wage paid | wage paid |

| Journeyman Lineman or | \$ 27.90 | \$ 29.40 | \$ 30.90 |
|-----------------------|-------------|-------------|-------------|
| Equipment Operators | *plus 7% of | *plus 7% of | *plus 7% of |
| with Crane License | the hourly | the hourly | the hourly |
| | wage paid | wage paid | wage paid |

^{*}The 7% is based on the hourly wage paid, straight time or premium time.

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE. *Note* Double time for all emergency work designated by the Dept. of Jurisdiction. NOTE: WAGE CAP - Double the straight time hourly base wage shall be the maximum hourly wage compensation for any hour worked. Contractor is still responsible to pay the hourly benefit amount for each hour worked.

HOLIDAY

Paid: See (5, 6, 8, 13, 25) on HOLIDAY PAGE plus Governor of NYS Election Day. Overtime: See (5, 6, 8, 13, 25) on HOLIDAY PAGE plus Governor of NYS Election Day.

NOTE: All paid holidays falling on Saturday shall be observed on the preceding Friday. All paid holidays falling on Sunday shall be observed on the following Monday. Supplements for holidays paid at straight time.

REGISTERED APPRENTICES

WAGES per hour: 1000 hour terms at the following percentage of the applicable Journeyman Lineman wage.

| 1st 60% | 2nd 65% | 3rd 70% | 4th 75% | 5th 80% | 6th 85% | 7th 90% | |
|------------|-------------|---------------|-------------|------------|-------------|------------|-------------|
| 00 /0 | 0370 | 7070 | 7 3 70 | 00 70 | 03 /0 | 30 /0 | |
| SUPPLEME | NTAL BENEFI | ITS per hour: | | | | | |
| | | | 07/01/2022 | | 05/01/2023 | | 05/06/2024 |
| | | | \$ 25.90 | | \$ 26.40 | | \$ 26.90 |
| | | | *plus 7% of | | *plus 7% of | | *plus 7% of |
| | | | the hourly | | the hourly | | the hourly |
| | | | wage paid | | wage paid | | wage paid |

^{*}The 7% is based on the hourly wage paid, straight time or premium time.

6-1249a-LT

Lineman Electrician - Tree Trimmer

05/01/2023

JOB DESCRIPTION Lineman Electrician - Tree Trimmer

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Dutchess, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orange, Orleans, Oswego, Otsego, Putnam, Rensselaer, Rockland, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Wyoming, Yates

WAGES

Applies to line clearance, tree work and right-of-way preparation on all new or existing energized overhead or underground electrical, telephone and CATV lines. This also would include stump removal near underground energized electrical lines, including telephone and CATV lines.

| Per hour: | 07/01/2022 | 01/01/2023 |
|--------------------|------------|------------|
| Tree Trimmer | \$ 28.25 | \$ 29.80 |
| Equipment Operator | 24.98 | 26.35 |
| Equipment Mechanic | 24.98 | 26.35 |
| Truck Driver | 20.80 | 21.94 |
| Groundman | 17.13 | 18.07 |
| Flag person | 13.20* | 13.20* |

^{*}NOTE- Rate effective 12/31/2022: \$14.20

SUPPLEMENTAL BENEFITS

Per hour worked (but also required on non-worked holidays):

| | 07/01/2022 | 01/01/2023 |
|------------|-------------------------|-------------------------|
| Journeyman | \$ 10.23 *plus 3% of | \$ 10.48 *plus 3% of |
| | the hourly wage paid | the hourly wage paid |

* The 3% is based on the hourly wage paid, straight time rate or premium rate.

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

NOTE: WAGE CAP - Double the straight time hourly base wage shall be the maximum hourly wage compensation for any hour worked. Contractor is still responsible to pay the hourly benefit amount for each hour worked.

HOLIDAY

See (5, 6, 8, 15) on HOLIDAY PAGE Paid: See (5, 6, 8, 15, 16, 25) on HOLIDAY PAGE Overtime:

NOTE: All paid holidays falling on a Saturday shall be observed on the preceding Friday.

All paid holidays falling on a Sunday shall be observed on the following Monday.

6-1249TT

Mason - Building 05/01/2023

JOB DESCRIPTION Mason - Building

DISTRICT 12

ENTIRE COUNTIES

Albany, Clinton, Columbia, Essex, Franklin, Fulton, Greene, Hamilton, Montgomery, Rensselaer, Saratoga, Schenectady, Schoharie, Warren, Washington

WAGES

07/01/2022 Per hour

Tile/Marble/Terrazzo

\$ 36.71 Setter 28.61 Finisher

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day.

NOTE - In order to use the '4 Day/10 Hour Work Schedule,' as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule, form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour worked

Journeyman Setter \$ 21.43 18.52 Journeyman Finisher

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

See (1) on HOLIDAY PAGE Paid: See (5, 6) on HOLIDAY PAGE Overtime:

REGISTERED APPRENTICES

Wages per hour

Hour Terms at the following percentage of Journeyman's wage

Setter:

1st term 0-500 hrs 60% 2nd term 501-1500 hrs 70% 3rd term 1501-2500 hrs 80% 4th term 2501-3500 hrs 85% 5th term 3501-4500 hrs 90% 6th term 4501-6000 hrs 95%

Finisher:

1st term 0-500 hrs 70% 2nd term 501-1500 hrs 80% 3rd term 1501-2500 hrs 90% 4th term 2501-3700 hrs 95%

Supplemental Benefits per hour worked

07/01/2022

Setter:

1st term 0-500 hrs \$ 12.68 2nd term 501-1500 hrs 12.68 3rd term 1501-2500 hrs 17.05

| Last r ablished on May or 2020 | | 1 10 Namber 202000077 Caratega County |
|--------------------------------|----------|---------------------------------------|
| 4th term 2501-3500 hrs | 17.05 | |
| 5th term 3501-4500 hrs | 19.24 | |
| 6th term 4501-6000 hrs | 21.43 | |
| Finisher: | | |
| 1st term 0-500 hrs | \$ 11.97 | |
| 2nd term 501-1500 hrs | 11.97 | |
| 3rd term 1501-2500 hrs | 15.24 | |
| 4th term 2501-3700 hrs | 15.24 | |
| | | 12-2TS.1 |

Mason - Building 05/01/2023

JOB DESCRIPTION Mason - Building

DISTRICT 12

ENTIRE COUNTIES

Albany, Columbia, Fulton, Greene, Hamilton, Montgomery, Rensselaer, Saratoga, Schenectady, Schoharie, Washington

PARTIAL COUNTIES

Warren: Only the Townships of Bolton, Lake George, Lake Luzerne, Queensbury, Stony Creek, Thurman & Warrensburg.

WAGES

| Per hour | 07/01/2022 |
|--|-------------------|
| Bricklayer | \$ 39.54 39.54 |
| Cement Mason(Bldg) Plasterer/Fireproofing* | 39.54 39.54 |
| Pointer/Caulker/Cleaner Stone Mason | 39.54 39.54 |
| Acid Brick | 40.04 |

(*)Fireproofing of Structural only.

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day.

NOTE - In order to use the '4 Day/10 Hour Work Schedule,' as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour worked

Journeyman \$ 22.63

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

Note: Any holiday which occurs on Sunday shall be observed the following Monday.

REGISTERED APPRENTICES

Wages per hour

750 hour terms at the following percentage of Journey's wage

| 1st | 2nd | 3rd | 4th | 5th | 6th | 7th | 8th |
|-----|-----|-----|-----|-----|-----|-----|-----|
| 60% | 60% | 65% | 70% | 75% | 80% | 85% | 90% |

Supplemental Benefits per hour worked

All Terms \$ 22.63

12-2b.1

Mason - Heavy&Highway 05/01/2023

JOB DESCRIPTION Mason - Heavy&Highway

DISTRICT 12

ENTIRE COUNTIES

Albany, Cayuga, Clinton, Columbia, Essex, Franklin, Fulton, Greene, Hamilton, Herkimer, Jefferson, Lewis, Madison, Montgomery, Oneida, Oswego, Rensselaer, Saratoga, Schenectady, Schoharie, St. Lawrence, Warren, Washington

PARTIAL COUNTIES

Prevailing Wage Rates for 07/01/2022 - 06/30/2023 Last Published on May 01 2023

Onondaga: For Heavy & Highway Cement Mason or Plaster Work in Onondaga County, refer to Mason-Heavy&Highway tag 1-2h/h on.

WAGES

Per hour

07/01/2022

Mason &

Bricklayer \$40.76

Additional \$1.00 per hour for work on any swing scaffold or staging suspended by means of ropes or cables.

SUPPLEMENTAL BENEFITS

Per hour worked

Journeyman

\$21.48

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

Note: If a holiday falls on Sunday, the Monday following shall constitute the day of the legal holiday.

REGISTERED APPRENTICES

Wages per hour

750 HR TERMS at the following percent of Journeyman's wage

2nd 3rd 4th 5th 6th 7th 8th 1st 60% 60% 65% 70% 75% 80% 85% 90%

Supplemental Benefits per hour worked

0 to 500 Hours \$ 12.98 All Other \$ 21.48

12-2hh.1

Millwright 05/01/2023

JOB DESCRIPTION Millwright

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orleans, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Wyoming, Yates

WAGES

THE FOLLOWING RATE APPLIES TO ANY GAS/STEAM TURBINE AND OR RELATED COMPONENT WORK, INCLUDING NEW INSTALLATIONS OR MAINTENANCE AND ANY/ALL WORK PERFORMED WITHIN THE PROPERTY LIMITS OF A NUCLEAR FACILITY.

Per hour: 07/01/2022

Millwright - Power Generation \$41.23

NOTE: ADDITIONAL PREMIUMS PAID FOR THE FOLLOWING WORK LISTED BELOW (amount subject to any overtime premiums):

- Certified Welders shall receive an additional \$1.75 per hour provided he/she is directed to perform certified welding.
- If a work site has been declared a hazardous site by the Owner and the use of protective gear (including, as a minimum, air purifying canister-type chemical respirators) are required, then that employee shall receive an additional \$1.50 per hour.
- An employee performing the work of a machinist shall receive an additional \$2.00 per hour. For the purposes of this premium to apply, a "machinist" is a person who uses a lathe, Bridgeport, milling machine or similar type of tool to make or modify parts.
- When performing work underground at 500 feet and below, the employee shall receive an additional \$1.00 per hour.

SUPPLEMENTAL BENEFITS

Per hour paid:

Journeyman \$26.72*

*NOTE: Subject to OT premium

OVERTIME PAY

See (B, E, *E2, Q, V) on OVERTIME PAGE

*NOTE - Saturday may be used as a make-up day and worked at the straight time rate of pay during a work week when conditions such as weather, power failure, fire, or natural disaster prevent the performance of work on a regular scheduled work day.

HOLIDAY

Paid: See (1) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

NOTE: Any holiday that falls on Sunday shall be observed the following Monday. Any holiday that falls on Saturday shall be observed the preceding Friday.

REGISTERED APPRENTICES

WAGES per hour: One year terms at the following percentage of Journeyman's wage:

 Appr. 1st year
 65 %*

 Appr. 2nd year
 75 %*

 Appr. 3rd year
 80 %*

 Appr. 4th year
 90 %*

*NOTE: Additional premium for the following work listed below:

Certified Welder \$ 1.75
Hazardous Waste Work 1.50
Machinist 2.00
Underground 1.00
(500' and below)

SUPPLEMENTAL BENEFITS per hour:

 Appr. 1st year
 \$ 11.83

 Appr. 2nd year
 22.26

 Appr. 3rd year
 23.74

 Appr. 4th year
 25.24

6-1163Power

Millwright 05/01/2023

JOB DESCRIPTION Millwright

ENTIRE COUNTIES

Albany, Chenango, Delaware, Fulton, Montgomery, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie

WAGES

Per hour: 07/01/2022

Building \$35.84 Heavy & Highway 37.84

NOTE ADDITIONAL PREMIUMS PAID FOR THE FOLLOWING WORK LISTED BELOW (amount subject to any overtime premiums):

- Certified Welders shall receive \$1.75 per hour in addition to the current Millwrights rate provided he/she is directed to perform certified welding.
- For Building work if a work site has been declared a hazardous site by the Owner and the use of protective gear (including, as a minimum, air purifying canister-type chemical respirators) are required, then that employee shall receive a \$1.50 premium per hour for Building work.
- For Heavy & Highway work if the work is performed at a State or Federally designated hazardous waste site where employees are required to wear protective gear, the employees performing the work shall receive an additional \$2.00 per hour over the millwright heavy and highway wage rate for all hours worked on the day protective gear was worn.
- An employee performing the work of a machinist shall receive \$2.00 per hour in addition to the current Millwrights rate. For the purposes of this premium to apply, a "machinist" is a person who uses a lathe, Bridgeport, milling machine or similar type of tool to make or modify parts.
- When performing work underground at 500 feet and below, the employee shall receive an additional \$1.00.

SUPPLEMENTAL BENEFITS

Per hour:

Journeyman \$ 25.41

OVERTIME PAY

See (B, E, *E2, Q) on OVERTIME PAGE

*Note - Saturday may be used as a make-up day and worked at the straight time rate of pay during a work week when conditions such as weather, power failure, fire, or natural disaster prevent the performance of work on a regular scheduled work day.

HOLIDAY

Paid: See (1) on HOLIDAY PAGE

Overtime:

See (5, 6) on HOLIDAY PAGE

Note: Any holiday that falls on Sunday shall be observed the following Monday. Any holiday that falls on Saturday shall be observed the preceding Friday.

REGISTERED APPRENTICES

Wages per hour:

(1) year terms at the following percentage of Journeyman's rate.

| 1st | 2nd | 3rd | 4th |
|-----|-----|-----|-----|
| 65% | 75% | 80% | 90% |

Supplemental Benefits per hour:

Apprentices:

| 1st term | \$ 11.93 |
|----------|----------|
| 2nd term | 21.37 |
| 3rd term | 22.72 |
| 4th term | 24 06 |

2-1163.1

Operating Engineer - Building

05/01/2023

JOB DESCRIPTION Operating Engineer - Building

ENTIRE COUNTIES

Albany, Clinton, Columbia, Essex, Franklin, Fulton, Greene, Hamilton, Herkimer, Montgomery, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Warren, Washington

PARTIAL COUNTIES

Dutchess: Defined as north of the northern boundary line of City of Poughkeepsie then due east to Route 115 to Bedell Road then east along Bedell Road to VanWagner Road then north along VanWagner Road to Bower Road then east along Bower Road to Rte. 44 east to Route 343 then along Route 343 east to the northern boundary of Town of Dover Plains and east along the northern boundary of Town of Dover Plains to Connecticut.

WAGES

CLASS A1:

Crane, hydraulic cranes, tower crane, locomotive crane, piledriver, cableway, derricks, whirlies, dragline, boom trucks over 5 tons.

CLASS A:

Shovel, all Excavators (including rubber tire full swing), Gradalls, power road grader, all CMI equipment, front-end rubber tire loader, tractor-mounted drill (quarry master), mucking machine, concrete central mix plant, concrete pump, belcrete system, automated asphalt concrete plant, and tractor road paver, boom trucks 5 tons and under, maintenance engineer, self-contained crawler drill-hydraulic rock drill.

CLASS B:

Backhoes (rubber tired backhoe/loader combination), bulldozer, pushcat, tractor, traxcavator, scraper, LeTourneau grader, form fine grader, self-propelled soil compactor (fill roller), asphalt roller, blacktop spreader, power brooms, sweepers, trenching machine, Barber Green loader, side booms, hydro hammer, concrete spreader, concrete finishing machine, one drum hoist, power hoisting (single drum), hoist two drum or more, three drum engine, power hoisting (two drum and over), two drum and swinging engine, three drum swinging engine, hod hoist, A-L frame winches, core and well drillers (one drum), post hole digger, model CHB Vibro-Tamp or similar machine, batch bin and plant operator, dinky locomotive, skid steer loader, track excavator 5/8 cubic yard or smaller, front end rubber tired loader under four cubic yards, vacum machine (mounted or towed).

CLASS C:

Fork lift, high lift, all terrain fork lift: or similar, oiler, fireman and heavy-duty greaser, boilers and steam generators, pump, vibrator, motor mixer, air compressor, dust collector, welding machine, well point, mechanical heater, generators, temporary light plants, electric submersible pumps 4" and over, murphy type diesel generator, conveyor, elevators, concrete mixer, beltcrete power pack (belcrete system), seeding, and mulching machines, pumps.

WAGES per hour

| • | 07/01/2022 |
|------------|------------|
| Class # A1 | \$ 47.81 |
| Class # A | 47.32 |
| Class # B | 46.30 |
| Class # C | 43.40 |

Additional \$0.50 per hr for Tower Cranes.

Additional \$1.25 per hr for Cranes with Boom length & jib 150ft. and over.

Additional \$2.25 per hr for Cranes with Boom length & jib 200ft. and over.

^{*} In the event that equipment listed above is operated by robotic control, the classification covering the operation will be the same as if manually operated.

Additional \$2.50 per hr over B rate for Nuclear Leader work.

Additional \$0.40 per hr for tunnel or excavation of shaft 40' or more deep.

Additional \$2.50 per hour if work requires Personal Protective Equipment for hazardous waste site activities with a level C or over rating.

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day.

NOTE - In order to use the '4 Day/10 Hour Work schedule', as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour

07/01/2022

Journeyman \$30.55

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

Note: If a holiday falls on Sunday, it will be celebrated on Monday. If the holiday falls on Saturday, it will be celebrated on Friday.

Employees who work a designated holiday shall be paid double time plus 8 hours of straight time.

REGISTERED APPRENTICES

Wages per hour

1000 hours terms at the following percentage of Journeyperson's wage Class B

1st 2nd 3rd 4th 60% 70% 80% 90%

Supplemental Benefits per hour worked

All terms \$ 25.85

1-158 Alb

Operating Engineer - Heavy&Highway

05/01/2023

DISTRICT 1

JOB DESCRIPTION Operating Engineer - Heavy&Highway

ENTIRE COUNTIES

Albany, Broome, Chenango, Clinton, Columbia, Essex, Franklin, Fulton, Greene, Hamilton, Herkimer, Montgomery, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Tioga, Warren, Washington

PARTIAL COUNTIES

Dutchess: Defined as north of the northern boundary line of City of Poughkeepsie then due east to Route 115 to Bedell Road then east along Bedell Road to VanWagner Road then north along VanWagner Road to Bower Road then east along Bower Road to Rte. 44 east to Route 343 then along Route 343 east to the northern boundary of Town of Dover Plains and east along the northern boundary of Town of Dover Plains to Connecticut.

WAGES

CLASSIFICATION A:

Asphalt Curb Machine (Self Propelled, Slipform), Asphalt Paver, Automated Concrete Spreader (CMI Type), Automatic Fine Grader, Backhoe (Except Tractor Mounted, Rubber Tired), Backhoe Excavator Full Swing (CAT 212 or similar type), Back Filling Machine, Belt Placer (CMI Type), Blacktop Plant (Automated), Boom truck, GPS operated Bull Dozer, Cableway, Caisson Auger, Central Mix Concrete Plant (Automated), Concrete Curb Machine (Self Propelled, Slipform), Concrete Pump, Crane, Cherry Picker, Derricks (steel erection), Dragline, Overhead Crane (Gantry or Straddle type), Pile Driver, Truck Crane, Directional Drilling Machine, Dredge, Dual Drum Paver, Excavator (All PurposeHydraulically Operated) (Gradall or Similar), Front End Loader (4 cu. yd. and Over), Head Tower (Sauerman or Equal), Hoist (Two or Three Drum), Holland Loader, Maintenance Engineer, Mine Hoist, Mucking Machine or Mole, Pavement Breaker(SP) Wertgen; PB-4 and similar type, Power Grader, Profiler (over 105 H.P.), Quad 9, Quarry Master (or equivalent), Scraper, Shovel, Side Boom, Slip Form Paver (If a second man is needed, he shall be an Oiler), Tractor Drawn BeltType Loader, Truck or Trailer Mounted Log Chipper (Self Feeder), Tug Operator (Manned Rented Equipment Excluded), Tunnel Shovel

CLASSIFICATION B:

Backhoe (Tractor Mounted, Rubber Tired), Bituminous Recycler Machine, Bituminous Spreader and Mixer, Blacktop Plant (NonAutomated), Blast or Rotary Drill (Truck or Tractor Mounted), Brokk, Boring Machine, Cage Hoist, Central Mix Plant [(NonAutomated) and All Concrete Batching Plants], Concrete Paver (Over 16S), Crawler Drill (Self-contained), Crusher, Diesel Power Unit, Drill Rigs, Tractor Mounted, Front End Loader (Under 4 cu. yd.), Greaseman/Lubrication Engineer, HiPressure Boiler (15 lbs. and over), Hoist (One Drum), Hydro-Axe, Kolman Plant Loader and Similar Type Loaders (If Employer requires another man to clean the screen or to maintain the equipment, he shall be an Oiler), L.C.M. Work Boat Operator, Locomotive, Material handling knuckle boom, Mini Excavator (under 18,000 lbs.), Mixer (for stabilized base self-propelled), Monorail Machine, Plant Engineer, Prentice Loader, Profiler (105 H.P. and under), Pug Mill, Pump Crete, Ready Mix Concrete Plant, Refrigeration Equipment (for soil stabilization), Road Widener, Roller (all above subgrade), Sea Mule, Self-contained Rideon Rock Drill(Excluding Air-Track Type Drill), Skidder, Tractor with Dozer and/or Pusher, Trencher, Tugger Hoist, Vacum machine (mounted or towed), Vermeer saw (ride on, any size or type), Welder, Winch, Winch Cat

CLASSIFICATION C:

A Frame Winch Hoist on Truck, Articulated Heavy Hauler, Aggregate Plant, Asphalt or Concrete Grooving Machine (ride on), Ballast Regulator(Ride-on), Boiler (used in conjunction with production), Bituminous Heater (self-propelled), Boat (powered), Cement and Bin Operator, Concrete Pavement Spreader and Finisher Concrete Paver or Mixer (16' and under), Concrete Saw (self-propelled), Conveyor, Deck Hand, Directional Drill Machine Locator, Drill (Core and Well), Farm Tractor with accessories, Fine Grade Machine, Fireman, Fork Lift, Form Tamper, Grout Pump, Gunite Machine, Hammers (Hydraulic self-propelled), Hydra-Spiker (ride-on), Hydraulic Pump (jacking system), Hydro-Blaster (Water), Mulching Machine, Oiler, Parapet Concrete or Pavement Grinder, Post Hole Digger and Post Driver, Power Broom (towed), Power Heaterman, Power Sweeper, Revinius Widener, Roller (Grade and Fill), Scarifier (ride-on), Shell Winder, Skid steer loader (Bobcat or similar), Span-Saw (ride-on), Steam Cleaner, Tamper (ride-on), Tie Extractor (ride-on), Tie Handler (ride-on), Tie Inserter (ride-on), Tie Spacer (ride-on), Tire Repair, Track Liner (ride-on), Tractor, Tractor (with towed accessories), Vibratory Compactor, Vibro Tamp, Well Point, and the following hands-off equipment: Compressors, Dust Collectors, Generators, Pumps, Welding Machines, Light Plants and Heaters

- Note for all above classifications of Operating Engineer - In the event that equipment listed above is operated by robotic control, the classification covering the operation will be the same as if manually operated.

WAGES per hour

| | 07/01/2022 |
|-----------------|------------|
| Master Mechanic | \$ 51.03 |
| Class A* | 49.42 |
| Class B | 48.51 |
| Class C | 45.94 |
| | |

Additional \$2.50 per hour for All Employees who work a single irregular work shift starting from 5:00 PM to 1:00 AM that is mandated by the Contracting Agency.

Additional \$2.50 per hr. for hazardous waste removal work on State and/or Federally designated waste site which require employees to wear Level C or above forms of personal protection.

- (*) Premiums for CRANES is based upon Class A rates with the following premiums:
- Additional \$4.00 per hr for Tower Cranes, including self erecting.
- Additional \$3.00 per hr for Lattice Boom Cranes and all other cranes with a manufacturers rating of fifty (50) tons and over.
- Additional \$2.00 per hr for all Hydraulic Cranes and Derricks with a manufacturer's rating of 49 ton and below, including boom trucks.

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day.

NOTE - In order to use the '4 Day/10 Hour Work schedule', as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour

Journeyperson \$30.75

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

Note: If the holiday falls on Sunday, it will be celebrated on Monday. If the Holiday falls on a Saturday employer can choose to celebrate Saturday or give Friday off with pay.

REGISTERED APPRENTICES

Wages per hour

1000 hours terms at the following percentage of Journeyperson's wage Class B

1st 2nd 3rd 4th 60% 70% 80% 90%

Supplemental Benefits per hour worked

All Terms \$ 26.15

1-158H/H Alb

Operating Engineer - Survey Crew

05/01/2023

JOB DESCRIPTION Operating Engineer - Survey Crew

DISTRICT 12

ENTIRE COUNTIES

Albany, Allegany, Broome, Cayuga, Chemung, Chenango, Clinton, Columbia, Cortland, Essex, Franklin, Fulton, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Oneida, Onondaga, Ontario, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Tioga, Tompkins, Warren, Washington, Wayne, Yates

PARTIAL COUNTIES

Dutchess: The northern portion of the county from the northern boundary line of the City of Poughkeepsie, north.

Genesee: Only the portion of the county that lies east of a line down the center of Route 98 to include all area that lies within the City of

Batavia.

WAGES

These rates apply to Building, Tunnel and Heavy Highway.

Per hour:

SURVEY CLASSIFICATIONS:

Party Chief - One who directs a survey party.

Instrument Person - One who operates the surveying instruments.

Rod Person - One who holds the rods and assists the Instrument Person.

07/01/2022

Party Chief \$47.37 Instrument Person 43.51 Rod Person 32.26

Additional \$3.00/hr. for Tunnel Work Additional \$2.50/hr. for Hazardous Work Site

SUPPLEMENTAL BENEFITS

Per hour worked:

Journeyman \$28.05

OVERTIME PAY

See (B, E, P, *X) on OVERTIME PAGE

*Note: \$24.10/Hr. Only for "ALL" premium hours paid when worked.

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

REGISTERED APPRENTICES

WAGES: 1000 hour terms based on the Percentage of Rod Persons Wage:

07/01/2022

 0-1000
 60%

 1001-2000
 70%

 2001-3000
 80%

SUPPLEMENTAL BENEFIT per hour worked:

0-1000 \$ 19.83 / PHP \$17.03 1001-2000 22.85 / " 19.45 2001-3000 25.88 / " 21.93

NOTE: PHP is premium hours paid when worked.

12-158-545 D.H.H.

Operating Engineer - Survey Crew - Consulting Engineer

05/01/2023

JOB DESCRIPTION Operating Engineer - Survey Crew - Consulting Engineer

DISTRICT 12

ENTIRE COUNTIES

Albany, Allegany, Broome, Cayuga, Chemung, Chenango, Clinton, Columbia, Cortland, Essex, Franklin, Fulton, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Oneida, Onondaga, Ontario, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Tioga, Tompkins, Warren, Washington, Wayne, Yates

PARTIAL COUNTIES

Dutchess: The northern portion of the county from the northern boundary line of the City of Poughkeepsie, north.

Genesee: Only the portion of the county that lies east of a line down the center of Route 98 to include all area that lies within the City of

Batavia.

WAGES

These rates apply to feasibility and preliminary design surveying, line and grade surveying for inspection or supervision of construction when performed under a Consulting Engineer Agreement.

Per hour:

SURVEY CLASSIFICATIONS:

Party Chief - One who directs a survey party.

Instrument Person - One who operates the surveying instruments.

Rod Person - One who holds the rods and assists the Instrument Person.

07/01/2022

Party Chief \$ 47.37 Instrument Person 43.51 Rod Person 32.26

Additional \$3.00/hr. for Tunnel Work.

Additional \$2.50/hr. for EPA or DEC certified toxic or hazardous waste work.

SUPPLEMENTAL BENEFITS

Per hour worked:

Journeyman \$ 28.05

OVERTIME PAY

See (B, E, Q, *X) on OVERTIME PAGE

*Note: \$24.10/Hr. Only for "ALL" premium hours paid when worked.

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

REGISTERED APPRENTICES

WAGES: 1000 hour terms based on percentage of Rod Persons Wage:

07/01/2022

0-1000 60% 1001-2000 70% 2001-3000 80%

SUPPLEMENTAL BENEFIT per hour worked:

0-1000 \$ 19.83 / PHP \$17.03 1001-2000 \$ 22.85 / " 19.45 2001-3000 \$ 25.88 / " 21.93

NOTE: PHP is premium hours paid when worked.

12-158-545 DCE

DISTRICT 7

JOB DESCRIPTION Operating Engineer - Tunnel

05/01/2023

ENTIRE COUNTIES

Operating Engineer - Tunnel

Albany, Allegany, Broome, Cayuga, Chemung, Chenango, Clinton, Columbia, Cortland, Essex, Franklin, Fulton, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Oneida, Onondaga, Ontario, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Tioga, Tompkins, Warren, Washington, Wayne, Yates

PARTIAL COUNTIES

Dutchess: Northern part of Dutchess, to the northern boundary line of the City of Poughkeepie, then due east to Route 115 to Bedell Road, then east along Bedell Road to VanWagner Road, then north along VanWagner Road to Bower Road, then east along Bower Road to Rte. 44 east to Rte. 343, then along Rte. 343 east to the northern boundary of the Town of Dover Plains and east along the northern boundary of the Town of Dover Plains, to the borderline of the State of Connecticut.

Genesee: Only that portion of the county that lies east of a line drawn down the center of Route 98 and the entirety of the City of Batavia.

WAGES

CLASS A: Automatic Concrete Spreader (CMI Type); Automatic Fine Grader; Backhoe (except tractor mounted, rubber tired); Belt Placer (CMI Type); Blacktop Plant (automated); Cableway; Caisson Auger; Central Mix Concrete Plant (automated); Concrete Curb Machine (self-propelled slipform); Concrete Pump (8" or over); Dredge; Dual Drum Paver; Excavator; Front End Loader (4 cu. yd & over); Gradall; Head Tower (Sauerman or Equal); Hoist (shaft); Hoist (two or three Drum); Log Chipper/Loader (self-feeder); Maintenance Engineer (shaft and tunnel); any Mechanical Shaft Drill; Mine Hoist; Mining Machine(Mole and similar types); Mucking Machine or Mole; Overhead Crane (Gantry or Straddle Type); Pile Driver; Power Grader; Remote Controlled Mole or Tunnel Machine; Scraper; Shovel; Side Boom; Slip Form Paver (If a second man is needed, they shall be an Oiler); Tripper/Maintenance Engineer (shaft & tunnel); Tractor Drawn Belt-Type Loader; Tug Operator (manned rented equipment excluded); Tunnel Shovel

CLASS B: Automated Central Mix Concrete Plant; Backhoe (topside); Backhoe (track mounted, rubber tired); Backhoe (topside); Bituminous Spreader and Mixer, Blacktop Plant (non-automated); Blast or Rotary Drill (truck or tractor mounted); Boring Machine; Cage Hoist; Central Mix Plant(non-automated); all Concrete Batching Plants; Compressors (4 or less exceeding 2,000 c.f.m. combined capacity); Concrete Pump; Crusher; Diesel Power Unit; Drill Rigs (tractor mounted); Front End Loader (under 4 cu. yd.); Grayco Epoxy Machine; Hoist (One Drum); Hoist (2 or 3 drum topside); Knuckle Boom material handler; Kolman Plant Loader & similar type Loaders (if employer requires another person to clean the screen or to maintain the equipment, they shall be an Oiler); L.C.M. Work Boat Operator; Locomotive; Maintenance Engineer (topside); Maintenance Grease Man; Mixer (for stabilized base-self propelled); Monorail Machine; Plant Engineer; Personnel Hoist; Pump Crete; Ready Mix Concrete Plant; Refrigeration Equipment (for soil stabilization); Road Widener; Roller (all above sub-grade); Sea Mule; Shotcrete Machine; Shovel (topside); Tractor with Dozer and/or Pusher; Trencher; Tugger Hoist; Tunnel Locomotive; Vacuum Machine (mounted or towed); Welder; Winch; Winch Cat

CLASS C: A Frame Truck; All Terrain Telescoping Material Handler; Ballast Regulator (ride-on); Compressors (4 not to exceed 2,000 c.f.m. combined capacity; or 3 or less with more than 1200 c.f.m. but not to exceed 2,000 c.f.m.); Compressors ((any size, but subject to other provisions for compressors), Dust Collectors, Generators, Pumps, Welding Machines, Light Plants (4 or any type combination)); Concrete Pavement Spreaders and Finishers; Conveyor; Drill (core); Drill (well); Electric Pump used in conjunction with Well Point System; Farm Tractor with Accessories; Fine Grade Machine; Fork Lift; Grout Pump (over 5 cu. ft.); Gunite Machine; Hammers (hydraulic-self-propelled); Hydra-Spiker (ride-on); Hydra-Blaster (water); Hydro-Blaster; Motorized Form Carrier; Post Hole Digger and Post Driver; Power Sweeper; Roller grade & fill); Scarifer (ride-on); Span-Saw (ride-on); Submersible Electric Pump (when used in lieu of well points); Tamper (ride-on); Tie-Extractor (ride-on), Tie Handler (ride-on), Tie Inserter (ride-on), Tie Spacer (ride-on); Track Liner (ride-on); Tractor with towed accessories; Vibratory Compactor; Vibro Tamp, Well Point

CLASS D: Aggregate Plant; Cement & Bin Operator; Compressors (3 or less not to exceed 1,200 c.f.m. combined capacity); Compressors ((any size, but subject to other provisions for compressors), Dust Collectors, Generators, Pumps, Welding Machines, Light Plants (3 or less or any type or combination)); Concrete Saw (self-propelled); Form Tamper; Greaseman; Hydraulic Pump (jacking system); Junior Engineer; Light Plants; Mulching Machine; Oiler; Parapet Concrete or Pavement Grinder; Power Broom (towed); Power Heaterman (when used for production); Revinius Widener; Shell Winder; Steam Cleaner; Tractor

| Per hour: | 07/01/2022 |
|-----------------|------------|
| Master Mechanic | \$ 52.60 |
| CLASS A | 50.19 |
| CLASS B | 48.97 |
| CLASS C | 46.18 |
| CLASS D | 43.17 |
| | |

Additional \$5.00 per hour for Hazardous Waste Work on a state or federally designated hazardous waste site where the Operating Engineer is in direct contact with hazardous material and when personal protective equipment is required for respiratory, skin and eye protection. Fringe benefits will be paid at the hourly wage premium.

CRANES:

Crane 1: All cranes, including self-erecting to be paid \$4.00 per hour over the Class A rate.

Crane 2: All Lattice Boom Cranes and all cranes with a manufacturer's rating of fifty (50) ton and over to be paid \$3.00 per hour over Class A rate.

Crane 3: All hydraulic cranes and derricks with a manufacturer's rating of forty nine (49) ton and below, including boom trucks, to be paid \$2.00 per hour over Class A rate.

| Crane 1 | \$ 54.19 |
|---------|----------|
| Crane 2 | 53.19 |
| Crane 3 | 52.19 |

SUPPLEMENTAL BENEFITS

Per hour:

\$ 23.70 + 9.35*

^{*} This portion of benefits subject to same premium rate as shown for overtime wages.

OVERTIME PAY

See (B, B2, E, Q, X) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE If a holiday falls on Sunday, it shall be observed on Monday.

REGISTERED APPRENTICES

WAGES:(1000) hours terms at the following percentage of Journeyman's Class B wage.

 1st term
 60%

 2nd term
 65%

 3rd term
 70%

 4th term
 75%

SUPPLEMENTAL BENEFITS per hour: Same as Journeyman

7-158-832TL.

Painter 05/01/2023

JOB DESCRIPTION Painter

DISTRICT 1

ENTIRE COUNTIES

Albany, Clinton, Essex, Franklin, Fulton, Hamilton, Montgomery, Rensselaer, Saratoga, Schenectady, Schoharie, Warren, Washington

WAGES

Per hour

| | 07/01/2022 | 05/01/2023 |
|--------------------|------------|-------------|
| Painter\Wallcovers | \$ 30.79** | \$ 31.49*** |
| Drywall Finishers | 30.79** | 31.19*** |
| Spray Rate | 30.79** | 31.19*** |
| Structrual Steel* | 31.79** | 32.19*** |
| Lead Abatement | 31.79** | 32.19*** |
| Lead Abatement on | | |
| Structural Steel | 32.79** | 33.19*** |

^(*)Employees working on objects with the use of swing stage, boatswain chair, pick and cables only will be paid at Structural Steel rate.

Bridge Painter

See Bridge Painter rates for the following work:

All Bridges and Tanks

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day.

NOTE - In order to use the '4 Day/10 Hour Work schedule', as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour

Journeyperson \$ 18.95 \$ 19.85

OVERTIME PAY

See (B, E2, H) on OVERTIME PAGE

THE FOLLOWING ADDITIONAL HOURLY RATE WILL APPLY ON ALL CONTRACTING AGENCY MANDATED SHIFT(S) OR SINGULAR IRREGULAR SHIFT WHEN THE SHIFT STARTS BETWEEN THE HOURS LISTED BELOW:

2:30 PM to 6:00 AM PLUS \$1.00 TO APPLICABLE RATE*

*Additional \$1.00 is Not Subject to Overtime

HOLIDAY

Paid: See (1) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

Note: If the holiday falls on Sunday, it shall be observed on Monday.

REGISTERED APPRENTICES

Wages per hour

^(**) Plus Additional \$1.00 per hour not subject to Overtime/Premiums

^(***) Plus Additional \$1.25 per hour not subject to Overtime/Premiums

1000 hour terms at the following percentage of Journeyperson's base wage

1st 2nd 3rd 4th 5th 6th 45% 50% 60% 70% 80% 90%

Supplemental Benefits per hour

All Terms \$ 18.95 \$ 19.85

1-201-P

Painter - Bridge & Structural Steel

05/01/2023

JOB DESCRIPTION Painter - Bridge & Structural Steel

DISTRICT 8

ENTIRE COUNTIES

Albany, Bronx, Clinton, Columbia, Dutchess, Essex, Franklin, Fulton, Greene, Hamilton, Kings, Montgomery, Nassau, New York, Orange, Putnam, Queens, Rensselaer, Richmond, Rockland, Saratoga, Schenectady, Schoharie, Suffolk, Sullivan, Ulster, Warren, Washington, Westchester

WAGES

Per Hour: STEEL:

Bridge Painting: 07/01/2022 10/01/2022 \$ 53.00 \$ 54.50 + 9.63* + 10.10*

ADDITIONAL \$6.00 per hour for POWER TOOL/SPRAY, whether straight time or overtime.

NOTE: All premium wages are to be calculated on base rate per hour only.

NOTE: Generally, for Bridge Painting Contracts, ALL WORKERS on and off the bridge (including Flagmen) are to be paid Painter's Rate; the contract must be ONLY for Bridge Painting.

SHIFT WORK:

When directly specified in public agency or authority contract documents for an employer to work a second shift and works the second shift with employees other than from the first shift, all employees who work the second shift will be paid 10% of the base wage shift differential in lieu of overtime for the first eight (8) hours worked after which the employees shall be paid at time and one half of the regular wage rate. When a single irregular work shift is mandated in the job specifications or by the contracting agency, wages shall be paid at time and one half for single shifts between the hours of 3pm-11pm or 11pm-7am.

SUPPLEMENTAL BENEFITS

Per Hour: Journeyworker:

OVERTIME PAY

See (B, F, R) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE Overtime: See (4, 6) on HOLIDAY PAGE

REGISTERED APPRENTICES

Wage - Per hour:

Apprentices: (1) year terms

^{*} For the period of May 1st to November 15th, this amount is payable up to 40 hours. For the period of Nov 16th to April 30th, this amount is payable up to 50 hours. EXCEPTION: First and last week of employment, and for the weeks of Memorial Day, Independence Day and Labor Day, where the amount is paid for the actual number of hours worked (no cap).

^{*} For the period of May 1st to November 15th, this amount is payable up to 40 hours. For the period of Nov 16th to April 30th, this amount is payable up to 50 hours. EXCEPTION: First and last week of employment, and for the weeks of Memorial Day, Independence Day and Labor Day, where the amount is paid for the actual number of hours worked (no cap).

| | + 5.78 | + 6.06 |
|-----------------------------------|---------------------|---------------------|
| 3rd year | \$ 42.40 | \$ 43.60 |
| Supplemental Benefits - Per hour: | + 7.70 | + 8.08 |
| 1st year | \$.25 + 12.24 | \$.25 + 12.34 |
| 2nd year | \$ 10.90 + 18.36 | \$ 10.90 + 18.51 |
| 3rd year | \$ 10.90 + 24.48 | \$ 10.90 + 24.68 |

NOTE: All premium wages are to be calculated on base rate per hour only.

8-DC-9/806/155-BrSS

Painter - Line Striping 05/01/2023

JOB DESCRIPTION Painter - Line Striping

ENTIRE COUNTIES

Albany, Clinton, Columbia, Dutchess, Essex, Franklin, Fulton, Greene, Hamilton, Montgomery, Nassau, Orange, Putnam, Rensselaer, Rockland, Saratoga, Schenectady, Schoharie, Suffolk, Sullivan, Ulster, Warren, Washington, Westchester

WAGES

Per hour:

Painter (Striping-Highway): 07/01/2022 Striping-Machine Operator* \$31.53

Linerman Thermoplastic 38.34

Note: * Includes but is not limited to: Positioning of cones and directing of traffic using hand held devices. Excludes the Driver/Operator of equipment used in the maintenance and protection of traffic safety.

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day.

NOTE - In order to use the '4 Day/10 Hour Work Schedule,' as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour paid: Journeyworker:

Striping Machine Operator: \$10.03 Linerman Thermoplastic: \$10.03

OVERTIME PAY

See (B, B2, E2, F, S) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 20) on HOLIDAY PAGE
Overtime: See (5, 20) on HOLIDAY PAGE

REGISTERED APPRENTICES

One (1) year terms at the following wage rates:

 1st Term:
 \$ 15.00

 2nd Term:
 18.92

 3rd Term:
 25.22

Supplemental Benefits per hour:

 1st term:
 \$ 9.16

 2nd Term:
 10.03

 3rd Term:
 10.03

8-1456-LS

JOB DESCRIPTION Painter - Metal Polisher

ENTIRE COUNTIES

Albany, Allegany, Bronx, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Dutchess, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Kings, Lewis, Livingston, Madison, Monroe, Montgomery, Nassau, New York, Niagara, Oneida, Onondaga, Ontario, Orange, Orleans, Oswego, Otsego, Putnam, Queens, Rensselaer, Richmond, Rockland, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Suffolk, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Westchester, Wyoming, Yates

WAGES

| | 07/01/2022 |
|------------------|------------|
| Metal Polisher | \$ 37.78 |
| Metal Polisher* | 38.80 |
| Metal Polisher** | 41.78 |

^{*}Note: Applies on New Construction & complete renovation ** Note: Applies when working on scaffolds over 34 feet.

SUPPLEMENTAL BENEFITS

Per Hour: 07/01/2022

Journeyworker:

All classification \$ 11.24

OVERTIME PAY

See (B, E, P, T) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6, 11, 15, 16, 25, 26) on HOLIDAY PAGE Overtime: See (5, 6, 9, 11, 15, 16, 25, 26) on HOLIDAY PAGE

REGISTERED APPRENTICES

Wages per hour:

One (1) year term at the following wage rates:

| | 07/01/2022 |
|------------|------------|
| 1st year | \$ 16.00 |
| 2nd year | 17.00 |
| 3rd year | 18.00 |
| 1st year* | \$ 16.39 |
| 2nd year* | 17.44 |
| 3rd year* | 18.54 |
| 1st year** | \$ 18.50 |
| 2nd year** | 19.50 |
| 3rd year** | 20.50 |

^{*}Note: Applies on New Construction & complete renovation

Supplemental benefits:

Per hour:

| 1st year | \$ 7.99 |
|----------|---------|
| 2nd year | 7.99 |
| 3rd year | 7.99 |

8-8A/28A-MP

Plumber 05/01/2023

JOB DESCRIPTION Plumber

DISTRICT 1

ENTIRE COUNTIES

Clinton, Warren, Washington

PARTIAL COUNTIES

Saratoga: Entire county except the Townships of Stillwater, Halfmoon, Galway, Milton, Charlton, Clifton Park and City of Mechanicville.

WAGES Per hour

07/01/2022

Plumber &

Steamfitter \$ 39.65

^{**} Note: Applies when working on scaffolds over 34 feet.

SUPPLEMENTAL BENEFITS

Per hour

\$ 21.85 Journeyman +10.98*

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (22) on HOLIDAY PAGE See (5, 6, 23) on HOLIDAY PAGE Overtime:

Note: For the paid Christmas Holiday the employee must have worked 20 regular working days in the calendar year with contractor to qualify

Note: Whenever a Holiday falls on a Saturday, the preceding day, Friday, shall be observed as the Holiday. If a Holiday falls on a Sunday, the following day, Monday shall be observed as the Holiday.

REGISTERED APPRENTICES

Wages per hour

One year terms at the following percentage of Journeyman's wage

| 1st yr | 50% |
|--------|-----|
| 2nd yr | 60% |
| 3rd yr | 70% |
| 4th yr | 80% |
| 5th yr | 90% |
| | |

Supplemental Benefits per hour worked

\$ 18.68 + 5.49* 1st yr 2nd yr 19.31 + 6.59* 3rd yr 19.95 + 7.69*4th yr 20.58 + 8.78* 21.22 + 9.88* 5th yr

1-773-SF

Plumber 05/01/2023

JOB DESCRIPTION Plumber **DISTRICT** 1

ENTIRE COUNTIES

Albany, Columbia, Fulton, Greene, Montgomery, Rensselaer, Schenectady, Schoharie

PARTIAL COUNTIES

Hamilton: Only the Towns of Arietta, Benson, Hope, Inlet, Lake Pleasant, Morehouse and Wells.

Saratoga: Only the Towns of Charlton, Clifton Park, Galway, Halfmoon, Milton, Stillwater and Waterford and the city of Mechanicville.

WAGES

Per hour:

Plumber:

07/01/2022 05/01/2023 Additional

Pipefitter, Steamfitter

\$48.30 \$ 2.80

SUPPLEMENTAL BENEFITS

Per hour

Journeyman \$27.74

OVERTIME PAY

See (B1, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE See (5, 6) on HOLIDAY PAGE Overtime:

Note: Whenever a Holiday falls on Saturday, the preceding day, Friday, shall be observed as the Holiday. If a Holiday falls on a Sunday, the following day, Monday shall be observed as the Holiday.

REGISTERED APPRENTICES

Wages per hour

^{*} This portion of the benefit is subject to the SAME PREMIUM as shown for overtime and applicable to paid Holidays

^{*} This portion of the benefit is subject to the SAME PREMIUM as shown for overtime.

^{*} This portion per hour paid.

One year terms at the following percentage of Journeyperson's wage.

1st 2nd 3rd 4th 5th \$ 22.01 \$ 26.79 \$ 31.57 \$ 36.35 \$ 43.52

Supplemental Benefits per hour:

Apprentices Indentured on or before April 30, 2019

All Terms \$ 27.74

Apprentices Indentured on or after May 1st, 2019
Terms 1-4
Terms 5
27.74

1-7-SF

Roofer 05/01/2023

JOB DESCRIPTION Roofer DISTRICT 1

ENTIRE COUNTIES

Albany, Clinton, Columbia, Essex, Fulton, Greene, Hamilton, Montgomery, Rensselaer, Saratoga, Schenectady, Warren, Washington

WAGES

Per hour

| | 07/01/2022 | 07/01/2023 Additional |
|----------------------|------------|--------------------------|
| Roofer/Waterproofer | \$ 33.55 | \$ 2.50 |
| Asphalt Cold Process | 34.05 | |
| Fluid Applied Roof | 34.05 | |
| Pitch & Asbestos | 35.55 | |

Shift Work:

On government mandated shift work starting after 12:00pm and before 4:00am workers shall be paid \$4.00 additional per hour

SUPPLEMENTAL BENEFITS

Per hour

Journeyman \$22.02

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE.

HOLIDAY

Paid: See (1) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

Note: When any Holiday falls on Saturday, the Friday before such Holiday shall be recognized as the legal Holiday. When a Holiday falls on Sunday, it shall be observed the following Monday.

REGISTERED APPRENTICES

Wages per hour

Apprentice terms at the following per cent of the Roofer/Waterproofer rate. For Pitch & Asbestos work, an additional \$2.00 must be paid in wages. For Asphalt Cold Process work and Fluid Applied Roof coating, an additional \$0.50 must be paid in the wages.

1st Term 58% + \$3.00

1500 hrs.

2nd Term 74% + \$3.00

1 yr. and 1500 hrs. as 1st term.

3rd Term 90%

1 yr. and 1500 hrs. as 2nd term.

3rd Term complete at 1 yr and 1050 hrs. as 3rd term

Supplemental Benefits per hour worked

 1st Term
 \$ 17.44

 2nd Term
 17.87

 3rd Term
 21.35

1-241

Sheetmetal Worker 05/01/2023

JOB DESCRIPTION Sheetmetal Worker

DISTRICT 1

DISTRICT 1

ENTIRE COUNTIES

Albany, Clinton, Columbia, Essex, Franklin, Fulton, Greene, Hamilton, Montgomery, Rensselaer, Saratoga, Schenectady, Schoharie, Warren, Washington

WAGES

Per hour

07/01/2022 06/01/2023

Additional

Sheetmetal Worker \$ 36.50 \$ 2.45

All work requiring HAZWOPER Training additional \$1.00 per hour

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Thursday. Friday may be used as a make-up day. NOTE - In order to use the '4 Day/10 Hour Work schedule', as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour

Journeyman \$35.73

OVERTIME PAY

See (B,E,E5,Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

When any holiday falls on Saturday, the Friday before such holiday shall be recognized as the legal holiday. Any holiday falling on Sunday, the following Monday shall be recognized as the legal holiday.

REGISTERED APPRENTICES

Wages per hour

6 Month Terms at the following rate:

| 1st term | \$ 20.27 |
|-----------|----------|
| 2nd term | 21.97 |
| 3rd term | 22.83 |
| 4th term | 23.68 |
| 5th term | 22.40 |
| 6th term | 23.51 |
| 7th term | 25.37 |
| 8th term | 27.22 |
| 9th term | 29.08 |
| 10th term | 30.93 |
| | |

Supplemental Benefits per hour

| 1st term | \$ 22.06 |
|-----------|----------|
| 2nd term | 22.67 |
| 3rd term | 22.98 |
| 4th term | 23.42 |
| 5th term | 30.01 |
| 6th term | 30.46 |
| 7th term | 31.21 |
| 8th term | 31.97 |
| 9th term | 32.72 |
| 10th term | 33.47 |
| | |

1-83

Sprinkler Fitter 05/01/2023

JOB DESCRIPTION Sprinkler Fitter

ENTIRE COUNTIES

Albany, Rensselaer, Saratoga, Schenectady, Warren

WAGES

Per hour 07/01/2022

Sprinkler \$40.81

Fitter

SUPPLEMENTAL BENEFITS

Per hour

Journeyperson \$25.91

OVERTIME PAY

See (B, H) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

Note: When a holiday falls on Sunday, the following Monday shall be considered a holiday and all work performed on either day shall be at the double time rate. When a holiday falls on Saturday, the preceding Friday shall be considered a holiday and all work performed on either day shall be at the double time rate.

REGISTERED APPRENTICES

Wages per hour

One Half Year terms at the following wage.

| 1st | 2nd | 3rd | 4th | 5th | 6th | 7th | 8th | 9th | 10th |
|-------------|--------------|----------|----------|----------|----------|----------|----------|----------|---------------------|
| \$ 18.70 | \$ 20.78 | \$ 22.61 | \$ 24.69 | \$ 26.76 | \$ 28.84 | \$ 30.92 | \$ 33.00 | \$35.08 | \$ 37.15 |
| Supplementa | Benefits per | hour | | | | | | | |
| 1st | 2nd | 3rd | 4th | 5th | 6th | 7th | 8th | 9th | 10th |
| \$ 8.37 | \$ 8.37 | \$ 19.76 | \$ 19.76 | \$ 20.01 | \$ 20.01 | \$ 20.01 | \$ 20.01 | \$ 20.01 | \$ 20.01 1-669-3 |

Teamster - Building 05/01/2023

JOB DESCRIPTION Teamster - Building

DISTRICT 1

ENTIRE COUNTIES

Albany, Columbia, Fulton, Greene, Montgomery, Rensselaer, Saratoga, Schenectady, Schoharie, Washington

PARTIAL COUNTIES

Warren: Only the Townships of Bolton, Warrensburg, Thurman, Stony Creek, Lake George, Lake Luzerne and Queensbury.

WAGES

GROUP # A:

Straight trucks, winch, transit mix on the site, road oilers, dump trucks, pick-ups, panel, water trucks, fuel trucks on the site (including nozzle).

GROUP # B:

Low boy or Low boy trailer, Euclids or similar equipment.

WAGES per hour

07/01/2022

Group A \$ 29.02 Group B 29.32

SUPPLEMENTAL BENEFITS

Per hour 07/01/2022

Journeyperson \$ 27.54

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

Note: Any holiday which occurs on Sunday shall be observed the following Monday.

1-294

Teamster - Heavy&Highway

05/01/2023

JOB DESCRIPTION Teamster - Heavy&Highway

DISTRICT 1

ENTIRE COUNTIES

Albany, Columbia, Fulton, Greene, Hamilton, Herkimer, Montgomery, Oneida, Rensselaer, Saratoga, Schenectady, Schoharie, Washington

PARTIAL COUNTIES

Chenango: Entire county except the Townships of Afton, Bainbridge, Coventry, Greene, Guilford, Oxford and Smithville.

Lewis: Only the Township of Grieg, Lewis, Leyden, Lowville, Lyonsdale, Martinsburg, Turin, West Turin and Watson.

Madison: Only the Townships of Brookfield, Eaton, Hamilton, Lebanon, Lincoln, Madison, Smithfield, Stockbridge and the City of Oneida Otsego: Entire county EXCEPT Townships of Butternuts, Laurens, Maryland, Milford, Morris, Oneonta, Otego, Unidilla and Worchester.

Warren: Only the Townships of Bolton, Warrensburg, Thurman, Stony Creek, Luzerne, Caldwell (Lake George), and Queensbury.

WAGES

GROUP #1:

Warehousemen, Yardmen, Truck Helpers, Pickups, Panel Trucks, Flatboy Material Trucks(straight jobs), Single Axel Dump Trucks, Dumpsters, Material Checkers and Receivers, Greasers, Truck Tiremen, Mechanics Helpers and Parts Chasers.

GROUP #2:

Tandems and Batch Trucks, Mechanics, Dispatcher.

GROUP #3:

Semi-Trailers, Low-boy Trucks, Asphalt Distributor Trucks, and Agitator, Mixer Trucks and dumpcrete type vehicles, Truck Mechanic, Fuel Trucks.

GROUP #4:

Specialized Earth Moving Equipment, Euclid type, or similar off-highway, where not self-loading, Straddle (Ross) Carrier, and self-contained concrete mobile truck.

GROUP #5:

Off-highway Tandem Back-Dump, Twin Engine Equipment and Double-Hitched Equipment where not self-loading.

| WAGES per hour | 07/01/2022 | 07/01/2023 |
|----------------|------------|------------|
| Group #1 | \$ 34.90 | \$ 37.59 |
| Group #2 | 34.96 | 37.65 |
| Group #3 | 35.05 | 37.74 |
| Group #4 | 35.18 | 37.87 |
| Group #5 | 35.34 | 38.03 |
| | | |

Hazardous waste projects that require a Level C or greater protection shall be paid an additional \$ 1.00 per hour.

All employees who work a single irregular work shift starting between 5pm and 1 am on governmental mandated night shifts shall be paid an additional \$1.50 per hour.

For work bid on or after April 1, 1995, there shall be a 12 month carryover of the last posted rate in effect at the time of the bid.

** IMPORTANT NOTICE - EFFECTIVE 04/01/2009 **

Four (4), ten (10) hour days may be worked at straight time during a week, Monday thru Friday.

NOTE - In order to use the '4 Day/10 Hour Work schedule', as your normal schedule, you must submit an 'Employer Registration for Use of 4 Day/10 Hour Work Schedule,' form PW30.1; and there must be a dispensation of hours in place on the project. If the PW30.1 is not submitted you may be liable for overtime payments for work over 8 hours per day.

SUPPLEMENTAL BENEFITS

Per hour:

\$ 27.32 \$ 28.13 +\$1.00 per* +\$1.00 per* hour worked hour worked

(*) not applicable to paid holidays

OVERTIME PAY

See (B, E, Q, X) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE Overtime: See (5, 6) on HOLIDAY PAGE

1-294h/h

Welder 05/01/2023

JOB DESCRIPTION Welder

DISTRICT 1

ENTIRE COUNTIES

Albany, Allegany, Bronx, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Dutchess, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Kings, Lewis, Livingston, Madison, Monroe, Montgomery, Nassau, New York, Niagara, Oneida, Onondaga, Ontario, Orange, Orleans, Oswego, Otsego, Putnam, Queens, Rensselaer, Richmond, Rockland, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Suffolk, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Westchester, Wyoming, Yates

WAGES

Per hour 07/01/2022

Welder: To be paid the same rate of the mechanic performing the work.*

*EXCEPTION: If a specific welder certification is required, then the 'Certified Welder' rate in that trade tag will be paid.

OVERTIME PAY HOLIDAY

1-As Per Trade

Overtime Codes

Following is an explanation of the code(s) listed in the OVERTIME section of each classification contained in the attached schedule. Additional requirements may also be listed in the HOLIDAY section.

NOTE: Supplemental Benefits are 'Per hour worked' (for each hour worked) unless otherwise noted

| (AA) | Time and one half of the hourly rate after 7 and one half hours per day |
|--------|--|
| (A) | Time and one half of the hourly rate after 7 hours per day |
| (B) | Time and one half of the hourly rate after 8 hours per day |
| (B1) | Time and one half of the hourly rate for the 9th & 10th hours week days and the 1st 8 hours on Saturday. Double the hourly rate for all additional hours |
| (B2) | Time and one half of the hourly rate after 40 hours per week |
| (C) | Double the hourly rate after 7 hours per day |
| (C1) | Double the hourly rate after 7 and one half hours per day |
| (D) | Double the hourly rate after 8 hours per day |
| (D1) | Double the hourly rate after 9 hours per day |
| (E) | Time and one half of the hourly rate on Saturday |
| (E1) | Time and one half 1st 4 hours on Saturday; Double the hourly rate all additional Saturday hours |
| (E2) | Saturday may be used as a make-up day at straight time when a day is lost during that week due to inclement weather |
| (E3) | Between November 1st and March 3rd Saturday may be used as a make-up day at straight time when a day is lost during that week due to inclement weather, provided a given employee has worked between 16 and 32 hours that week |
| (E4) | Saturday and Sunday may be used as a make-up day at straight time when a day is lost during that week due to inclement weather |
| (E5) | Double time after 8 hours on Saturdays |
| (F) | Time and one half of the hourly rate on Saturday and Sunday |
| (G) | Time and one half of the hourly rate on Saturday and Holidays |
| (H) | Time and one half of the hourly rate on Saturday, Sunday, and Holidays |
| (1) | Time and one half of the hourly rate on Sunday |
| (J) | Time and one half of the hourly rate on Sunday and Holidays |
| (K) | Time and one half of the hourly rate on Holidays |
| (L) | Double the hourly rate on Saturday |
| (M) | Double the hourly rate on Saturday and Sunday |
| (N) | Double the hourly rate on Saturday and Holidays |
| (O) | Double the hourly rate on Saturday, Sunday, and Holidays |
| (P) | Double the hourly rate on Sunday |
| (Q) | Double the hourly rate on Sunday and Holidays |
| (R) | Double the hourly rate on Holidays |
| (S) | Two and one half times the hourly rate for Holidays |

- (S1) Two and one half times the hourly rate the first 8 hours on Sunday or Holidays One and one half times the hourly rate all additional hours.
- (T) Triple the hourly rate for Holidays
- (U) Four times the hourly rate for Holidays
- (V) Including benefits at SAME PREMIUM as shown for overtime
- (W) Time and one half for benefits on all overtime hours.
- (X) Benefits payable on Paid Holiday at straight time. If worked, additional benefit amount will be required for worked hours. (Refer to other codes listed.)

Holiday Codes

PAID Holidays:

Paid Holidays are days for which an eligible employee receives a regular day's pay, but is not required to perform work. If an employee works on a day listed as a paid holiday, this remuneration is in addition to payment of the required prevailing rate for the work actually performed.

OVERTIME Holiday Pay:

Overtime holiday pay is the premium pay that is required for work performed on specified holidays. It is only required where the employee actually performs work on such holidays. The applicable holidays are listed under HOLIDAYS: OVERTIME. The required rate of pay for these covered holidays can be found in the OVERTIME PAY section listings for each classification.

Following is an explanation of the code(s) listed in the HOLIDAY section of each classification contained in the attached schedule. The Holidays as listed below are to be paid at the wage rates at which the employee is normally classified.

| (1) | None |
|------|---|
| (2) | Labor Day |
| (3) | Memorial Day and Labor Day |
| (4) | Memorial Day and July 4th |
| (5) | Memorial Day, July 4th, and Labor Day |
| (6) | New Year's, Thanksgiving, and Christmas |
| (7) | Lincoln's Birthday, Washington's Birthday, and Veterans Day |
| (8) | Good Friday |
| (9) | Lincoln's Birthday |
| (10) | Washington's Birthday |
| (11) | Columbus Day |
| (12) | Election Day |
| (13) | Presidential Election Day |
| (14) | 1/2 Day on Presidential Election Day |
| (15) | Veterans Day |
| (16) | Day after Thanksgiving |
| (17) | July 4th |
| (18) | 1/2 Day before Christmas |
| (19) | 1/2 Day before New Years |
| (20) | Thanksgiving |
| (21) | New Year's Day |
| (22) | Christmas |
| (23) | Day before Christmas |
| (24) | Day before New Year's |
| (25) | Presidents' Day |
| (26) | Martin Luther King, Jr. Day |
| (27) | Memorial Day |
| (28) | Easter Sunday |

(29) Juneteenth



New York State Department of Labor - Bureau of Public Work State Office Building Campus Building 12 - Room 130 Albany, New York 12240

REQUEST FOR WAGE AND SUPPLEMENT INFORMATION

As Required by Articles 8 and 9 of the NYS Labor Law

 $Fax\ (518)\ 485\text{--}1870\ \text{or mail this form for new schedules or for determination for additional occupations}.$

This Form Must Be Typed

| Submitted By: (Check Only One) Contracting Agency Architect or Engineering | ng Firm Public Work District Office Date: |
|---|--|
| A. Public Work Contract to be let by: (Enter Data Pertaining t | o Contracting/Public Agency) |
| 1. Name and complete address | 2. NY State Units (see Item 5) 01 DOT 02 OGS 03 Dormitory Authority 04 State University Construction Fund 05 Mental Hygiene Facilities Corp. 06 OTHER N.Y. STATE UNIT 07 City 08 Local School District 09 Special Local District, i.e., Fire, Sewer, Water District 10 Village 11 Town 12 County 13 Other Non-N.Y. State (Describe) |
| E-Mail: 3. SEND REPLY TO | 4. SERVICE REQUIRED. Check appropriate box and provide project information. New Schedule of Wages and Supplements. APPROXIMATE BID DATE: Additional Occupation and/or Redetermination |
| Telephone:() Fax: () E-Mail: | PRC NUMBER ISSUED PREVIOUSLY FOR THIS PROJECT : |
| B. PROJECT PARTICULARS | |
| 5. Project Title Description of Work Contract Identification Number Note: For NYS units, the OSC Contract No. | 6. Location of Project: Location on Site Route No/Street Address Village or City Town County |
| 7. Nature of Project - Check One: 1. New Building 2. Addition to Existing Structure 3. Heavy and Highway Construction (New and Repair) 4. New Sewer or Waterline 5. Other New Construction (Explain) 6. Other Reconstruction, Maintenance, Repair or Alteration 7. Demolition 8. Building Service Contract | 8. OCCUPATION FOR PROJECT : Construction (Building, Heavy Highway/Sewer/Water) Tunnel Residential Landscape Maintenance Elevator Moving furniture and equipment Elevator maintenance Elevator maintenance Exterminators, Fumigators Fire Safety Director, NYC Only Guards, Watchmen Guards, Watchmen Howards Moving furniture and equipment Evaluation Trash and refuse removal Window cleaners Other (Describe) |
| 9. Has this project been reviewed for compliance with the W | icks Law involving separate bidding? YES ☐ NO ☐ |
| 10. Name and Title of Requester | Signature |



NEW YORK STATE DEPARTMENT OF LABOR Bureau of Public Work - Debarment List

LIST OF EMPLOYERS INELIGIBLE TO BID ON OR BE AWARDED ANY PUBLIC WORK CONTRACT

Under Article 8 and Article 9 of the NYS Labor Law, a contractor, sub-contractor and/or its successor shall be debarred and ineligible to submit a bid on or be awarded any public work or public building service contract/sub-contract with the state, any municipal corporation or public body for a period of five (5) years from the date of debarment when:

- Two (2) final determinations have been rendered within any consecutive six-year (6) period determining that such contractor, sub-contractor and/or its successor has WILLFULLY failed to pay the prevailing wage and/or supplements;
- One (1) final determination involves falsification of payroll records or the kickback of wages and/or supplements.

The agency issuing the determination and providing the information, is denoted under the heading 'Fiscal Officer'. DOL = New York State Department of Labor; NYC = New York City Comptroller's Office; AG = New York State Attorney General's Office; DA = County District Attorney's Office.

<u>Debarment Database:</u> To search for contractors, sub-contractors and/or their successors debarred from bidding or being awarded any public work contract or subcontract under NYS Labor Law Articles 8 and 9, <u>or</u> under NYS Workers' Compensation Law Section 141-b, access the database at this link: https://applications.labor.ny.gov/EDList/searchPage.do

For inquiries where WCB is listed as the "Agency", please call 1-866-546-9322

| AGENCY | Fiscal Officer | FEIN | EMPLOYER NAME | EMPLOYER DBA NAME | ADDRESS | DEBARMENT START DATE | DEBARMENT END DATE |
|--------|----------------|------------|--|----------------------|--|-------------------------|-----------------------|
| DOL | DOL | ****5754 | 0369 CONTRACTORS, LLC | | 515 WEST AVE UNIT PH 13NORWALK CT 06850 | 05/12/2021 | 05/12/2026 |
| DOL | DOL | ****4018 | ADIRONDACK BUILDING RESTORATION INC. | | 4156 WILSON ROAD EAST TABERG NY 13471 | 03/26/2019 | 03/26/2024 |
| DOL | AG | ****1812 | ADVANCED BUILDERS & LAND DEVELOPMENT, INC. | | 400 OSER AVE #2300HAUPPAUGE NY 11788 | 09/11/2019 | 09/11/2024 |
| DOL | DOL | ****1687 | ADVANCED SAFETY SPRINKLER INC | | 261 MILL ROAD P.O BOX 296EAST AURORA NY 14052 | 05/29/2019 | 05/29/2024 |
| DOL | NYC | | AGOSTINHO TOME | | 405 BARRETTO ST BRONX NY 10474 | 05/31/2018 | 05/31/2023 |
| DOL | NYC | | ALL COUNTY SEWER & DRAIN, INC. | | 7 GREENFIELD DR WARWICK NY 10990 | 03/25/2022 | 03/25/2027 |
| DOL | NYC | | AMJED PARVEZ | | 401 HANOVER AVENUE STATEN ISLAND NY 10304 | 01/11/2021 | 01/11/2026 |
| DOL | DOL | | ANGELO F COKER | | 2610 SOUTH SALINA STREET SUITE 14SYRACUSE NY 13205 | 09/17/2020 | 09/17/2025 |
| DOL | DOL | | ANGELO F COKER | | 2610 SOUTH SALINA STREET SUITE 14SYRACUSE NY 13205 | 12/04/2018 | 12/04/2023 |
| DOL | DOL | | ANGELO GARCIA | | 515 WEST AVE UNIT PH 13NORWALK CT 06850 | 05/12/2021 | 05/12/2026 |
| DOL | DOL | | ANGELO TONDO | | 449 WEST MOMBSHA ROAD MONROE NY 10950 | 06/06/2022 | 06/06/2027 |
| DOL | DOL | | ANITA SALERNO | | 158 SOLAR ST SYRACUSE NY 13204 | 01/07/2019 | 01/07/2024 |
| DOL | DOL | ****4231 | ANKER'S ELECTRIC SERVICE, INC. | | 10 SOUTH 5TH ST LOCUST VALLEY NY 11560 | 09/26/2022 | 09/26/2027 |
| DOL | DOL | | ANTONIO ESTIVEZ | | 442 ARMONK RD MOUNT KISCO NY 10549 | 06/12/2018 | 06/12/2023 |
| DOL | NYC | | ARADCO CONSTRUCTION CORP | | 115-46 132RD ST SOUTH OZONE PARK NY 11420 | 09/17/2020 | 09/17/2025 |
| DOL | DOL | | ARNOLD A. PAOLINI | | 1250 BROADWAY ST BUFFALO NY 14212 | 02/03/2020 | 02/03/2025 |
| DOL | NYC | | ARSHAD MEHMOOD | | 168-42 88TH AVENUE JAMAICA NY 11432 | 11/20/2019 | 11/20/2024 |
| DOL | NYC | ****2591 | AVI 212 INC. | | 260 CROPSEY AVENUE APT 11GBROOKLYN NY 11214 | 10/30/2018 | 10/30/2023 |
| DOL | NYC | | AVM CONSTRUCTION CORP | | 117-72 123RD ST SOUTH OZONE PARK NY 11420 | 09/17/2020 | 09/17/2025 |
| DOL | NYC | | AZIDABEGUM | | 524 MCDONALD AVENUE BROOKLYN NY 11218 | 09/17/2020 | 09/17/2025 |
| DOL | DOL | ****8421 | B & B DRYWALL, INC | | 206 WARREN AVE APT 1WHITE PLAINS NY 10603 | 12/14/2021 | 12/14/2026 |
| DOL | NYC | | BALWINDER SINGH | | 421 HUDSON ST SUITE C5NEW YORK NY 10014 | 02/20/2019 | 02/20/2024 |
| DOL | NYC | ****8416 | BEAM CONSTRUCTION, INC. | | 50 MAIN ST WHITE PLAINS NY 10606 | 01/04/2019 | 01/04/2024 |
| DOL | DOL | | BERNARD BEGLEY | | 38 LONG RIDGE ROAD BEDFORD NY 10506 | 12/18/2019 | 12/18/2024 |
| DOL | NYC | ****2113 | BHW CONTRACTING, INC. | | 401 HANOVER AVENUE STATEN ISLAND NY 10304 | 01/11/2021 | 01/11/2026 |
| DOL | DOL | | BIAGIO CANTISANI | | | 06/12/2018 | 06/12/2023 |
| DOL | DOL | ****3627 | BJB CONSTRUCTION CORP. | | 38 LONG RIDGE ROAD BEDFORD NY 10506 | 12/18/2019 | 12/18/2024 |
| DOL | DOL | ****4512 | BOB BRUNO EXCAVATING, INC | | 5 MORNINGSIDE DR AUBURN NY 13021 | 05/28/2019 | 05/28/2024 |
| DOL | DOL | | BOGDAN MARKOVSKI | | 370 W. PLEASANTVIEW AVE SUITE 2.329HACKENSACK NJ 07601 | 02/11/2019 | 02/11/2024 |
| DOL | DOL | | BRADLEY J SCHUKA | | 4 BROTHERS ROAD WAPPINGERS FALLS NY 12590 | 10/20/2020 | 10/20/2025 |
| DOL | DOL | | BRUCE P. NASH JR. | | 5841 BUTTERNUT ROAD EAST SYRACUSE NY 13057 | 09/12/2018 | 09/12/2023 |
| DOL | DOL | ****9383 | C.C. PAVING AND EXCAVATING, INC. | | 2610 SOUTH SALINA ST SUITE 12SYRACUSE NY 13205 | 09/17/2020 | 09/17/2025 |
| DOL | DOL | ****9383 | C.C. PAVING AND EXCAVATING, INC. | | 2610 SOUTH SALINA ST SUITE 12SYRACUSE NY 13205 | 12/04/2018 | 12/04/2023 |
| 201 | 50 | ***** 1000 | O D D ENTERDRICE INO | | D.O. DOV 004 | 00/00/0000 | 00/00/0005 |

| Γ | Т | _ | _ | T | <u> </u> | | T |
|-----|-----|-----------|---|--|--|------------|------------|
| DOL | DOL | ****5161 | CALADRI DEVELOPMENT CORP. | | 1223 PARK ST. PEEKSKILL NY 10566 | 05/17/2021 | 05/17/2026 |
| DOL | DOL | ****3391 | CALI ENTERPRISES, INC. | | 1223 PARK STREET PEEKSKILL NY 10566 | 05/17/2021 | 05/17/2026 |
| DOL | NYC | | CALVIN WALTERS | | 465 EAST THIRD ST MT. VERNON NY 10550 | 09/09/2019 | 09/09/2024 |
| DOL | DOL | | CANTISANI & ASSOCIATES LTD | | 442 ARMONK RD MOUNT KISCSO NY 10549 | 06/12/2018 | 06/12/2023 |
| DOL | DOL | | CANTISANI HOLDING LLC | | | 06/12/2018 | 06/12/2023 |
| DOL | DOL | | CARMEN RACHETTA | | 8531 OSWEGO RD BALDWINSVILLE NY 13027 | 02/03/2020 | 02/03/2025 |
| DOL | DOL | ****3812 | CARMODY "2" INC | | | 06/12/2018 | 06/12/2023 |
| DOL | DOL | ****1143 | CARMODY BUILDING CORP | CARMODY CONTRACTIN G AND CARMODY CONTRACTIN G CORP. | 442 ARMONK RD MOUNT KISCO NY 10549 | 06/12/2018 | 06/12/2023 |
| DOL | DOL | | CARMODY CONCRETE CORPORATION | | | 06/12/2018 | 06/12/2023 |
| DOL | DOL | | CARMODY ENTERPRISES, LTD. | | 442 ARMONK RD MOUNT KISCO NY 10549 | 06/12/2018 | 06/12/2023 |
| DOL | DOL | | CARMODY INC | | 442 ARMONK RD MOUNT KISCO NY 10549 | 06/12/2018 | 06/12/2023 |
| DOL | DOL | ****3812 | CARMODY INDUSTRIES INC | | | 06/12/2018 | 06/12/2023 |
| DOL | DOL | | CARMODY MAINTENANCE CORPORATION | | 442 ARMONK RD MOUNT KISCO NY 10549 | 06/12/2018 | 06/12/2023 |
| DOL | DOL | | CARMODY MASONRY CORP | | 442 ARMONK RD MOUNT KISCO NY 10549 | 06/12/2018 | 06/12/2023 |
| DOL | AG | ****7247 | CENTURY CONCRETE CORP | | 2375 RAYNOR ST RONKONKOMA NY 11779 | 08/04/2021 | 08/04/2026 |
| DOL | DOL | *****0026 | CHANTICLEER CONSTRUCTION LLC | | 4 BROTHERS ROAD WAPPINGERS FALLS NY 12590 | 10/20/2020 | 10/20/2025 |
| DOL | NYC | | CHARLES ZAHRADKA | | 863 WASHINGTON STREET FRANKLIN SQUARE NY 11010 | 03/10/2020 | 03/10/2025 |
| DOL | DOL | | CHRISTOPHER GRECO | | 26 NORTH MYRTLE AVENUE SPRING VALLEY NY 10956 | 02/18/2021 | 02/18/2026 |
| DOL | DOL | | CHRISTOPHER J MAINI | | 19 CAITLIN AVE JAMESTOWN NY 14701 | 09/17/2018 | 09/17/2023 |
| DOL | DOL | | CHRISTOPHER PAPASTEFANOU A/K/A CHRIS PAPASTEFANOU | | 1445 COMMERCE AVE BRONX NY 10461 | 05/30/2019 | 05/30/2024 |
| DOL | DOL | ****1927 | CONSTRUCTION PARTS WAREHOUSE, INC. | CPW | 5841 BUTTERNUT ROAD EAST SYRACUSE NY 13057 | 09/12/2018 | 09/12/2023 |
| DOL | DOL | | CRAIG JOHANSEN | | 10 SOUTH 5TH ST LOCUST VALLEY NY 11560 | 09/26/2022 | 09/26/2027 |
| DOL | DOL | ****3228 | CROSS-COUNTY LANDSCAPING AND TREE SERVICE, INC. | ROCKLAND TREE SERVICE | 26 NORTH MYRTLE AVENUE SPRING VALLEY NY 10956 | 02/18/2021 | 02/18/2026 |
| DOL | DOL | ****2524 | CSI ELECTRICAL & MECHANICAL INC | | 42-32 235TH ST DOUGLASTON NY 11363 | 01/14/2019 | 01/14/2024 |
| DOL | DOL | ****7619 | DANCO CONSTRUCTION UNLIMITED INC. | | 485 RAFT AVENUE HOLBROOK NY 11741 | 10/19/2021 | 10/19/2026 |
| DOL | DOL | | DANIEL ROBERT MCNALLY | | 7 GREENFIELD DRIVE WARWICK NY 10990 | 03/25/2022 | 03/25/2027 |
| DOL | DOL | | DARIAN L COKER | | 2610 SOUTH SALINA ST SUITE 2CSYRACUSE NY 13205 | 09/17/2020 | 09/17/2025 |
| DOL | DOL | | DARIAN L COKER | | 2610 SOUTH SALINA ST SUITE 2CSYRACUSE NY 13205 | 12/04/2018 | 12/04/2023 |
| DOL | NYC | | DAVID WEINER | | 14 NEW DROP LANE 2ND FLOORSTATEN ISLAND NY 10306 | 11/14/2019 | 11/14/2024 |
| DOL | DOL | | DELPHI PAINTING & DECORATING CO INC | | 1445 COMMERCE AVE BRONX NY 10461 | 05/30/2019 | 05/30/2024 |
| DOL | DOL | ****5175 | EAGLE MECHANICAL AND GENERAL CONSTRUCTION LLC | | 11371 RIDGE RD WOLCOTT NY 14590 | 02/03/2020 | 02/03/2025 |
| DOL | AG | | EDWIN HUTZLER | | 23 NORTH HOWELLS RD BELLPORT NY 11713 | 08/04/2021 | 08/04/2026 |
| DOL | DA | | EDWIN HUTZLER | | 2375 RAYNOR STREET RONKONKOMA NY 11779 | 08/04/2021 | 08/04/2026 |
| DOL | DOL | *****0780 | EMES HEATING & PLUMBING | | 5 EMES LANE | 01/20/2002 | 01/20/3002 |

| | 1 | • | | | | | |
|-----|-----|-----------|--|-----------------------------|---|------------|------------|
| DOL | NYC | *****5917 | EPOCH ELECTRICAL, INC | | 97-18 50TH AVE CORONA NY 11368 | 04/19/2018 | 04/19/2024 |
| DOL | DOL | | FAIGY LOWINGER | | 11 MOUNTAIN RD 28 VAN BUREN DRMONROE NY 10950 | 03/20/2019 | 03/20/2024 |
| DOL | DOL | | FRANK BENEDETTO | | 19 CATLIN AVE JAMESTOWN NY 14701 | 09/17/2018 | 09/17/2023 |
| DOL | DOL | ****4722 | FRANK BENEDETTO AND CHRISTOPHER J MAINI | B & M CONCRETE | 19 CAITLIN AVE JAMESTOWN NY 14701 | 09/17/2018 | 09/17/2023 |
| DOL | DA | | FREDERICK HUTZLER | | 2375 RAYNOR STREET RONKONKOMA NY 11779 | 08/04/2021 | 08/04/2026 |
| DOL | NYC | ****6616 | G & G MECHANICAL ENTERPRISES, LLC. | | 1936 HEMPSTEAD TURNPIKE EAST MEDOW NY 11554 | 11/29/2019 | 11/29/2024 |
| DOL | DOL | | GABRIEL FRASSETTI | | | 04/10/2019 | 04/10/2024 |
| DOL | NYC | | GAYATRI MANGRU | | 21 DAREWOOD LANE VALLEY STREAM NY 11581 | 09/17/2020 | 09/17/2025 |
| DOL | DOL | | GEOFF CORLETT | | 415 FLAGGER AVE #302STUART FL 34994 | 10/31/2018 | 10/31/2023 |
| DOL | DA | | GEORGE LUCEY | | 150 KINGS STREET BROOKLYN NY 11231 | 01/19/1998 | 01/19/2998 |
| DOL | DOL | | GIGI SCHNECKENBURGER | | 261 MILL RD EAST AURORA NY 14052 | 05/29/2019 | 05/29/2024 |
| DOL | NYC | ****3164 | GLOBE GATES INC | GLOBAL OVERHEAD DOORS | 405 BARRETTO ST BRONX NY 10474 | 05/31/2018 | 05/31/2023 |
| DOL | DOL | | HANS RATH | | 24 ELDOR AVENUE NEW CITY NY 10956 | 02/03/2020 | 02/03/2025 |
| DOL | DOL | | HERBERT CLEMEN | | 42 FOWLER AVENUE CORTLAND MANOR NY 10567 | 01/24/2023 | 01/24/2028 |
| DOL | DOL | | HERBERT CLEMEN | | 42 FOWLER AVENUE CORTLAND MANOR NY 10567 | 10/25/2022 | 10/25/2027 |
| DOL | DOL | ****5131 | INTEGRITY MASONRY, INC. | M&R CONCRETE | 722 8TH AVE WATERVLIET NY 12189 | 06/05/2018 | 06/05/2023 |
| DOL | DOL | | IRENE KASELIS | | 32 PENNINGTON AVE WALDWICK NJ 07463 | 05/30/2019 | 05/30/2024 |
| DOL | DOL | ****9211 | J. WASE CONSTRUCTION CORP. | | 8545 RT 9W ATHENS NY 12015 | 03/09/2021 | 03/09/2026 |
| DOL | DOL | | J.M.J CONSTRUCTION | | 151 OSTRANDER AVENUE SYRACUSE NY 13205 | 11/21/2022 | 11/21/2027 |
| DOL | DOL | | J.R. NELSON CONSTRUCTION | | 531 THIRD STREET ALBANY NY 12206 | 12/22/2022 | 12/22/2027 |
| DOL | DOL | | J.R. NELSON CONSTRUCTION | | 531 THIRD STREET ALBANY NY 12206 | 10/25/2022 | 10/25/2027 |
| DOL | DOL | | J.R. NELSON, LLC | | 531 THIRD STREET ALBANY NY 12206 | 12/22/2022 | 12/22/2027 |
| DOL | DOL | | J.R. NELSON, LLC | | 531 THIRD STREET ALBANY NY 12206 | 10/25/2022 | 10/25/2027 |
| DOL | DOL | | J.R.N COMPANIES, LLC | | 531 THIRD STREET ALBANY NY 12206 | 12/12/2022 | 12/12/2027 |
| DOL | DOL | | J.R.N COMPANIES, LLC | | 531 THIRD STREET ALBANY NY 12206 | 10/25/2022 | 10/25/2027 |
| DOL | DOL | ****1147 | J.R.N. CONSTRUCTION, LLC | | 531 THIRD ST ALBANY NY 12206 | 12/22/2022 | 12/22/2027 |
| DOL | DOL | ****1147 | J.R.N. CONSTRUCTION, LLC | | 531 THIRD ST ALBANY NY 12206 | 10/25/2022 | 10/25/2027 |
| DOL | DOL | | JAMES C. DELGIACCO | | 722 8TH AVE WATERVLIET NY 12189 | 06/05/2018 | 06/05/2023 |
| DOL | DOL | | JAMES J. BAKER | | 7901 GEE ROAD CANASTOTA NY 13032 | 08/17/2021 | 08/17/2026 |
| DOL | DOL | | JAMES LIACONE | | 9365 WASHINGTON ST LOCKPORT IL 60441 | 07/23/2018 | 07/23/2023 |
| DOL | DOL | | JAMES RACHEL | | 9365 WASHINGTON ST LOCKPORT IL 60441 | 07/23/2018 | 07/23/2023 |
| DOL | DOL | | JASON P. RACE | | 3469 STATE RT. 69 PERISH NY 13131 | 09/29/2021 | 09/29/2026 |
| DOL | DOL | | JASON P. RACE | | 3469 STATE RT. 69 PERISH NY 13131 | 02/09/2022 | 02/09/2027 |
| DOL | DOL | | JASON P. RACE | | 3469 STATE RT. 69 PERISH NY 13131 | 11/15/2022 | 11/15/2027 |
| DOL | DOL | | JASON P. RACE | | 3469 STATE RT. 69 PERISH NY 13131 | 03/01/2022 | 03/01/2027 |
| DOL | DOL | ****7993 | JBS DIRT, INC. | | 7901 GEE ROAD CANASTOTA NY 13032 | 08/17/2021 | 08/17/2026 |


| DOL | DOL | ****5368 | JCH MASONRY & LANDSCAPING INC. | | 35 CLINTON AVE OSSINING NY 10562 | 09/12/2018 | 09/12/2023 |
|-----|-----|-----------|---|-----------------|---|------------|------------|
| DOL | DOL | ****2435 | JEFFEL D. JOHNSON | JMJ7 AND SON | 5553 CAIRNSTRAIL CLAY NY 13041 | 11/21/2022 | 11/21/2027 |
| DOL | DOL | | JEFFEL JOHNSON ELITE CARPENTER REMODEL AND CONSTRUCTION | 30N | C2 EVERGREEN CIRCLE LIVERPOOL NY 13090 | 11/21/2022 | 11/21/2027 |
| DOL | DOL | ****2435 | JEFFREY M. JOHNSON | JMJ7 AND SON | 5553 CAIRNS TRAIL CLAY NY 13041 | 11/21/2022 | 11/21/2027 |
| DOL | NYC | | JENNIFER GUERRERO | CON | 1936 HEMPSTEAD TURNPIKE EAST MEADOW NY 11554 | 11/29/2019 | 11/29/2024 |
| DOL | DOL | | JIM PLAUGHER | | 17613 SANTE FE LINE ROAD WAYNEFIELD OH 45896 | 07/16/2021 | 07/16/2026 |
| DOL | DOL | | JMJ7 & SON CONSTRUCTION, LLC | | 5553 CAIRNS TRAIL LIVERPOOL NY 13041 | 11/21/2022 | 11/21/2027 |
| DOL | DOL | | JMJ7 AND SONS CONTRACTORS | | 5553 CAIRNS TRAIL CLAY NY 13041 | 11/21/2022 | 11/21/2027 |
| DOL | DOL | | JMJ7 CONTRACTORS | | 7014 13TH AVENUE BROOKLYN NY 11228 | 11/21/2022 | 11/21/2027 |
| DOL | DOL | | JMJ7 CONTRACTORS AND SONS | | 5553 CAIRNS TRAIL CLAY NY 13041 | 11/21/2022 | 11/21/2027 |
| DOL | DOL | | JMJ7 CONTRACTORS, LLC | | 5553 CAIRNS TRAIL CLAY NY 13041 | 11/21/2022 | 11/21/2027 |
| DOL | DOL | | JOHN GOCEK | | 14B COMMERCIAL AVE ALBANY NY 12065 | 11/14/2019 | 11/14/2024 |
| DOL | DOL | | JOHN MARKOVIC | | 47 MANDON TERRACE HAWTHORN NJ 07506 | 03/29/2021 | 03/29/2026 |
| DOL | DOL | | JOHN WASE | | 8545 RT 9W ATHENS NY 12015 | 03/09/2021 | 03/09/2026 |
| DOL | DOL | | JON E DEYOUNG | | 261 MILL RD P.O BOX 296EAST AURORA NY 14052 | 05/29/2019 | 05/29/2024 |
| DOL | DOL | | JORGE RAMOS | | 8970 MIKE GARCIA DR MANASSAS VA 20109 | 07/16/2021 | 07/16/2026 |
| DOL | DOL | | JORI PEDERSEN | | 415 FLAGER AVE #302STUART FL 34994 | 10/31/2018 | 10/31/2023 |
| DOL | DOL | | JOSE CHUCHUCA | | 35 CLINTON AVE OSSINING NY 10562 | 09/12/2018 | 09/12/2023 |
| DOL | DOL | | JOY MARTIN | | 2404 DELAWARE AVE NIGARA FALLS NY 14305 | 09/12/2018 | 09/12/2023 |
| DOL | DOL | ****5116 | JP RACE PAINTING, INC. T/A RACE PAINTING | | 3469 STATE RT. 69 PERISH NY 13131 | 02/09/2022 | 02/09/2027 |
| DOL | DOL | ****5116 | JP RACE PAINTING, INC. T/A RACE PAINTING | | 3469 STATE RT. 69 PERISH NY 13131 | 11/15/2022 | 11/15/2027 |
| DOL | DOL | ****5116 | JP RACE PAINTING, INC. T/A RACE PAINTING | | 3469 STATE RT. 69 PERISH NY 13131 | 09/29/2021 | 09/29/2026 |
| DOL | DOL | ****5116 | JP RACE PAINTING, INC. T/A RACE PAINTING | | 3469 STATE RT. 69 PERISH NY 13131 | 03/01/2022 | 03/01/2027 |
| DOL | DOL | ****5116 | JP RACE PAINTING, INC. T/A RACE PAINTING | | 3469 STATE RT. 69 PERISH NY 13131 | 03/01/2022 | 03/01/2027 |
| DOL | DOL | ****1147 | JRN CONSTRUCTION, LLC | | 531 THIRD STREET ALBANY NY 12206 | 10/25/2022 | 10/25/2027 |
| DOL | DOL | ****1147 | JRN CONSTRUCTION, LLC | | 531 THIRD STREET ALBANY NY 12206 | 12/22/2022 | 12/22/2027 |
| DOL | DOL | | JRN PAVING, LLC | | 531 THIRD STREET ALBANY NY 12206 | 10/25/2022 | 10/25/2027 |
| DOL | DOL | | JRN PAVING, LLC | | 531 THIRD STREET ALBANY NY 12206 | 12/22/2022 | 12/22/2027 |
| DOL | DOL | | JULIUS AND GITA BEHREND | | 5 EMES LANE MONSEY NY 10952 | 11/20/2002 | 11/20/3002 |
| DOL | DOL | | KARIN MANGIN | | 796 PHELPS ROAD FRANKLIN LAKES NJ 07417 | 12/01/2020 | 12/01/2025 |
| DOL | DOL | | KATE E. CONNOR | | 7088 INTERSTATE ISLAND RD SYRACUSE NY 13209 | 03/31/2021 | 03/31/2026 |
| DOL | DOL | ****2959 | KELC DEVELOPMENT, INC | | 7088 INTERSTATE ISLAND RD SYRACUSE NY 13209 | 03/31/2021 | 03/31/2026 |
| DOL | DOL | | KIMBERLY F. BAKER | | 7901 GEE ROAD CANASTOTA NY 13032 | 08/17/2021 | 08/17/2026 |
| DOL | DOL | ****3490 | L & M CONSTRUCTION/DRYWALL INC. | | 1079 YONKERS AVE YONKERS NY 10704 | 08/07/2018 | 08/07/2023 |
| DOL | DA | *****8816 | LAKE CONSTRUCTION AND DEVELOPMENT CORPORATION | | 150 KINGS STREET BROOKLYN NY 11231 | 08/19/1998 | 08/19/2998 |

| DOL | DOL | | LEROY E. NELSON JR | | 531 THIRD ST ALBANY NY 12206 | 10/25/2022 | 10/25/2027 |
|-----|-----|-----------|---|------------------------------------|---|------------|------------|
| DOL | DOL | | LEROY E. NELSON JR | | 531 THIRD ST ALBANY NY 12206 | 12/22/2022 | 12/22/2027 |
| DOL | AG | ****3291 | LINTECH ELECTRIC, INC. | | 3006 TILDEN AVE BROOKLYN NY 11226 | 02/16/2022 | 02/16/2027 |
| DOL | DA | ****4460 | LONG ISLAND GLASS & STOREFRONTS, LLC | | 4 MANHASSET TRL RIDGE NY 11961 | 09/06/2018 | 09/06/2023 |
| DOL | DOL | | LOUIS A. CALICCHIA | | 1223 PARK ST. PEEKSKILL NY 10566 | 05/17/2021 | 05/17/2026 |
| DOL | NYC | | LUBOMIR PETER SVOBODA | | 27 HOUSMAN AVE STATEN ISLAND NY 10303 | 12/26/2019 | 12/26/2024 |
| DOL | NYC | | M & L STEEL & ORNAMENTAL IRON CORP. | | 27 HOUSMAN AVE STATEN ISLAND NY 10303 | 12/26/2019 | 12/26/2024 |
| DOL | DOL | ****2196 | MAINSTREAM SPECIALTIES, INC. | | 11 OLD TOWN RD SELKIRK NY 12158 | 02/02/2021 | 02/02/2026 |
| DOL | DA | | MANUEL P TOBIO | | 150 KINGS STREET BROOKLYN NY 14444 | 08/19/1998 | 08/19/2998 |
| DOL | DA | | MANUEL TOBIO | | 150 KINGS STREET BROOKLYN NY 11231 | 08/19/1998 | 08/19/2998 |
| DOL | NYC | | MAREK FABIJANOWSKI | | 50 MAIN ST WHITE PLAINS NY 10606 | 01/04/2019 | 01/04/2024 |
| DOL | NYC | | MARIA NUBILE | | 84-22 GRAND AVENUE ELMHURST NY 11373 | 03/10/2020 | 03/10/2025 |
| DOL | DOL | | MASONRY CONSTRUCTION, INC. | | 442 ARMONK RD MOUNT KISCO NY 10549 | 06/12/2018 | 06/12/2023 |
| DOL | DOL | *****3333 | MASONRY INDUSTRIES, INC. | | 442 ARMONK RD MOUNT KISCO NY 10549 | 06/12/2018 | 06/12/2023 |
| DOL | DOL | | MATTHEW P. KILGORE | | 4156 WILSON ROAD EAST TABERG NY 13471 | 03/26/2019 | 03/26/2024 |
| DOL | DOL | | MAURICE GAWENO | | 442 ARMONK RD MOUNT KISCO NY 10549 | 06/12/2018 | 06/12/2023 |
| DOL | DOL | | MICHAEL LENIHAN | | 1079 YONKERS AVE UNIT 4YONKERS NY 10704 | 08/07/2018 | 08/07/2023 |
| DOL | DOL | ****4829 | MILESTONE ENVIRONMENTAL CORPORATION | | 704 GINESI DRIVE SUITE 29MORGANVILLE NJ 07751 | 04/10/2019 | 04/10/2024 |
| DOL | NYC | ****9926 | MILLENNIUM FIRE PROTECTION, LLC | | 325 W. 38TH STREET SUITE 204NEW YORK NY 10018 | 11/14/2019 | 11/14/2024 |
| DOL | NYC | *****0627 | MILLENNIUM FIRE SERVICES, LLC | | 14 NEW DROP LNE 2ND FLOORSTATEN ISLAND NY 10306 | 11/14/2019 | 11/14/2024 |
| DOL | DOL | ****1320 | MJC MASON CONTRACTING, INC. | | 42 FOWLER AVENUE CORTLAND MANOR NY 10567 | 10/25/2022 | 10/25/2027 |
| DOL | DOL | ****1320 | MJC MASON CONTRACTING, INC. | | 42 FOWLER AVENUE CORTLAND MANOR NY 10567 | 01/24/2023 | 01/24/2028 |
| DOL | NYC | | MUHAMMED A. HASHEM | | 524 MCDONALD AVENUE BROOKLYN NY 11218 | 09/17/2020 | 09/17/2025 |
| DOL | NYC | | NAMOW, INC. | | 84-22 GRAND AVENUE ELMHURST NY 11373 | 03/10/2020 | 03/10/2025 |
| DOL | DA | *****9786 | NATIONAL INSULATION & GC CORP | | 180 MILLER PLACE HICKSVILLE NY 11801 | 12/12/2018 | 12/12/2023 |
| DOL | NYC | | NAVIT SINGH | | 402 JERICHO TURNPIKE NEW HYDE PARK NY 11040 | 08/10/2022 | 08/10/2027 |
| DOL | DOL | | NICHOLE E. FRASER A/K/A NICHOLE RACE | | 3469 STATE RT. 69 PERISH NY 13131 | 03/01/2022 | 03/01/2027 |
| DOL | DOL | | NICHOLE E. FRASER A/K/A NICHOLE RACE | | 3469 STATE RT. 69 PERISH NY 13131 | 11/15/2022 | 11/15/2027 |
| DOL | DOL | | NICHOLE E. FRASER A/K/A NICHOLE RACE | | 3469 STATE RT. 69 PERISH NY 13131 | 09/29/2021 | 09/29/2026 |
| DOL | DOL | | NICHOLE E. FRASER A/K/A NICHOLE RACE | | 3469 STATE RT. 69 PERISH NY 13131 | 02/09/2022 | 02/09/2027 |
| DOL | DOL | ****7429 | NICOLAE I. BARBIR | BESTUCCO CONSTRUCTI ON, INC. | 444 SCHANTZ ROAD ALLENTOWN PA 18104 | 09/17/2020 | 09/17/2025 |
| DOL | NYC | ****5643 | NYC LINE CONTRACTORS, INC. | 21,, | 402 JERICHO TURNPIKE NEW HYDE PARK NY 11040 | 08/10/2022 | 08/10/2027 |
| DOL | DOL | | PAULINE CHAHALES | | 935 S LAKE BLVD MAHOPAC NY 10541 | 03/02/2021 | 03/02/2026 |
| DOL | DOL | | PETER STEVENS | | 11 OLD TOWN ROAD SELKIRK NY 12158 | 02/02/2021 | 02/02/2026 |
| DOL | DOL | | PETER STEVENS | | 8269 21ST ST BELLEROSE NY 11426 | 12/22/2022 | 12/22/2027 |

| DOL | DOL | *****0466 | PRECISION BUILT FENCES, INC. | | 1617 MAIN ST PEEKSKILL NY 10566 | 03/03/2020 | 03/03/2025 |
|-----|-----|-----------|--|-------------------------------|--|------------|------------|
| DOL | NYC | | RASHEL CONSTRUCTION CORP | | 524 MCDONALD AVENUE BROOKLYN NY 11218 | 09/17/2020 | 09/17/2025 |
| DOL | DOL | *****1068 | RATH MECHANICAL CONTRACTORS, INC. | | 24 ELDOR AVENUE NEW CITY NY 10956 | 02/03/2020 | 02/03/2025 |
| DOL | DOL | ****2633 | RAW POWER ELECTRIC CORP. | | 3 PARK CIRCLE MIDDLETOWN NY 10940 | 07/11/2022 | 07/11/2027 |
| DOL | DA | ****7559 | REGAL CONTRACTING INC. | | 24 WOODBINE AVE NORTHPORT NY 11768 | 10/01/2020 | 10/01/2025 |
| DOL | DOL | ****9148 | RICH T CONSTRUCTION | | 107 WILLOW WOOD LANE CAMILLUS NY 13031 | 11/13/2018 | 11/13/2023 |
| DOL | DOL | | RICHARD MACONE | | 8617 THIRD AVE BROOKLYN NY 11209 | 09/17/2018 | 09/17/2023 |
| DOL | DOL | | RICHARD REGGIO | | 1617 MAIN ST PEEKSKILL NY 10566 | 03/03/2020 | 03/03/2025 |
| DOL | DOL | *****9148 | RICHARD TIMIAN | RICH T CONSTRUCTI ON | 108 LAMONT AVE SYRACUSE NY 13209 | 10/16/2018 | 10/16/2023 |
| DOL | DOL | | RICHARD TIMIAN JR. | | 108 LAMONT AVE SYRACUSE NY 13209 | 10/16/2018 | 10/16/2023 |
| DOL | DOL | | RICHARD TIMIAN JR. | | 108 LAMONT AVE SYRACUSE NY 13209 | 11/13/2018 | 11/13/2023 |
| DOL | DOL | | ROBBYE BISSESAR | | 89-51 SPRINGFIELD BLVD QUEENS VILLAGE NY 11427 | 01/11/2003 | 01/11/3003 |
| DOL | DOL | | ROBERT A. VALERINO | | 3841 LANYARD COURT NEW PORT RICHEY FL 34652 | 07/09/2019 | 07/09/2024 |
| DOL | DOL | | ROBERT BRUNO | | 5 MORNINGSIDE DRIVE AUBURN NY 13021 | 05/28/2019 | 05/28/2024 |
| DOL | DOL | | RODERICK PUGH | | 404 OAK ST SUITE 101SYRACUSE NY 13203 | 07/23/2018 | 07/23/2023 |
| DOL | DOL | ****4880 | RODERICK PUGH CONSTRUCTION INC. | | 404 OAK ST SUITE 101SYRACUSE NY 13203 | 07/23/2018 | 07/23/2023 |
| DOL | DOL | | ROMEO WARREN | | 161 ROBYN RD MONROE NY 10950 | 07/11/2022 | 07/11/2027 |
| DOL | DOL | | RONALD MESSEN | | 14B COMMERCIAL AVE ALBANY NY 12065 | 11/14/2019 | 11/14/2024 |
| DOL | DOL | | ROSEANNE CANTISANI | | | 06/12/2018 | 06/12/2023 |
| DOL | DOL | ****7172 | RZ & AL INC. | | 198 RIDGE AVENUE VALLEY STREAM NY 11581 | 06/06/2022 | 06/06/2027 |
| DOL | DOL | ****1365 | S & L PAINTING, INC. | | 11 MOUNTAIN ROAD P.O BOX 408MONROE NY 10950 | 03/20/2019 | 03/20/2024 |
| DOL | DOL | ****7730 | S C MARTIN GROUP INC. | | 2404 DELAWARE AVE NIAGARA FALLS NY 14305 | 09/12/2018 | 09/12/2023 |
| DOL | DOL | | SAL FRESINA MASONRY CONTRACTORS, INC. | | 1935 TEALL AVENUE SYRACUSE NY 13206 | 07/16/2021 | 07/16/2026 |
| DOL | DOL | | SAL MASONRY CONTRACTORS, INC. | | (SEE COMMENTS) SYRACUSE NY 13202 | 07/16/2021 | 07/16/2026 |
| DOL | DOL | ****9874 | SALFREE ENTERPRISES INC | | P.O BOX 14 2821 GARDNER RDPOMPEI NY 13138 | 07/16/2021 | 07/16/2026 |
| DOL | DOL | | SALVATORE A FRESINA A/K/A SAM FRESINA | | 107 FACTORY AVE P.O BOX 11070SYRACUSE NY 13218 | 07/16/2021 | 07/16/2026 |
| DOL | DOL | | SAM FRESINA | | 107 FACTORY AVE P.O BOX 11070SYRACUSE NY 13218 | 07/16/2021 | 07/16/2026 |
| DOL | NYC | ****0349 | SAM WATERPROOFING INC | | 168-42 88TH AVENUE APT.1 AJAMAICA NY 11432 | 11/20/2019 | 11/20/2024 |
| DOL | NYC | ****1130 | SCANA CONSTRUCTION CORP. | | 863 WASHINGTON STREET FRANKLIN SQUARE NY 11010 | 03/10/2020 | 03/10/2025 |
| DOL | DOL | ****2045 | SCOTT DUFFIE | DUFFIE'S ELECTRIC, INC. | P.O BOX 111 CORNWALL NY 12518 | 03/03/2020 | 03/03/2025 |
| DOL | DOL | | SCOTT DUFFIE | | P.O BOX 111 CORNWALL NY 12518 | 03/03/2020 | 03/03/2025 |
| DOL | NYC | ****6597 | SHAIRA CONSTRUCTION CORP. | | 421 HUDSON STREET SUITE C5NEW YORK NY 10014 | 02/20/2019 | 02/20/2024 |
| DOL | DOL | | SHANE NOLAN | | 9365 WASHINGTON ST LOCKPORT IL 60441 | 07/23/2018 | 07/23/2023 |

| DOL | DOL | | SHULEM LOWINGER | | 11 MOUNTAIN ROAD 28 VAN BUREN DRMONROE NY 10950 | 03/20/2019 | 03/20/2024 |
|-----|-----|-----------|--|--------------------------|--|------------|------------|
| DOL | DOL | *****0816 | SOLAR ARRAY SOLUTIONS, | | 9365 WASHINGTON ST LOCKPORT IL 60441 | 07/23/2018 | 07/23/2023 |
| DOL | DOL | ****0440 | SOLAR GUYS INC. | | 8970 MIKE GARCIA DR MANASSAS VA 20109 | 07/16/2021 | 07/16/2026 |
| DOL | NYC | | SOMATIE RAMSUNAHAI | | 115-46 132ND ST SOUTH OZONE PARK NY 11420 | 09/17/2020 | 09/17/2025 |
| DOL | DOL | *****2221 | SOUTH BUFFALO ELECTRIC, INC. | | 1250 BROADWAY ST BUFFALO NY 14212 | 02/03/2020 | 02/03/2025 |
| DOL | NYC | *****3661 | SPANIER BUILDING MAINTENANCE CORP | | 200 OAK DRIVE SYOSSET NY 11791 | 03/14/2022 | 03/14/2027 |
| DOL | DOL | | STANADOS KALOGELAS | | 485 RAFT AVENUE HOLBROOK NY 11741 | 10/19/2021 | 10/19/2026 |
| DOL | DOL | ****3496 | STAR INTERNATIONAL INC | | 89-51 SPRINGFIELD BLVD QUEENS VILLAGE NY 11427 | 08/11/2003 | 08/11/3003 |
| DOL | DOL | ****6844 | STEAM PLANT AND CHX SYSTEMS INC. | | 14B COMMERCIAL AVENUE ALBANY NY 12065 | 11/14/2019 | 11/14/2024 |
| DOL | DOL | ****9933 | STEED GENERAL CONTRACTORS, INC. | | 1445 COMMERCE AVE BRONX NY 10461 | 05/30/2019 | 05/30/2024 |
| DOL | DOL | ****9528 | STEEL-IT, LLC. | | 17613 SANTE FE LINE ROAD WAYNESFIELD OH 45896 | 07/16/2021 | 07/16/2026 |
| DOL | DOL | | STEFANOS PAPASTEFANOU, JR. A/K/A STEVE PAPASTEFANOU, JR. | | 256 WEST SADDLE RIVER RD UPPER SADDLE RIVER NJ 07458 | 05/30/2019 | 05/30/2024 |
| DOL | DOL | | STEVE TATE | | 415 FLAGER AVE #302STUART FL 34994 | 10/31/2018 | 10/31/2023 |
| DOL | DOL | | STEVEN MARTIN | | 2404 DELWARE AVE NIAGARA FALLS NY 14305 | 09/12/2018 | 09/12/2023 |
| DOL | DOL | *****3800 | SUBURBAN RESTORATION CO. INC. | | 5-10 BANTA PLACE FAIR LAWN PLACE NJ 07410 | 03/29/2021 | 03/29/2026 |
| DOL | DOL | *****1060 | SUNN ENTERPRISES GROUP, LLC | | 370 W. PLEASANTVIEW AVE SUITE 2.329HACKENSACK NJ 07601 | 02/11/2019 | 02/11/2024 |
| DOL | DOL | *****9150 | SURGE INC. | | 8269 21ST STREET BELLEROSE NY 11426 | 12/22/2022 | 12/22/2027 |
| DOL | DOL | | SYED RAZA | | 198 RIDGE AVENUE NY 11581 | 06/06/2022 | 06/06/2027 |
| DOL | DOL | *****8209 | SYRACUSE SCALES, INC. | | 158 SOLAR ST SYRACUSE NY 13204 | 01/07/2019 | 01/07/2024 |
| DOL | DOL | | TERRY THOMPSON | | 11371 RIDGE RD WOLCOTT NY 14590 | 02/03/2020 | 02/03/2025 |
| DOL | DOL | ****9733 | TERSAL CONSTRUCTION SERVICES INC | | 107 FACTORY AVE P.O BOX 11070SYRACUSE NY 13208 | 07/16/2021 | 07/16/2026 |
| DOL | DOL | | TERSAL CONTRACTORS, INC. | | 221 GARDNER RD P.O BOX 14POMPEI NY 13138 | 07/16/2021 | 07/16/2026 |
| DOL | DOL | | TERSAL DEVELOPMENT CORP. | | 1935 TEALL AVENUE SYRACUSE NY 13206 | 07/16/2021 | 07/16/2026 |
| DOL | DOL | | TEST | | P.O BOX 123 ALBANY NY 12204 | 05/20/2020 | 05/20/2025 |
| DOL | DOL | ****6789 | TEST1000 | | P.O BOX 123 ALBANY NY 12044 | 03/01/2021 | 03/01/2026 |
| DOL | DOL | ****5766 | THE COKER CORPORATION | COKER CORPORATIO N | 2610 SOUTH SALINA ST SUITE 14SYRACUSE NY 13205 | 12/04/2018 | 12/04/2023 |
| DOL | DOL | ****5766 | THE COKER CORPORATION | COKER CORPORATIO N | 2610 SOUTH SALINA ST SUITE 14SYRACUSE NY 13205 | 09/17/2020 | 09/17/2025 |
| DOL | DA | ****4106 | TRIPLE H CONCRETE CORP | | 2375 RAYNOR STREET RONKONKOMA NY 11779 | 08/04/2021 | 08/04/2026 |
| DOL | DOL | ****8210 | UPSTATE CONCRETE & MASONRY CONTRACTING CO INC | | 449 WEST MOMBSHA ROAD MONROE NY 10950 | 06/06/2022 | 06/06/2027 |
| DOL | DOL | ****6392 | V.M.K CORP. | | 8617 THIRD AVE BROOKLYN NY 11209 | 09/17/2018 | 09/17/2023 |
| DOL | DOL | ****6418 | VALHALLA CONSTRUCTION, LLC. | | 796 PHLEPS ROAD FRANKLIN LAKES NJ 07417 | 12/01/2020 | 12/01/2025 |
| DOL | NYC | ****2426 | VICKRAM MANGRU | VICK CONSTRUCTI ON | 21 DAREWOOD LANE VALLEY STREAM NY 11581 | 09/17/2020 | 09/17/2025 |
| DOL | NYC | | VICKRAM MANGRU | | 21 DAREWOOD LANE VALLEY STREAM NY 11581 | 09/17/2020 | 09/17/2025 |

| DOL | DOL | | VICTOR ALICANTI | | 42-32 235TH ST DOUGLASTON NY 11363 | 01/14/2019 | 01/14/2024 |
|-----|-----|----------|---------------------------------------|------------------------------|--|------------|------------|
| DOL | NYC | | VIKTAR PATONICH | | 2630 CROPSEY AVE BROOKLYN NY 11214 | 10/30/2018 | 10/30/2023 |
| DOL | DOL | | VIKTORIA RATH | | 24 ELDOR AVENUE NEW CITY NY 10956 | 02/03/2020 | 02/03/2025 |
| DOL | NYC | ****3673 | WALTERS AND WALTERS, INC. | | 465 EAST AND THIRD ST MT. VERNON NY 10550 | 09/09/2019 | 09/09/2024 |
| DOL | DOL | ****3296 | WESTERN NEW YORK CONTRACTORS, INC. | | 3841 LAYNARD COURT NEW PORT RICHEY FL 34652 | 07/09/2019 | 07/09/2024 |
| DOL | DOL | | WHITE PLAINS CARPENTRY CORP | | 442 ARMONK RD | 06/12/2018 | 06/12/2023 |
| DOL | DOL | | WILLIAM G. PROERFRIEDT | | 85 SPRUCEWOOD ROAD WEST BABYLON NY 11704 | 01/19/2021 | 01/19/2026 |
| DOL | DOL | ****5924 | WILLIAM G. PROPHY, LLC | WGP CONTRACTIN G, INC. | 54 PENTAQUIT AVE BAYSHORE NY 11706 | 01/19/2021 | 01/19/2026 |
| DOL | DOL | ****4730 | XGD SYSTEMS, LLC | TDI GOLF | 415 GLAGE AVE #302STUART FL 34994 | 10/31/2018 | 10/31/2023 |



SECTION 011000

SUMMARY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Project information.
- 2. Work covered by Contract Documents.
- 3. Phased construction.
- 4. Work under Owner's separate contracts.
- 5. Contractor's use of site and premises.
- 6. Coordination with occupants.
- 7. Work restrictions.

B. Related Requirements:

1. Section 015000 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.

1.3 PROJECT INFORMATION

- A. Project Identification: Rowland Street Highway Facility Cold Storage PEMB
 - 1. Project Location: Rowland Street, Milton NY
 - a. Latitude: 43.056301b. Longitude: -73.850701
- B. Owner: Town of Milton
 - 1. Owner's Representative: Scott Ostrander, Town Supervisor
- C. Architect/Engineer: Delaware Engineering, D.P.C
 - 1. Architect's/Engineer's Representative: Cody Messier, PE
 - a. Address: 28 Madison Ave Ext., Albany, NY 12203
 - b. Phone: 518-452-1290

D. Project Coordinator for Multiple Contracts: Delaware Engineering has been engaged by Owner to serve as Project coordinator.

1.4 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Work of Project is defined by the Contract Documents and includes, but is not limited to, the following:
 - 1. Design, fabrication, and delivery of a pre-engineered metal building for the construction of a new cold storage building and other Work indicated in the Contract Documents.
 - 2. Procurement, fabrication, and delivery of insulated metal wall panels and metal roof panels.
- B. Type of Contract:
 - 1. Project will be constructed under a single prime contract.

1.5 PHASED CONSTRUCTION

- A. Construction of the Work will be in phases, with each phase substantially complete as indicated below.
 - 1. Phase 1: Pre-engineered metal building design & fabrication
 - a. Commencement of Construction:
 - 1) Notice to Proceed: Work of this phase shall commence within 7 after the Notice to Proceed.
 - 2) Start Date: Work of this phase shall commence by June 29, 2023.
 - b. Substantial Completion (Delivery to Site):
 - 1) By December 26, 2023.
 - 2. Phase 2 (by others): Sitework & Foundation Preparation to Receive Pre-engineered metal building
 - a. Commencement of Construction:
 - 1) Notice to Proceed: Work of this phase shall commence within 7 after the Notice to Proceed.
 - 2) Start Date: Work of this phase shall commence by September 28, 2023.
 - b. Substantial Completion (Building foundation set to receive Pre-Engineered Metal Building):
 - 1) By December 26, 2023.
 - 3. Phase 3 (by others): Erection of Pre-engineered metal building
 - a. Commencement of Construction:

- 1) Start Date: Work of this phase shall commence by December 27, 2023.
- b. Substantial Completion:
 - 1) By January 26, 2023.

1.6 WORK UNDER OWNER'S SEPARATE CONTRACTS

- A. Work with Separate Contractors: Cooperate fully with Owner's separate contractors, so work on those contracts may be carried out smoothly, without interfering with or delaying Work under this Contract or other contracts. Coordinate the Work of this Contract with work performed under Owner's separate contracts.
- B. Concurrent Work: Owner will award separate contract(s) for the following construction operations at Project site. Those operations will be conducted simultaneously with Work under this Contract.
 - 1. Rowland Street Facility Site Development & Foundation Construction: General site work including but not limited to electrical service, sewer service, water service, grading, concrete foundations, concrete foundation walls, concrete slab-on-grade, erection of PEMB, installation of metal wall panels, installation of metal roof panels, and procurement and installation of doors, including overhead coiling doors.

1.7 CONTRACTOR'S USE OF SITE AND PREMISES

- A. Unrestricted Use of Site: Each Contractor shall have full use of Project site for construction operations during construction period. Contractor's use of Project site is limited only by Owner's right to perform work or to retain other contractors on portions of Project.
- B. Limits on Use of Site: Limit use of Project site to Work in areas indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.

1.8 COORDINATION WITH OCCUPANTS

- A. Full Owner Occupancy: Owner will occupy Project site and existing adjacent building(s) during entire construction period. Cooperate with Owner during construction operations to minimize conflicts and facilitate Owner usage. Perform the Work so as not to interfere with Owner's day-to-day operations. Maintain existing exits unless otherwise indicated.
 - 1. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from Owner and approval of authorities having jurisdiction.
 - 2. Notify Owner not less than 72 hours in advance of activities that will affect Owner's operations.

1.9 WORK RESTRICTIONS

- A. Comply with restrictions on construction operations.
 - 1. Comply with limitations on use of public streets, work on public streets, rights of way, and other requirements of authorities having jurisdiction.
- B. Smoking and Controlled Substance Restrictions: Use of tobacco products, alcoholic beverages, and other controlled substances on Owner's property is not permitted.
- C. Employee Identification: Provide identification tags for Contractor personnel working on Project site. Require personnel to use identification tags at all times.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011000

SECTION 012500

SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for substitutions.
- B. Related Requirements:
 - 1. Section 016000 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

1.3 DEFINITIONS

- A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents.
 - 1. Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of product, regulatory changes, or unavailability of required warranty terms.
 - 2. Substitutions for Convenience: Changes proposed by Contractor or Owner that are not required to meet other Project requirements but may offer advantage to Contractor or Owner.

1.4 ACTION SUBMITTALS

- A. Substitution Requests: Submit documentation identifying product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Substitution Request Form: Use form **acceptable to Architect**.
 - 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
 - a. Statement indicating why specified product or fabrication or installation method cannot be provided, if applicable.
 - b. Coordination of information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors that will be necessary to accommodate proposed substitution.

- c. Detailed comparison of significant qualities of proposed substitutions with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes, such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
- d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
- e. Samples, where applicable or requested.
- f. Certificates and qualification data, where applicable or requested.
- g. List of similar installations for completed projects, with project names and addresses as well as names and addresses of architects and owners.
- h. Material test reports from a qualified testing agency, indicating and interpreting test results for compliance with requirements indicated.
- i. Research reports evidencing compliance with building code in effect for Project, from ICC-ES.
- j. Detailed comparison of Contractor's construction schedule using proposed substitutions with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
- k. Cost information, including a proposal of change, if any, in the Contract Sum.
- 1. Contractor's certification that proposed substitution complies with requirements in the Contract Documents, except as indicated in substitution request, is compatible with related materials and is appropriate for applications indicated.
- m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
- 3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within 7 days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or 7days of receipt of additional information or documentation, whichever is later.
 - a. Forms of Acceptance: Change Order, Construction Change Directive, or Architect's Supplemental Instructions for minor changes in the Work.
 - b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

1.5 QUALITY ASSURANCE

A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

1.6 PROCEDURES

A. Coordination: Revise or adjust affected work as necessary to integrate work of the approved substitutions.

1.7 SUBSTITUTIONS

- A. Substitutions for Cause: Submit requests for substitution immediately on discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.
 - 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:
 - a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - b. Substitution request is fully documented and properly submitted.
 - c. Requested substitution will not adversely affect Contractor's construction schedule.
 - d. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - e. Requested substitution is compatible with other portions of the Work.
 - f. Requested substitution has been coordinated with other portions of the Work.
 - g. Requested substitution provides specified warranty.
 - h. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
 - i. The requested substitution offers the Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities the Owner must assume. The Owner's additional responsibilities may include compensation to Engineer for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
- B. Substitutions for Convenience: Not allowed.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012500

SECTION 012600

CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

B. Related Requirements:

- 1. Section 012500 "Substitution Procedures" for administrative procedures for handling requests for substitutions made after the Contract award.
- 2. Section 013100 "Project Management and Coordination" for requirements for forms for contract modifications provided as part of web-based Project management software.

1.3 MINOR CHANGES IN THE WORK

A. Architect will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710.

1.4 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 - 1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
 - 2. Within 15 days after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts
 - c. Include costs of labor and supervision directly attributable to the change.

- d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
- e. Quotation Form: Use forms acceptable to Architect.
- B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.
 - 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
 - 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - 4. Include costs of labor and supervision directly attributable to the change.
 - 5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
 - 6. Comply with requirements in Section 012500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
 - 7. Proposal Request Form: Use form acceptable to Architect.

1.5 CHANGE ORDER PROCEDURES

A. On Owner's approval of a Work Change Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on AIA Document G701.

1.6 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: Architect may issue a Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
 - 1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
 - 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012600

SECTION 012900

PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.

B. Related Requirements:

- 1. Section 012600 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
- 2. Section 013200 "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

1.3 DEFINITIONS

A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.4 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.
 - 1. Coordinate line items in the schedule of values with items required to be indicated as separate activities in Contractor's construction schedule.
 - 2. Submit the schedule of values to Architect at earliest possible date, but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
- B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.
 - 1. Identification: Include the following Project identification on the schedule of values:
 - a. Project name and location.
 - b. Owner's name.
 - c. Owner's Project number.

- d. Name of Architect.
- e. Architect's Project number.
- f. Contractor's name and address.
- g. Date of submittal.
- 2. Arrange schedule of values consistent with format of AIA Document G703.
- 3. Arrange the schedule of values in tabular form, with separate columns to indicate the following for each item listed:
 - a. Related Specification Section or division.
 - b. Description of the Work.
 - c. Name of subcontractor.
 - d. Name of manufacturer or fabricator.
 - e. Name of supplier.
 - f. Change Orders (numbers) that affect value.
 - g. Dollar value of the following, as a percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent. Round dollar amounts to whole dollars, with total equal to Contract Sum.
 - 1) Labor.
 - 2) Materials.
 - 3) Equipment.
- 4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
- 5. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
 - a. Differentiate between items stored on-site and items stored off-site.
- 6. Overhead Costs, Proportional Distribution: Include total cost and proportionate share of general overhead and profit for each line item.
- 7. Closeout Costs. Include separate line items under Contractor and principal subcontracts for Project closeout requirements in an amount totaling five percent of the Contract Sum and subcontract amount.
- 8. Schedule of Values Revisions: Revise the schedule of values when Change Orders or Construction Change Directives result in a change in the Contract Sum. Include at least one separate line item for each Change Order and Construction Change Directive.

1.5 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment following the initial Application for Payment shall be consistent with previous applications and payments, as certified by Architect and paid for by Owner.
- B. Payment Application Times: The date for each progress payment is indicated in the Owner/Contractor Agreement. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.

- C. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.
 - 1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
 - 2. Include amounts for work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.
 - 3. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
 - 4. Indicate separate amounts for work being carried out under Owner-requested project acceleration.
- E. Stored Materials: Include in Application for Payment amounts applied for materials or equipment purchased or fabricated and stored, but not yet installed. Differentiate between items stored on-site and items stored off-site.
 - 1. Provide certificate of insurance, evidence of transfer of title to Owner, and consent of surety to payment for stored materials.
 - 2. Provide supporting documentation that verifies amount requested, such as paid invoices. Match amount requested with amounts indicated on documentation; do not include overhead and profit on stored materials.
 - 3. Provide summary documentation for stored materials indicating the following:
 - a. Value of materials previously stored and remaining stored as of date of previous Applications for Payment.
 - b. Value of previously stored materials put in place after date of previous Application for Payment and on or before date of current Application for Payment.
 - c. Value of materials stored since date of previous Application for Payment and remaining stored as of date of current Application for Payment.
- F. Transmittal: Submit three signed and notarized original copies of each Application for Payment to Architect] by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
 - 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- G. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from entities lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.
 - 1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
 - 2. When an application shows completion of an item, submit conditional final or full waivers.

- 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
- 4. Submit final Application for Payment with or preceded by conditional final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
- 5. Waiver Forms: Submit executed waivers of lien on forms acceptable to Owner.
- H. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
 - 1. List of subcontractors.
 - 2. Schedule of values.
 - 3. Contractor's construction schedule (preliminary if not final).
 - 4. Products list (preliminary if not final).
 - 5. Sustainable design action plans, including preliminary project materials cost data.
 - 6. Schedule of unit prices.
 - 7. Submittal schedule (preliminary if not final).
 - 8. List of Contractor's staff assignments.
 - 9. List of Contractor's principal consultants.
 - 10. Copies of building permits.
 - 11. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 - 12. Initial progress report.
 - 13. Report of preconstruction conference.
- I. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
 - 1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 - a. Complete administrative actions, submittals, and Work preceding this application, as described in Section 017700 "Closeout Procedures."
 - 2. This application shall reflect Certificate(s) of Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
- J. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
 - 1. Evidence of completion of Project closeout requirements.
 - 2. Certification of completion of final punch list items.
 - 3. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 - 4. Updated final statement, accounting for final changes to the Contract Sum.
 - 5. AIA Document G706.
 - 6. AIA Document G706A.
 - 7. AIA Document G707.
 - 8. Evidence that claims have been settled.

- 9. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
- 10. Final liquidated damages settlement statement.
- 11. Proof that taxes, fees, and similar obligations are paid.
- 12. Waivers and releases.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012900

PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative provisions for coordinating construction operations on Project, including, but not limited to, the following:
 - 1. General coordination procedures.
 - 2. Coordination drawings.
 - 3. RFIs.
 - 4. Digital project management procedures.
 - 5. Project meetings.

B. Related Requirements:

- 1. Section 013200 "Construction Progress Documentation" for preparing and submitting Contractor's construction schedule.
- 2. Section 017300 "Execution" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.
- 3. Section 017700 "Closeout Procedures" for coordinating closeout of the Contract.

1.3 DEFINITIONS

A. RFI: Request for Information. Request from Owner, Architect, or Contractor seeking information required by or clarifications of the Contract Documents.

1.4 INFORMATIONAL SUBMITTALS

- A. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:
 - 1. Name, address, telephone number, and email address of entity performing subcontract or supplying products.
 - 2. Number and title of related Specification Section(s) covered by subcontract.
 - 3. Drawing number and detail references, as appropriate, covered by subcontract.

B. Key Personnel Names: Within 15 days of starting construction operations, submit a list of key personnel assignments, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses, cellular telephone numbers, and e-mail addresses. Provide names, addresses, and telephone numbers of individuals assigned as alternates in the absence of individuals assigned to Project.

1.5 GENERAL COORDINATION PROCEDURES

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations included in different Sections that depend on each other for proper installation, connection, and operation.
 - 1. Schedule construction operations in sequence required to obtain the best results, where installation of one part of the Work depends on installation of other components, before or after its own installation.
 - 2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
 - 3. Make adequate provisions to accommodate items scheduled for later installation.
- B. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
 - 1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.
- C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities and direction of Project coordinator to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
 - 1. Preparation of Contractor's construction schedule.
 - 2. Preparation of the schedule of values.
 - 3. Installation and removal of temporary facilities and controls.
 - 4. Delivery and processing of submittals.
 - 5. Progress meetings.
 - 6. Preinstallation conferences.
 - 7. Project closeout activities.
 - 8. Startup and adjustment of systems.

1.6 REQUEST FOR INFORMATION (RFI)

- A. General: Immediately on discovery of the need for additional information, clarification, or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.
 - 1. Architect will return without response those RFIs submitted to Architect by other entities controlled by Contractor.

- 2. Coordinate and submit RFIs in a prompt manner to avoid delays in Contractor's work or work of subcontractors.
- B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:
 - 1. Project name.
 - 2. Owner name.
 - 3. Owner's Project number.
 - 4. Name of Architect.
 - 5. Architect's Project number.
 - 6. Date.
 - 7. Name of Contractor.
 - 8. RFI number, numbered sequentially.
 - 9. RFI subject.
 - 10. Specification Section number and title and related paragraphs, as appropriate.
 - 11. Drawing number and detail references, as appropriate.
 - 12. Field dimensions and conditions, as appropriate.
 - 13. Contractor's suggested resolution. If Contractor's suggested resolution impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
 - 14. Contractor's signature.
 - 15. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.
 - a. Include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments on attached sketches.
- C. RFI Forms: AIA Document G716.
 - 1. Attachments shall be electronic files in PDF format.
- D. Architect's Action: Architect will review each RFI, determine action required, and respond. Allow five days for Architect's response for each RFI. RFIs received by Architect 1:00 p.m. will be considered as received the following working day.
 - 1. The following Contractor-generated RFIs will be returned without action:
 - a. Requests for approval of submittals.
 - b. Requests for approval of substitutions.
 - c. Requests for approval of Contractor's means and methods.
 - d. Requests for coordination information already indicated in the Contract Documents.
 - e. Requests for adjustments in the Contract Time or the Contract Sum.
 - f. Requests for interpretation of Architect's actions on submittals.
 - g. Incomplete RFIs or inaccurately prepared RFIs.
 - 2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt by Architect of additional information.

- 3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Section 012600 "Contract Modification Procedures."
 - a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 5 days of receipt of the RFI response.
- E. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log weekly and include the following:
 - 1. Project name.
 - 2. Name and address of Contractor.
 - 3. Name and address of Architect
 - 4. RFI number, including RFIs that were returned without action or withdrawn.
 - 5. RFI description.
 - 6. Date the RFI was submitted.
 - 7. Date Architect's response was received.
 - 8. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
- F. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within three days if Contractor disagrees with response.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013100

CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
 - 1. Contractor's Construction Schedule.
 - 2. Material location reports.
- B. Related Requirements:
 - 1. Section 012900 "Payment Procedures" for schedule of values and requirements for use of cost-loaded schedule for Applications for Payment.
 - 2. Section 014000 "Quality Requirements" for schedule of tests and inspections.

1.2 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction Project. Activities included in a construction schedule consume time and resources.
 - 1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
 - 2. Predecessor Activity: An activity that precedes another activity in the network.
 - 3. Successor Activity: An activity that follows another activity in the network.
- B. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.
- C. Event: The starting or ending point of an activity.

1.3 INFORMATIONAL SUBMITTALS

- A. Format for Submittals: Submit required submittals in the following format:
 - 1. Working electronic copy of schedule file.
 - 2. PDF file.
- B. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.

1.4 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. Computer Scheduling Software: Prepare schedules using current version of a program that has been developed specifically to manage construction schedules.
- B. Time Frame: Extend schedule from date established for the Notice of Award to date of Substantial Completion.
 - 1. Contract completion date to not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- C. Activities: Treat each floor or separate area as a separate numbered activity for each main element of the Work. Comply with the following:
 - 1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
 - 2. Procurement Activities: Include procurement process activities for the following long lead-time items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
 - 3. Submittal Review Time: Include review and resubmittal times indicated in Section 013300 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's Construction Schedule with submittal schedule.
 - 4. Startup and Testing Time: Include no fewer than 15 days for startup and testing.
 - 5. Commissioning Time: Include no fewer than 15 days for commissioning.
 - 6. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
 - 7. Punch List and Final Completion: Include not more than 7 days for completion of punch list items and Final Completion.
- D. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.
 - 1. Work by Owner: Include a separate activity for each portion of the Work performed by Owner.
 - 2. Products Ordered in Advance: Include a separate activity for each product. Include delivery date indicated in Section 011000 "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
 - 3. Owner-Furnished Products: Include a separate activity for each product. Include delivery date indicated in Section 011000 "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
 - 4. Work Stages: Indicate important stages of construction for each major portion of the Work, including, but not limited to, the following:
 - a. Subcontract awards.
 - b. Submittals.
 - c. Purchases.
 - d. Fabrication.

- e. Deliveries.
- f. Installation.
- g. Tests and inspections.
- h. Adjusting.
- i. Startup and placement into final use and operation.
- i. Commissioning.
- E. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and Final Completion.
- F. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:
 - 1. Unresolved issues.
 - 2. Unanswered Requests for Information.
 - 3. Rejected or unreturned submittals.
 - 4. Notations on returned submittals.
 - 5. Pending modifications affecting the Work and the Contract Time.
- G. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities.
 - 1. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
 - 2. As the Work progresses, indicate Final Completion percentage for each activity.
- H. Distribution: Distribute copies of approved schedule to Architect, Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
 - 1. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

1.5 GANTT-CHART SCHEDULE REQUIREMENTS

- A. Gantt-Chart Schedule: Submit a comprehensive, fully developed, horizontal, Gantt-chart-type, Contractor's Construction Schedule within 30 days of date established for Notice of Award.
- B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line.
 - 1. For construction activities that require three months or longer to complete, indicate an estimated completion percentage in 10 percent increments within time bar.

1.6 REPORTS

A. Material Location Reports: At monthly intervals, prepare and submit a comprehensive list of materials delivered to and stored at Project site. List to be cumulative, showing materials previously reported plus items recently delivered. Include with list a statement of progress on

and delivery dates for materials or items of equipment fabricated or stored away from Project site. Indicate the following categories for stored materials:

- 1. Material stored prior to previous report and remaining in storage.
- 2. Material stored prior to previous report and since removed from storage and installed.
- 3. Material stored following previous report and remaining in storage.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013200

SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

- 1. Submittal schedule requirements.
- 2. Administrative and procedural requirements for submittals.

B. Related Requirements:

- 1. Section 012900 "Payment Procedures" for submitting Applications for Payment and the schedule of values.
- 2. Section 013100 "Project Management and Coordination" for submitting coordination drawings and subcontract list and for requirements for web-based Project software.
- 3. Section 013200 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
- 4. Section 014000 "Quality Requirements" for submitting test and inspection reports, and schedule of tests and inspections.
- 5. Section 017700 "Closeout Procedures" for submitting closeout submittals and maintenance material submittals.
- 6. Section 017823 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
- 7. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

1.2 DEFINITIONS

- A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action. Action submittals are those submittals indicated in individual Specification Sections as "action submittals."
- B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements. Informational submittals are those submittals indicated in individual Specification Sections as "informational submittals."

1.3 SUBMITTAL SCHEDULE

A. Submittal Schedule: Submit, as an action submittal, a list of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include

additional time required for making corrections or revisions to submittals noted by Architect and additional time for handling and reviewing submittals required by those corrections.

- 1. Coordinate submittal schedule with list of subcontracts, the schedule of values, and Contractor's construction schedule.
- 2. Final Submittal Schedule: Submit concurrently with the first complete submittal of Contractor's construction schedule.
 - a. Submit revised submittal schedule as required to reflect changes in current status and timing for submittals.
- 3. Format: Arrange the following information in a tabular format:
 - a. Scheduled date for first submittal.
 - b. Specification Section number and title.
 - c. Submittal Category: Action; informational.
 - d. Name of subcontractor.
 - e. Description of the Work covered.
 - f. Scheduled date for Architect's final release or approval.

1.4 SUBMITTAL FORMATS

- A. Submittal Information: Include the following information in each submittal:
 - 1. Project name.
 - 2. Date.
 - 3. Name of Architect.
 - 4. Name of Contractor.
 - 5. Name of firm or entity that prepared submittal.
 - 6. Names of subcontractor, manufacturer, and supplier.
 - 7. Unique submittal number, including revision identifier. Include Specification Section number with sequential alphanumeric identifier and alphanumeric suffix for resubmittals.
 - 8. Category and type of submittal.
 - 9. Submittal purpose and description.
 - 10. Number and title of Specification Section, with paragraph number and generic name for each of multiple items.
 - 11. Drawing number and detail references, as appropriate.
 - 12. Indication of full or partial submittal.
 - 13. Location(s) where product is to be installed, as appropriate.
 - 14. Other necessary identification.
 - 15. Remarks.
 - 16. Signature of transmitter.
- B. Options: Identify options requiring selection by Architect.
- C. Deviations and Additional Information: On each submittal, clearly indicate deviations from requirements in the Contract Documents, including minor variations and limitations; include relevant additional information and revisions, other than those requested by Architect on previous submittals. Indicate by highlighting on each submittal or noting on attached separate sheet.

D. Electronic Submittals: Prepare submittals as PDF package, incorporating complete information into each PDF file. Name PDF file with submittal number.

1.5 SUBMITTAL PROCEDURES

- A. Prepare and submit submittals required by individual Specification Sections. Types of submittals are indicated in individual Specification Sections.
 - 1. Email: Prepare submittals as PDF package and transmit to Architect by sending via email. Include PDF transmittal form. Include information in email subject line as requested by Architect.
 - a. Architect will return annotated file. Annotate and retain one copy of file as a digital Project Record Document file.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
 - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 - 2. Submit all submittal items required for each Specification Section concurrently unless partial submittals for portions of the Work are indicated on approved submittal schedule.
 - 3. Submit action submittals and informational submittals required by the same Specification Section as separate packages under separate transmittals.
 - 4. Coordinate transmittal of submittals for related parts of the Work specified in different Sections, so processing will not be delayed because of need to review submittals concurrently for coordination.
 - a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
 - 1. Initial Review: Allow 15 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
 - 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
 - 3. Resubmittal Review: Allow 15 days for review of each resubmittal.

a.

- D. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
 - 1. Note date and content of previous submittal.
 - 2. Note date and content of revision in label or title block, and clearly indicate extent of revision.

- 3. Resubmit submittals until they are marked with approval notation from Architect's action stamp.
- E. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- F. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's action stamp.

1.6 SUBMITTAL REQUIREMENTS

- A. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
 - 1. If information must be specially prepared for submittal because standard published data are unsuitable for use, submit as Shop Drawings, not as Product Data.
 - 2. Mark each copy of each submittal to show which products and options are applicable.
 - 3. Include the following information, as applicable:
 - a. Manufacturer's catalog cuts.
 - b. Manufacturer's product specifications.
 - c. Standard color charts.
 - d. Statement of compliance with specified referenced standards.
 - e. Testing by recognized testing agency.
 - f. Application of testing agency labels and seals.
 - g. Notation of coordination requirements.
 - h. Availability and delivery time information.
 - 4. For equipment, include the following in addition to the above, as applicable:
 - a. Wiring diagrams that show factory-installed wiring.
 - b. Printed performance curves.
 - c. Operational range diagrams.
 - d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.
 - 5. Submit Product Data before Shop Drawings, and before or concurrently with Samples.
- B. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data.
 - 1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
 - a. Identification of products.
 - b. Schedules.
 - c. Compliance with specified standards.
 - d. Notation of coordination requirements.
 - e. Notation of dimensions established by field measurement.

- f. Relationship and attachment to adjoining construction clearly indicated.
- g. Seal and signature of professional engineer if specified.
- C. Samples: Submit Samples for review of type, color, pattern, and texture for a check of these characteristics with other materials.
 - 1. Transmit Samples that contain multiple, related components, such as accessories together in one submittal package.
 - 2. Identification: Permanently attach label on unexposed side of Samples that includes the following:
 - a. Project name and submittal number.
 - b. Generic description of Sample.
 - c. Product name and name of manufacturer.
 - d. Sample source.
 - e. Number and title of applicable Specification Section.
 - f. Specification paragraph number and generic name of each item.
 - 3. Email Transmittal: Provide PDF transmittal. Include digital image file illustrating Sample characteristics and identification information for record.
- D. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
 - 1. Type of product. Include unique identifier for each product indicated in the Contract Documents or assigned by Contractor if none is indicated.
 - 2. Manufacturer and product name, and model number if applicable.
 - 3. Number and name of room or space.
 - 4. Location within room or space.
- E. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.
- F. Design Data: Prepare and submit written and graphic information indicating compliance with indicated performance and design criteria in individual Specification Sections. Include list of assumptions and summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Number each page of submittal.
- G. Certificates:
 - 1. Certificates and Certifications Submittals: Submit a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity. Provide a notarized signature where indicated.
 - 2. Installer Certificates: Submit written statements on manufacturer's letterhead, certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.

- 3. Manufacturer Certificates: Submit written statements on manufacturer's letterhead, certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.
- 4. Material Certificates: Submit written statements on manufacturer's letterhead, certifying that material complies with requirements in the Contract Documents.
- 5. Product Certificates: Submit written statements on manufacturer's letterhead, certifying that product complies with requirements in the Contract Documents.
- 6. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of AWS B2.1/B2.1M on AWS forms. Include names of firms and personnel certified.

H. Test and Research Reports:

- 1. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for substrate preparation and primers required.
- 2. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
- 3. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
- 4. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
- 5. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- 6. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:
 - a. Name of evaluation organization.
 - b. Date of evaluation.
 - c. Time period when report is in effect.
 - d. Product and manufacturers' names.
 - e. Description of product.
 - f. Test procedures and results.
 - g. Limitations of use.

1.7 DELEGATED DESIGN SERVICES

A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.

- 1. If criteria indicated are insufficient to perform services or certification required, submit a written request for additional information to Architect.
- B. Delegated Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF file, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.
 - 1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.

1.8 ARCHITECT'S REVIEW

- A. Action Submittals: Architect will review each submittal, indicate corrections or revisions required, and return.
 - 1. PDF Submittals: Architect will indicate, via markup on each submittal, the appropriate action.
- B. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- C. Partial submittals prepared for a portion of the Work will be reviewed when use of partial submittals has received prior approval from Architect.
- D. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.
- E. Architect will return without review submittals received from sources other than Contractor.
- F. Submittals not required by the Contract Documents will be returned by Architect without action.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013300

QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspection services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
 - 1. Specific quality-assurance and quality-control requirements for individual work results are specified in their respective Specification Sections. Requirements in individual Sections may also cover production of standard products.
 - 2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and quality-control procedures that facilitate compliance with the Contract Document requirements.
 - 3. Requirements for Contractor to provide quality-assurance and quality-control services required by Architect, Owner, Commissioning Authority, or authorities having jurisdiction are not limited by provisions of this Section.

1.2 DEFINITIONS

- A. Experienced: When used with an entity or individual, "experienced," unless otherwise further described, means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.
- B. Field Quality-Control Tests and Inspections: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- C. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, subcontractor, or sub-subcontractor, to perform a particular construction operation, including installation, erection, application, assembly, and similar operations.
 - 1. Use of trade-specific terminology in referring to a Work result does not require that certain construction activities specified apply exclusively to specific trade(s).
- D. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria. Unless otherwise indicated, copies of reports of tests or inspections performed for other than the Project do not meet this definition.

- E. Product Tests: Tests and inspections that are performed by a nationally recognized testing laboratory (NRTL) in accordance with 29 CFR 1910.7, by a testing agency accredited in accordance with NIST's National Voluntary Laboratory Accreditation Program (NVLAP), or by a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.
- F. Source Quality-Control Tests and Inspections: Tests and inspections that are performed at the source (e.g., plant, mill, factory, or shop).
- G. Testing Agency: An entity engaged to perform specific tests, inspections, or both. The term "testing laboratory" has the same meaning as the term "testing agency."
- H. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work, to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- I. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work, to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Contractor's quality-control services do not include contract administration activities performed by Architect or Construction Manager.

1.3 DELEGATED DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
 - 1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.
- B. Delegated Design Services Statement: Submit a statement signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional, indicating that the products and systems are in compliance with performance and design criteria indicated. Include list of codes, loads, and other factors used in performing these services.

1.4 CONFLICTING REQUIREMENTS

- A. Conflicting Standards and Other Requirements: If compliance with two or more standards or requirements is specified and the standards or requirements establish different or conflicting requirements for minimum quantities or quality levels, inform the Architect regarding the conflict and obtain clarification prior to proceeding with the Work. Refer conflicting requirements that are different, but apparently equal, to Architect for clarification before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified is the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as

appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.5 INFORMATIONAL SUBMITTALS

- A. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.
- B. Qualification Data: For Contractor's quality-control personnel.
- C. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.
- D. Schedule of Tests and Inspections: Prepare in tabular form and include the following:
 - 1. Specification Section number and title.
 - 2. Entity responsible for performing tests and inspections.
 - 3. Description of test and inspection.
 - 4. Identification of applicable standards.
 - 5. Identification of test and inspection methods.
 - 6. Number of tests and inspections required.
 - 7. Time schedule or time span for tests and inspections.
 - 8. Requirements for obtaining samples.
 - 9. Unique characteristics of each quality-control service.
- E. Reports: Prepare and submit certified written reports and documents as specified.
- F. Permits, Licenses, and Certificates: For Owner's record, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents established for compliance with standards and regulations bearing on performance of the Work.

1.6 CONTRACTOR'S QUALITY-CONTROL PLAN

- A. Quality-Control Plan, General: Submit quality-control plan within 10 days of Notice to Proceed. Submit in format acceptable to Architect. Identify personnel, procedures, controls, instructions, tests, records, and forms to be used to carry out Contractor's quality-assurance and quality-control responsibilities and to coordinate Owner's quality-assurance and quality-control activities. Coordinate with Contractor's Construction Schedule.
- B. Quality-Control Personnel Qualifications: Engage qualified personnel trained and experienced in managing and executing quality-assurance and quality-control procedures similar in nature and extent to those required for Project.
- C. Submittal Procedure: Describe procedures for ensuring compliance with requirements through review and management of submittal process. Indicate qualifications of personnel responsible for submittal review.

- D. Testing and Inspection: In quality-control plan, include a comprehensive schedule of Work requiring testing or inspection, including the following:
 - 1. Contractor-performed tests and inspections, including subcontractor-performed tests and inspections. Include required tests and inspections and Contractor-elected tests and inspections. Distinguish source quality-control tests and inspections from field quality-control tests and inspections.
 - 2. Special inspections required by authorities having jurisdiction and indicated on the Statement of Special Inspections.
 - 3. Owner-performed tests and inspections indicated in the Contract Documents, including tests and inspections indicated to be performed by Commissioning Authority.
- E. Continuous Inspection of Workmanship: Describe process for continuous inspection during construction to identify and correct deficiencies in workmanship in addition to testing and inspection specified. Indicate types of corrective actions to be required to bring the Work into compliance with standards of workmanship established by Contract requirements and approved mockups.
- F. Monitoring and Documentation: Maintain testing and inspection reports, including log of approved and rejected results. Include Work Architect has indicated as nonconforming or defective. Indicate corrective actions taken to bring nonconforming Work into compliance with requirements. Comply with requirements of authorities having jurisdiction.

1.7 REPORTS AND DOCUMENTS

- A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:
 - 1. Date of issue.
 - 2. Project title and number.
 - 3. Name, address, telephone number, and email address of testing agency.
 - 4. Dates and locations of samples and tests or inspections.
 - 5. Names of individuals making tests and inspections.
 - 6. Description of the Work and test and inspection method.
 - 7. Identification of product and Specification Section.
 - 8. Complete test or inspection data.
 - 9. Test and inspection results and an interpretation of test results.
 - 10. Record of temperature and weather conditions at time of sample-taking and testing and inspection.
 - 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
 - 12. Name and signature of laboratory inspector.
 - 13. Recommendations on retesting and reinspecting.
- B. Manufacturer's Technical Representative's Field Reports: Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:
 - 1. Name, address, telephone number, and email address of technical representative making report.

- 2. Statement on condition of substrates and their acceptability for installation of product.
- 3. Statement that products at Project site comply with requirements.
- 4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
- 5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
- 6. Statement of whether conditions, products, and installation will affect warranty.
- 7. Other required items indicated in individual Specification Sections.
- C. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:
 - 1. Name, address, telephone number, and email address of factory-authorized service representative making report.
 - 2. Statement that equipment complies with requirements.
 - 3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 - 4. Statement of whether conditions, products, and installation will affect warranty.
 - 5. Other required items indicated in individual Specification Sections.

1.8 QUALITY ASSURANCE

- A. Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.
- B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units. As applicable, procure products from manufacturers able to meet qualification requirements, warranty requirements, and technical or factory-authorized service representative requirements.
- C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- D. Installer Qualifications: A firm or individual experienced in installing, erecting, applying, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.
- E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that is similar in material, design, and extent to those indicated for this Project.
- F. Specialists: Certain Specification Sections require that specific construction activities be performed by entities who are recognized experts in those operations. Specialists will satisfy qualification requirements indicated and engage in the activities indicated.

- 1. Requirements of authorities having jurisdiction supersede requirements for specialists.
- G. Testing and Inspecting Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspection indicated, as documented in accordance with ASTM E329, and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.
- H. Manufacturer's Technical Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- I. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect, demonstrate, repair, and perform service on installations of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- J. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following:
 - 1. Contractor's Responsibilities:
 - a. Provide test specimens representative of proposed products and construction.
 - b. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
 - c. Provide sizes and configurations of test assemblies, mockups, and laboratory mockups to adequately demonstrate capability of products to comply with performance requirements.
 - d. Build site-assembled test assemblies and mockups, using installers who will perform same tasks for Project.
 - 2. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Architect and Commissioning Authority, with copy to Contractor. Interpret tests and inspections, and state in each report whether tested and inspected Work complies with or deviates from the Contract Documents.

1.9 QUALITY CONTROL

- A. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities, whether specified or not, to verify and document that the Work complies with requirements.
 - 1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.
 - 2. Engage a qualified testing agency to perform quality-control services.

- 3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspection will be performed.
- 4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
- 5. Testing and inspection requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
- 6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- B. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.
- C. Testing Agency Responsibilities: Cooperate with Architect, Commissioning Authority and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
 - 1. Notify Architect, Commissioning Authority, and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
 - 2. Determine the locations from which test samples will be taken and in which in-situ tests are conducted.
 - 3. Conduct and interpret tests and inspections, and state in each report whether tested and inspected Work complies with or deviates from requirements.
 - 4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
 - 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
 - 6. Do not perform duties of Contractor.
- D. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Section 013300 "Submittal Procedures."
- E. Manufacturer's Technical Services: Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in preinstallation conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.
- F. Contractor's Associated Requirements and Services: Cooperate with agencies and representatives performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
 - 1. Access to the Work.
 - 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 - 3. Adequate quantities of representative samples of materials that require testing and inspection. Assist agency in obtaining samples.
 - 4. Facilities for storage and field curing of test samples.

- 5. Security and protection for samples and for testing and inspection equipment at Project site.
- G. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and quality-control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspection.
 - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.
- H. Schedule of Tests and Inspections: Prepare a schedule of tests, inspections, and similar quality-control services required by the Contract Documents as a component of Contractor's quality-control plan. Coordinate and submit concurrently with Contractor's Construction Schedule. Update and submit with each Application for Payment.
 - 1. Schedule Contents: Include tests, inspections, and quality-control services, including Contractor- and Owner-retained services, commissioning activities, and other Project-required services paid for by other entities.
 - 2. Distribution: Distribute schedule to Owner, Architect, Commissioning Authority, testing agencies, and each party involved in performance of portions of the Work where tests and inspections are required.

1.10 SPECIAL TESTS AND INSPECTIONS

- A. Special Tests and Inspections: Contractor will engage a qualified testing agency to conduct special tests and inspections required by authorities having, and as follows:
 - 1. Verifying that manufacturer maintains detailed fabrication and quality-control procedures, and reviewing the completeness and adequacy of those procedures to perform the Work.
 - 2. Notifying Architect, Commissioning Authority, and Contractor promptly of irregularities and deficiencies observed in the Work during performance of its services.
 - 3. Submitting a certified written report of each test, inspection, and similar quality-control service to Architect and Commissioning Authorit with copy to Contractor and to authorities having jurisdiction.
 - 4. Submitting a final report of special tests and inspections at Substantial Completion, which includes a list of unresolved deficiencies.
 - 5. Interpreting tests and inspections, and stating in each report whether tested and inspected Work complies with or deviates from the Contract Documents.
 - 6. Retesting and reinspecting corrected Work.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:

- 1. Date test or inspection was conducted.
- 2. Description of the Work tested or inspected.
- 3. Date test or inspection results were transmitted to Architect.
- 4. Identification of testing agency or special inspector conducting test or inspection.
- B. Provide access to test and inspection log for Architect's, Commissioning Authority, and authorities' having jurisdiction reference during normal working hours.
 - 1. Submit log at Project closeout as part of Project Record Documents.

3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspection, sample-taking, and similar services, repair damaged construction and restore substrates and finishes.
 - 1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 017300 "Execution."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 014000

PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. The Work of This Section Includes: Administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.

B. Related Requirements:

- 1. Section 011000 "Summary" for Contractor requirements related to Owner-furnished products.
- 2. Section 012500 "Substitution Procedures" for requests for substitutions.
- 3. Section 017700 "Closeout Procedures" for submitting warranties.

1.2 DEFINITIONS

- A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
 - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature that is current as of date of the Contract Documents.
 - 2. New Products: Items that have not previously been incorporated into another project or facility. Salvaged items or items reused from other projects are not considered new products. Items that are manufactured or fabricated to include recycled content materials are considered new products unless otherwise indicated.
 - 3. Comparable Product: Product by named manufacturer that is demonstrated and approved through the comparable product submittal process described in "Comparable Products" Article, to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Basis-of-Design Product Specification: A specification in which a single manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation. Published attributes and characteristics of basis-of-design product establish salient characteristics of products.
 - 1. Evaluating Comparable Products: In addition to the basis-of-design product description, product attributes and characteristics may be listed to establish the significant qualities related to type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other special features and requirements

for purposes of evaluating comparable products of additional manufacturers named in the specification. Manufacturer's published attributes and characteristics of basis-of-design product also establish salient characteristics of products for purposes of evaluating comparable products.

- C. Subject to Compliance with Requirements: Where the phrase "Subject to compliance with requirements" introduces a product selection procedure in an individual Specification Section, provide products qualified under the specified product procedure. In the event that a named product or product by a named manufacturer does not meet the other requirements of the specifications, select another named product or product from another named manufacturer that does meet the requirements of the specifications; submit a comparable product request or substitution request, if applicable.
- D. Comparable Product Request Submittal: An action submittal requesting consideration of a comparable product, including the following information:
 - 1. Identification of basis-of-design product or fabrication or installation method to be replaced, including Specification Section number and title and Drawing numbers and titles.
 - 2. Data indicating compliance with the requirements specified in "Comparable Products" Article.
- E. Basis-of-Design Product Specification Submittal: An action submittal complying with requirements in Section 013300 "Submittal Procedures."
- F. Substitution: Refer to Section 012500 "Substitution Procedures" for definition and limitations on substitutions.

1.3 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.
- B. Identification of Products: Except for required labels and operating data, do not attach or imprint manufacturer or product names or trademarks on exposed surfaces of products or equipment that will be exposed to view in occupied spaces or on the exterior.
 - 1. Labels: Locate required product labels and stamps on a concealed surface, or, where required for observation following installation, on a visually accessible surface that is inconspicuous.
 - 2. Equipment Nameplates: Provide a permanent nameplate on each item of service- or poweroperated equipment. Locate on a visually accessible but inconspicuous surface. Include information essential for operation, including the following:
 - a. Name of product and manufacturer.
 - b. Model and serial number.
 - c. Capacity.
 - d. Speed.
 - e. Ratings.

3. See individual identification Sections in Divisions 21, 22, 23, and 26 for additional equipment identification requirements.

1.4 COORDINATION

A. Modify or adjust affected work as necessary to integrate work of approved comparable products and approved substitutions.

1.5 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle products, using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.

B. Delivery and Handling:

- 1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
- 2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
- 3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
- 4. Inspect products on delivery to determine compliance with the Contract Documents and that products are undamaged and properly protected.

C. Storage:

- 1. Provide a secure location and enclosure at Project site for storage of materials and equipment.
- 2. Store products to allow for inspection and measurement of quantity or counting of units.
- 3. Store materials in a manner that will not endanger Project structure.
- 4. Store products that are subject to damage by the elements under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation and with adequate protection from wind.
- 5. Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
- 6. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
- 7. Protect stored products from damage and liquids from freezing.

1.6 PRODUCT WARRANTIES

A. Warranties specified in other Sections are to be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.

- 1. Manufacturer's Warranty: Written standard warranty form furnished by individual manufacturer for a particular product and issued in the name of Owner or endorsed by manufacturer to Owner.
- 2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner and issued in the name of Owner or endorsed by manufacturer to Owner.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.
 - 1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
 - 2. Specified Form: When specified forms are included in the Project Manual, prepare a written document, using indicated form properly executed.
 - 3. See other Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements in Section 017700 "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

- A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.
 - 1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
 - 2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
 - 3. Owner reserves the right to limit selection to products with warranties meeting requirements of the Contract Documents.
 - 4. Where products are accompanied by the term "as selected," Architect will make selection.
 - 5. Descriptive, performance, and reference standard requirements in Specifications establish salient characteristics of products.
 - 6. Or Equal: For products specified by name and accompanied by the term "or equal," "or approved equal," or "or approved," comply with requirements in "Comparable Products" Article to obtain approval for use of an unnamed product.
 - a. Submit additional documentation required by Architect in order to establish equivalency of proposed products. Unless otherwise indicated, evaluation of "or equal" product status is by Architect, whose determination is final.
- B. Product Selection Procedures:

- 1. Sole Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 - a. Sole product may be indicated by the phrase "Subject to compliance with requirements, provide the following."
- 2. Sole Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 - a. Sole manufacturer/source may be indicated by the phrase "Subject to compliance with requirements, provide products by the following."
- 3. Limited List of Products: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered unless otherwise indicated.
 - a. Limited list of products may be indicated by the phrase "Subject to compliance with requirements, provide one of the following."
- 4. Non-Limited List of Products: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed or an unnamed product that complies with requirements.
 - a. Non-limited list of products is indicated by the phrase "Subject to compliance with requirements, available products that may be incorporated in the Work include, but are not limited to, the following."
 - b. Provision of an unnamed product is not considered a substitution, if the product complies with requirements.
- 5. Limited List of Manufacturers: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered unless otherwise indicated.
 - a. Limited list of manufacturers is indicated by the phrase "Subject to compliance with requirements, provide products by one of the following."
- 6. Non-Limited List of Manufacturers: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed or a product by an unnamed manufacturer that complies with requirements.
 - a. Non-limited list of manufacturers is indicated by the phrase "Subject to compliance with requirements, available manufacturers whose products may be incorporated in the Work include, but are not limited to, the following."
 - b. Provision of products of an unnamed manufacturer is not considered a substitution, if the product complies with requirements.

- 7. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications may additionally indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.
 - a. For approval of products by unnamed manufacturers, comply with requirements in Section 012500 "Substitution Procedures" for substitutions for convenience.

2.2 COMPARABLE PRODUCTS

- A. Conditions for Consideration of Comparable Products: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with the following requirements:
 - 1. Evidence that proposed product does not require revisions to the Contract Documents, is consistent with the Contract Documents, will produce the indicated results, and is compatible with other portions of the Work.
 - 2. Detailed comparison of significant qualities of proposed product with those of the named basis-of-design product. Significant product qualities include attributes such as type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other specific features and requirements.
 - 3. Evidence that proposed product provides specified warranty.
 - 4. List of similar installations for completed projects, with project names and addresses and names and addresses of architects and owners, if requested.
 - 5. Samples, if requested.
- B. Architect's Action on Comparable Products Submittal: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for a comparable product. Architect will notify Contractor of approval or rejection of proposed comparable product within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
 - 1. Architect's Approval of Submittal: See Section 013300 "Submittal Procedures."
 - 2. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.
- C. Submittal Requirements, Two-Step Process: Approval by Architect of Contractor's request for use of comparable product is not intended to satisfy other submittal requirements. Comply with specified submittal requirements.
- D. Submittal Requirements, Single-Step Process: When acceptable to Architect, incorporate specified submittal requirements of individual Specification Section in combined submittal for comparable products. Approval by Architect of Contractor's request for use of comparable product and of individual submittal requirements will also satisfy other submittal requirements.

| Rowland Street Highway Facility – Co | ld Storage | PEMB |
|--------------------------------------|------------|------|
|--------------------------------------|------------|------|

PART 3 - EXECUTION (Not Used)

END OF SECTION 016000

EXECUTION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes general administrative and procedural requirements governing execution of the Work, including, but not limited to, the following:
 - 1. Installation.
 - 2. Starting and adjusting.
 - 3. Protection of installed construction.
 - 4. Correction of the Work.

B. Related Requirements:

- 1. Section 011000 "Summary" for coordination of Owner's separate contracts, and limits on use of Project site.
- 2. Section 013300 "Submittal Procedures" for submitting surveys.
- 3. Section 017700 "Closeout Procedures" for submitting final property survey with Project Record Documents, recording of Owner-accepted deviations from indicated lines and levels, replacing defective work, and final cleaning.

1.2 QUALITY ASSURANCE

- A. Professional Engineer Qualifications: Refer to Section 014000 "Quality Requirements."
- B. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of specified products and equipment.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Comply with requirements specified in other Sections.
- B. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
 - 1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
 - 2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
 - 3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.

3.2 PREPARATION

- A. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- B. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- C. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents, submit a request for information to Architect in accordance with requirements in Section 013100 "Project Management and Coordination."

3.3 INSTALLATION

- A. Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
 - 1. Make vertical work plumb, and make horizontal work level.
 - 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure satisfactory results as judged by Architect. Maintain conditions required for product performance until Substantial Completion.

- D. Conduct construction operations, so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy of type expected for Project.
- E. Sequence the Work and allow adequate clearances to accommodate movement of construction items on-site and placement in permanent locations.
- F. Tools and Equipment: Select tools or equipment that minimize production of excessive noise levels.
- G. Templates: Obtain and distribute to the parties involved templates for Work specified to be factory prepared and field installed. Check Shop Drawings of other portions of the Work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.
- H. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions with manufacturer.
 - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
 - 2. Allow for building movement, including thermal expansion and contraction.
 - 3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.
- I. Joints: Make joints of uniform width. Where joint locations in exposed Work are not indicated, arrange joints for the best visual effect, as judged by Architect. Fit exposed connections together to form hairline joints.

3.4 STARTING AND ADJUSTING

- A. Coordinate startup and adjusting of equipment and operating components with requirements in Section 019113 "General Commissioning Requirements."
- B. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.
- C. Adjust equipment for proper operation. Adjust operating components for proper operation without binding.
- D. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- E. Manufacturer's Field Service: Comply with qualification requirements in Section 014000 "Quality Requirements."

3.5 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.
- B. Comply with manufacturer's written instructions for temperature and relative humidity.

3.6 CORRECTION OF THE WORK

- A. Repair or remove and replace damaged, defective, or nonconforming Work. Restore damaged substrates and finishes.
 - 1. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment.
- B. Repair Work previously completed and subsequently damaged during construction period. Repair to like-new condition.
- C. Restore permanent facilities used during construction to their specified condition.
- D. Remove and replace damaged surfaces that are exposed to view if surfaces cannot be repaired without visible evidence of repair.
- E. Repair components that do not operate properly. Remove and replace operating components that cannot be repaired.
- F. Remove and replace chipped, scratched, and broken glass or reflective surfaces.

END OF SECTION 017300

CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for Contract closeout, including, but not limited to, the following:
 - 1. Substantial Completion procedures.
 - 2. Final Completion procedures.
 - 3. List of incomplete items.
 - 4. Submittal of Project warranties.
 - 5. Final cleaning.

B. Related Requirements:

- 1. Section 012900 "Payment Procedures" for requirements for Applications for Payment for Substantial Completion and Final Completion.
- 2. Section 017823 "Operation and Maintenance Data" for additional operation and maintenance manual requirements.
- 3. Section 017839 "Project Record Documents" for submitting Record Drawings, Record Specifications, and Record Product Data.

1.2 DEFINITIONS

A. List of Incomplete Items: Contractor-prepared list of items to be completed or corrected, prepared for the Architect's use prior to Architect's inspection, to determine if the Work is substantially complete.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of cleaning agent.
- B. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.
- C. Certified List of Incomplete Items: Final submittal at Final Completion.

1.4 CLOSEOUT SUBMITTALS

- A. Certificates of Release: From authorities having jurisdiction.
- B. Certificate of Insurance: For continuing coverage.

C. Field Report: For pest-control inspection.

1.5 MAINTENANCE MATERIAL SUBMITTALS

A. Schedule of Maintenance Material Items: For maintenance material submittal items required by other Sections.

1.6 SUBSTANTIAL COMPLETION PROCEDURES

- A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's "punch list"), indicating the value of each item on the list and reasons why the Work is incomplete.
- B. Submittals Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
 - 1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction, permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
 - 2. Submit closeout submittals specified in other Division 01 Sections, including Project Record Documents, operation and maintenance manuals, damage or settlement surveys, property surveys, and similar final record information.
 - 3. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
 - 4. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by Architect. Label with manufacturer's name and model number.
 - a. Schedule of Maintenance Material Items: Prepare and submit schedule of maintenance material submittal items, including name and quantity of each item and name and number of related Specification Section. Obtain Owner's signature for receipt of submittals.
 - 5. Submit testing, adjusting, and balancing records.
 - 6. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
- C. Procedures Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
 - 1. Advise Owner of pending insurance changeover requirements.
 - 2. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
 - 3. Complete startup and testing of systems and equipment.
 - 4. Perform preventive maintenance on equipment used prior to Substantial Completion.

- 5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems. Submit demonstration and training video recordings specified in Section 017900 "Demonstration and Training."
- 6. Advise Owner of changeover in utility services.
- 7. Participate with Owner in conducting inspection and walkthrough with local emergency responders.
- 8. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
- 9. Complete final cleaning requirements.
- 10. Touch up paint and otherwise repair and restore marred exposed finishes to eliminate visual defects.
- D. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of 10 days prior to date the Work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.
 - 1. Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
 - 2. Results of completed inspection will form the basis of requirements for Final Completion.

1.7 FINAL COMPLETION PROCEDURES

- A. Submittals Prior to Final Completion: Before requesting final inspection for determining Final Completion, complete the following:
 - 1. Submit a final Application for Payment in accordance with Section 012900 "Payment Procedures."
 - 2. Certified List of Incomplete Items: Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list will state that each item has been completed or otherwise resolved for acceptance.
 - 3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.
 - 4. Submit pest-control final inspection report.
 - 5. Submit Final Completion photographic documentation.
- B. Inspection: Submit a written request for final inspection to determine acceptance a minimum of 10 days prior to date the Work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.
 - 1. Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.8 LIST OF INCOMPLETE ITEMS

- A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
 - 1. Organize list of spaces in sequential order, listed by room or space number.
 - 2. Organize items applying to each space by major element, including categories for ceilings, individual walls, floors, equipment, and building systems.
 - 3. Include the following information at the top of each page:
 - a. Project name.
 - b. Date.
 - c. Name of Architect.
 - d. Name of Contractor.
 - e. Page number.
 - 4. Submit list of incomplete items in the following format:
 - a. PDF Electronic File: Architect, will return annotated file.

1.9 SUBMITTAL OF PROJECT WARRANTIES

- A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where warranties are indicated to commence on dates other than date of Substantial Completion, or when delay in submittal of warranties might limit Owner's rights under warranty.
- B. Organize warranty documents into an orderly sequence based on the table of contents of Project Manual.
- C. Warranty Electronic File: Provide warranties and bonds in PDF format. Assemble complete warranty and bond submittal package into a single electronic PDF file with bookmarks enabling navigation to each item. Provide bookmarked table of contents at beginning of document.
 - 1. Submit on digital media acceptable to Architect.
- D. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
 - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:
 - a. Clean Project site of rubbish, waste material, litter, and other foreign substances.
 - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
 - c. Remove tools, construction equipment, machinery, and surplus material from Project site.
 - d. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
 - e. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Polish mirrors and glass, taking care not to scratch surfaces.
 - f. Remove labels that are not permanent.
 - g. Wipe surfaces of equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.

3.2 CORRECTION OF THE WORK

A. Complete repair and restoration operations required by "Correction of the Work" Article in Section 017300 "Execution" before requesting inspection for determination of Substantial Completion.

END OF SECTION 017700

SECTION 017823

OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:
 - 1. Operation and maintenance documentation directory manuals.
 - 2. Emergency manuals.
 - 3. Systems and equipment operation manuals.
 - 4. Systems and equipment maintenance manuals.
 - 5. Product maintenance manuals.

B. Related Requirements:

1. Section 013300 "Submittal Procedures" for submitting copies of submittals for operation and maintenance manuals.

1.3 DEFINITIONS

- A. System: An organized collection of parts, equipment, or subsystems united by regular interaction.
- B. Subsystem: A portion of a system with characteristics similar to a system.

1.4 CLOSEOUT SUBMITTALS

- A. Submit operation and maintenance manuals indicated. Provide content for each manual as specified in individual Specification Sections, and as reviewed and approved at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.
 - 1. Architect will comment on whether content of operation and maintenance submittals is acceptable.
 - 2. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.
- B. Format: Submit operation and maintenance manuals in the following format:

- 1. Submit by email to Architect Enable reviewer comments on draft submittals.
- C. Final Manual Submittal: Submit each manual in final form prior to requesting inspection for Substantial Completion and at least 15 days before commencing demonstration and training. Architect will return copy with comments.
 - 1. Correct or revise each manual to comply with Architect's comments. Submit copies of each corrected manual within 15 days of receipt of Architect's comments and prior to commencing demonstration and training.
- D. Comply with Section 017700 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

1.5 FORMAT OF OPERATION AND MAINTENANCE MANUALS

- A. Manuals, Electronic Files: Submit manuals in the form of a multiple file composite electronic PDF file for each manual type required.
 - 1. Electronic Files: Use electronic files prepared by manufacturer where available. Where scanning of paper documents is required, configure scanned file for minimum readable file size.
 - 2. File Names and Bookmarks: Bookmark individual documents based on file names. Name document files to correspond to system, subsystem, and equipment names used in manual directory and table of contents. Group documents for each system and subsystem into individual composite bookmarked files, then create composite manual, so that resulting bookmarks reflect the system, subsystem, and equipment names in a readily navigated file tree. Configure electronic manual to display bookmark panel on opening file.

1.6 REQUIREMENTS FOR EMERGENCY, OPERATION, AND MAINTENANCE MANUALS

- A. Organization of Manuals: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual shall contain the following materials, in the order listed:
 - 1. Title page.
 - 2. Table of contents.
 - 3. Manual contents.
- B. Title Page: Include the following information:
 - 1. Subject matter included in manual.
 - 2. Name and address of Project.
 - 3. Name and address of Owner.
 - 4. Date of submittal.
 - 5. Name and contact information for Contractor.
 - 6. Name and contact information for Construction Manager.
 - 7. Name and contact information for Architect.
 - 8. Name and contact information for Commissioning Authority.

- 9. Names and contact information for major consultants to the Architect that designed the systems contained in the manuals.
- 10. Cross-reference to related systems in other operation and maintenance manuals.
- C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.
- D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.
- E. Identification: In the documentation directory and in each operation and maintenance manual, identify each system, subsystem, and piece of equipment with same designation used in the Contract Documents. If no designation exists, assign a designation according to ASHRAE Guideline 4, "Preparation of Operating and Maintenance Documentation for Building Systems."

1.7 EMERGENCY MANUALS

- A. Emergency Manual: Assemble a complete set of emergency information indicating procedures for use by emergency personnel and by Owner's operating personnel for types of emergencies indicated.
- B. Content: Organize manual into a separate section for each of the following:
 - 1. Type of emergency.
 - 2. Emergency instructions.
 - 3. Emergency procedures.
- C. Type of Emergency: Where applicable for each type of emergency indicated below, include instructions and procedures for each system, subsystem, piece of equipment, and component:
 - 1. Fire.
 - 2. Gas leak.
 - 3. Power failure.
 - 4. System, subsystem, or equipment failure.
 - 5. Chemical release or spill.
- D. Emergency Instructions: Describe and explain warnings, trouble indications, error messages, and similar codes and signals. Include responsibilities of Owner's operating personnel for notification of Installer, supplier, and manufacturer to maintain warranties.
- E. Emergency Procedures: Include the following, as applicable:
 - 1. Instructions on stopping.
 - 2. Shutdown instructions for each type of emergency.
 - 3. Operating instructions for conditions outside normal operating limits.
 - 4. Required sequences for electric or electronic systems.
 - 5. Special operating instructions and procedures.

1.8 SYSTEMS AND EQUIPMENT OPERATION MANUALS

- A. Systems and Equipment Operation Manual: Assemble a complete set of data indicating operation of each system, subsystem, and piece of equipment not part of a system. Include information required for daily operation and management, operating standards, and routine and special operating procedures.
 - 1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
 - 2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.
- B. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:
 - 1. System, subsystem, and equipment descriptions. Use designations for systems and equipment indicated on Contract Documents.
 - 2. Performance and design criteria if Contractor has delegated design responsibility.
 - 3. Operating standards.
 - 4. Operating procedures.
 - 5. Operating logs.
 - 6. Wiring diagrams.
 - 7. Control diagrams.
 - 8. Piped system diagrams.
 - 9. Precautions against improper use.
 - 10. License requirements including inspection and renewal dates.
- C. Descriptions: Include the following:
 - 1. Product name and model number. Use designations for products indicated on Contract Documents.
 - 2. Manufacturer's name.
 - 3. Equipment identification with serial number of each component.
 - 4. Equipment function.
 - 5. Operating characteristics.
 - 6. Limiting conditions.
 - 7. Performance curves.
 - 8. Engineering data and tests.
 - 9. Complete nomenclature and number of replacement parts.
- D. Operating Procedures: Include the following, as applicable:
 - 1. Startup procedures.
 - 2. Equipment or system break-in procedures.
 - 3. Routine and normal operating instructions.
 - 4. Regulation and control procedures.
 - 5. Instructions on stopping.
 - 6. Normal shutdown instructions.
 - 7. Seasonal and weekend operating instructions.
 - 8. Required sequences for electric or electronic systems.
 - 9. Special operating instructions and procedures.

- E. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.
- F. Piped Systems: Diagram piping as installed, and identify color coding where required for identification.

1.9 SYSTEMS AND EQUIPMENT MAINTENANCE MANUALS

- A. Systems and Equipment Maintenance Manuals: Assemble a complete set of data indicating maintenance of each system, subsystem, and piece of equipment not part of a system. Include manufacturers' maintenance documentation, preventive maintenance procedures and frequency, repair procedures, wiring and systems diagrams, lists of spare parts, and warranty information.
 - 1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
 - 2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.
- B. Content: For each system, subsystem, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranties and bonds as described below.
- C. Source Information: List each system, subsystem, and piece of equipment included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.
- D. Manufacturers' Maintenance Documentation: Include the following information for each component part or piece of equipment:
 - 1. Standard maintenance instructions and bulletins; include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.
 - a. Prepare supplementary text if manufacturers' standard printed data are not available and where the information is necessary for proper operation and maintenance of equipment or systems.
 - 2. Drawings, diagrams, and instructions required for maintenance, including disassembly and component removal, replacement, and assembly.
 - 3. Identification and nomenclature of parts and components.
 - 4. List of items recommended to be stocked as spare parts.
- E. Maintenance Procedures: Include the following information and items that detail essential maintenance procedures:

- 1. Test and inspection instructions.
- 2. Troubleshooting guide.
- 3. Precautions against improper maintenance.
- 4. Disassembly; component removal, repair, and replacement; and reassembly instructions.
- 5. Aligning, adjusting, and checking instructions.
- 6. Demonstration and training video recording, if available.
- F. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules for preventive and routine maintenance and service with standard time allotment.
 - 1. Scheduled Maintenance and Service: Tabulate actions for daily, weekly, monthly, quarterly, semiannual, and annual frequencies.
 - 2. Maintenance and Service Record: Include manufacturers' forms for recording maintenance.
- G. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.
- H. Maintenance Service Contracts: Include copies of maintenance agreements with name and telephone number of service agent.
- I. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
 - 1. Include procedures to follow and required notifications for warranty claims.
- J. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in record Drawings to ensure correct illustration of completed installation.
 - 1. Do not use original project record documents as part of maintenance manuals.

1.10 PRODUCT MAINTENANCE MANUALS

- A. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.
- B. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.
- C. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.

- D. Product Information: Include the following, as applicable:
 - 1. Product name and model number.
 - 2. Manufacturer's name.
 - 3. Color, pattern, and texture.
 - 4. Material and chemical composition.
 - 5. Reordering information for specially manufactured products.
- E. Maintenance Procedures: Include manufacturer's written recommendations and the following:
 - 1. Inspection procedures.
 - 2. Types of cleaning agents to be used and methods of cleaning.
 - 3. List of cleaning agents and methods of cleaning detrimental to product.
 - 4. Schedule for routine cleaning and maintenance.
 - 5. Repair instructions.
- F. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.
- G. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
 - 1. Include procedures to follow and required notifications for warranty claims.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 017823

SECTION 017839

PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for Project Record Documents, including the following:
 - 1. Record Drawings.
 - 2. Record specifications.
 - 3. Record Product Data.
 - 4. Miscellaneous record submittals.

B. Related Requirements:

- 1. Section 017700 "Closeout Procedures" for general closeout procedures.
- 2. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.

1.3 CLOSEOUT SUBMITTALS

- A. Record Drawings: Comply with the following:
 - 1. Number of Copies: Submit one set(s) of marked-up record prints.
 - 2. Number of Copies: Submit copies of Record Drawings as follows:
 - a. Initial Submittal:
 - 1) Submit PDF electronic files of scanned record prints and one set(s) of file prints.
 - b. Final Submittal:
 - 1) Submit PDF electronic files of scanned Record Prints and three set(s) of file prints.
 - 2) Print each drawing, whether or not changes and additional information were recorded.
- B. Record Specifications: Submit annotated PDF electronic files of Project's Specifications, including addenda and Contract modifications.
- C. Record Product Data: Submit annotated PDF electronic files and directories of each submittal.

- 1. Where record Product Data are required as part of operation and maintenance manuals, submit duplicate marked-up Product Data as a component of manual.
- D. Miscellaneous Record Submittals: See other Specification Sections for miscellaneous record-keeping requirements and submittals in connection with various construction activities. Submit annotated PDF electronic files and directories of each submittal.

1.4 RECORD DRAWINGS

- A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.
 - 1. Preparation: Mark record prints to show the actual installation, where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.
 - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
 - b. Accurately record information in an acceptable drawing technique.
 - c. Record data as soon as possible after obtaining it.
 - d. Record and check the markup before enclosing concealed installations.
 - e. Cross-reference record prints to corresponding photographic documentation.
 - 2. Content: Types of items requiring marking include, but are not limited to, the following:
 - a. Dimensional changes to Drawings.
 - b. Revisions to details shown on Drawings.
 - c. Depths of foundations.
 - d. Locations and depths of underground utilities.
 - e. Revisions to routing of piping and conduits.
 - f. Revisions to electrical circuitry.
 - g. Actual equipment locations.
 - h. Duct size and routing.
 - i. Locations of concealed internal utilities.
 - j. Changes made by Change Order or Construction Change Directive.
 - k. Changes made following Architect's written orders.
 - 1. Details not on the original Contract Drawings.
 - m. Field records for variable and concealed conditions.
 - n. Record information on the Work that is shown only schematically.
 - 3. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
 - 4. Mark record prints with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
 - 5. Mark important additional information that was either shown schematically or omitted from original Drawings.
 - 6. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.

- B. Record Digital Data Files: Immediately before inspection for Certificate of Substantial Completion, review marked-up record prints with Architect. When authorized, prepare a full set of corrected digital data files of the Contract Drawings, as follows:
 - 1. Format: Annotated PDF electronic file.
 - 2. Incorporate changes and additional information previously marked on record prints. Delete, redraw, and add details and notations where applicable.
 - 3. Refer instances of uncertainty to Architect for resolution.
 - 4. Architect will furnish Contractor with one set of digital data files of the Contract Drawings for use in recording information.
 - a. See Section 013100 "Project Management and Coordination" for requirements related to use of Architect's digital data files.
 - b. Architect will provide data file layer information. Record markups in separate layers.
- C. Format: Identify and date each Record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.
 - 1. Record Prints: Organize record prints into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
 - 2. Format: Annotated PDF electronic file.
 - 3. Record Digital Data Files: Organize digital data information into separate electronic files that correspond to each sheet of the Contract Drawings. Name each file with the sheet identification. Include identification in each digital data file.
 - 4. Identification: As follows:
 - a. Project name.
 - b. Date.
 - c. Designation "PROJECT RECORD DRAWINGS."
 - d. Name of Architect.
 - e. Name of Contractor.

1.5 RECORD SPECIFICATIONS

- A. Preparation: Mark Specifications to indicate the actual product installation, where installation varies from that indicated in Specifications, addenda, and Contract modifications.
 - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 - 2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
 - 3. Record the name of manufacturer, supplier, Installer, and other information necessary to provide a record of selections made.
 - 4. For each principal product, indicate whether Record Product Data has been submitted in operation and maintenance manuals instead of submitted as Record Product Data.
 - 5. Note related Change Orders, Record Product Data, and Record Drawings where applicable.
- B. Format: Submit record specifications as annotated PDF electronic file.

1.6 RECORD PRODUCT DATA

- A. Recording: Maintain one copy of each submittal during the construction period for Project Record Document purposes. Post changes and revisions to Project Record Documents as they occur; do not wait until end of Project.
- B. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.
 - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 - 2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
 - 3. Note related Change Orders, Record Specifications, and Record Drawings where applicable.
- C. Format: Submit Record Product Data as annotated PDF electronic file.
 - 1. Include Record Product Data directory organized by Specification Section number and title, electronically linked to each item of Record Product Data.

1.7 MISCELLANEOUS RECORD SUBMITTALS

- A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.
- B. Format: Submit miscellaneous record submittals as PDF electronic file.
 - 1. Include miscellaneous record submittals directory organized by Specification Section number and title, electronically linked to each item of miscellaneous record submittals.

1.8 MAINTENANCE OF RECORD DOCUMENTS

A. Maintenance of Record Documents: Store Record Documents in the field office apart from the Contract Documents used for construction. Do not use Project Record Documents for construction purposes. Maintain Record Documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to Project Record Documents for Architect's reference during normal working hours.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 017839

SECTION 074113

INSULATED METAL ROOF PANELS

PART 1 - GENERAL

1.1 SECTION INCLUDES

A. Foamed-insulation-core standing seam metal roof panels, with related metal trim and accessories.

1.2 RELATED REQUIREMENTS

- A. Division 07 Section "Joint Sealants" for field-applied Joint Sealants.
- B. Division 13 Section "Metal Building Systems" for steel framing supporting metal panels.

1.3 REFERENCES

- A. American Society of Civil Engineers (ASCE): www.asce.org/codes-standards:
 - 1. ASCE 7 Minimum Design Loads for Buildings and Other Structures.
- B. ASTM International (ASTM): www.astm.org:
 - 1. ASTM A 653 Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
 - 2. ASTM A 755 Specification for Steel Sheet, Metallic Coated by the Hot-Dip Process and Prepainted by the Coil-Coating Process for Exterior Exposed Building Products.
 - 3. ASTM A 792 Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process.
 - 4. ASTM A 924 General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process.
 - 5. ASTM C 1363 Standard Test Method for Thermal Performance of Building Materials and Envelope Assemblies by Means of a Hot Box Apparatus
 - 6. ASTM D 1621 Compressive Properties of Rigid Cellular Plastics.
 - 7. ASTM D 1622 Apparent Density of Rigid Cellular Plastics.
 - 8. ASTM D 6226 Standard Test Method for Open Cell Content of Rigid Cellular Plastics
 - 9. ASTM C 518 Standard Test Method for Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus.
 - 10. ASTM D 2244 Test Method for Calculation of Color Differences from Instrumentally Measured Color Coordinates.
 - 11. ASTM D 4214 Test Methods for Evaluating Degree of Chalking of Exterior Paint Films.
 - 12. ASTM E 72 Standard Test Methods of Conducting Strength Tests of Panels for Building Construction.
 - 13. ASTM E 84 Test Methods for Surface Burning Characteristics of Building Materials.
 - 14. ASTM E 1592 Standard Test Method for Structural Performance of Sheet Metal Roof and Siding Systems by Uniform Static Air Pressure Difference.
 - 15. ASTM E 1646 Standard Test Method for Water Penetration of Exterior Metal Roof Panel Systems by Uniform Static Air Pressure Difference.

- 16. ASTM E 1680 Standard Test Method for Rate of Air Leakage through Exterior Metal Roof Panel Systems.
- 17. ASTM E 1980 Practice for Calculating Solar Reflectance Index of Horizontal and Low-Sloped Opaque Surfaces.
- C. Cool Roof Rating Council (CRRC): www.coolroofs.org/productratingprogram.html:
 - 1. CRRC-1-2016 CRRC Product Rating Program.
- D. Green Seal (GS) www.greenseal.org
 - 1. GS-11 Green Seal Standard for Paints and Coatings, Edition 3.2, October 26, 2015. US Green Building Council (USGBC): www.usgbc.org:

1.4 QUALITY ASSURANCE

- A. Manufacturer/Source: Provide metal panel assemblies and accessories from a single manufacturer approved under an accredited third-party quality control program
- B. Manufacturer Qualifications: Approved manufacturer listed in this Section with minimum ten years' experience in the manufacturing of similar products and successful use in similar applications.
 - 1. Approval of Comparable Products: Submit the following in accordance with project substitution requirements, within time allowed for substitution review:
 - a. Product data, including certified independent test data indicating compliance with requirements.
 - b. Samples of each component.
 - c. Sample submittal from similar project.
 - d. Project references: Minimum of five installations not less than five years old, with Owner and Architect contact information.
 - e. Sample warranty.
 - f. Certificate from an accredited third-party Quality Control Program.
- 1.5 Substitutions following award of contract are not allowed except as stipulated in Division 01 General Requirements
- 1.6 Approved manufacturers must meet separate requirements of Submittals Article.
 - A. Installer Qualifications: Experienced Installer with minimum of five years' experience with successfully completed projects of a similar nature and scope.
 - 1. Installer's Field Supervisor: Experienced mechanic [certified by metal panel manufacturer] supervising work on site whenever work is underway.
 - B. Buy American Compliance: Materials provided under work of this Section shall comply with the following requirements:
 - 1. Buy American Act of 1933 BAA-41 U.S.C §§ 10a 10d.
 - 2. Buy American provisions of Section 1605 of the American Recovery and Reinvestment Act of 2009 (ARRA).

1.7 ADMINISTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Prior to erection of framing, conduct preinstallation meeting at site attended by Owner, Architect, metal panel installer, metal panel manufacturer's technical representative, inspection agency, and related trade contractors.
 - 1. Coordinate building framing in relation to metal panel system.
 - 2. Coordinate openings and penetrations of metal panel system.

1.8 ACTION SUBMITTALS

- A. Product Data: Manufacturer's data sheets for specified products.
- B. Shop Drawings: Show layouts of metal panels. Include details of each condition of installation, panel profiles, and attachment to building. Provide details at a minimum scale 1-1/2-inch per foot of edge conditions, joints, fastener and sealant placement, flashings, openings, penetrations, curbs, vents, snow guards, lightning arresting equipment, and special details. Make distinctions between factory and field assembled work.
 - 1. Include data indicating compliance with performance requirements.
 - 2. Indicate points of supporting structure that must coordinate with metal panel system installation.
 - 3. Include structural data indicating compliance with performance requirements and requirements of local authorities having jurisdiction.
- C. Samples for Initial Selection: For each exposed product specified including sealants. Provide representative color charts of manufacturer's full range of colors.
- D. Samples for Verification:
 - 1. Provide 12-inch- (305 mm-) long section of each metal panel profile.
 - 2. Provide color chip verifying color selection.

1.9 INFORMATIONAL SUBMITTALS

- A. Product Test Results: Indicating compliance of products with requirements.
- B. Qualification Information: For Installer firm and Installer's field supervisor.
- C. Accreditation Certificate: Indicating that manufacturer is accredited under an accredited third-party quality control program, including IAS AC472 and based upon chapter 17 of the International Building Code (IBC).
- D. Buy American Certification: Manufacturers' letters of compliance acceptable to authorities having jurisdiction, indicating that products comply with requirements.
- E. Warranty:
 - 1. Submit manufacturer's written two (2) year limited warranty providing panels to be free from defects in materials and workmanship, beginning from the date of substantial completion excluding coil coatings (paint finishes) that are covered under a separate warranty.
 - 2. The installation contractor shall issue a separate warranty against defects in installed materials and workmanship, beginning from the date of substantial completion of the installation.

1.10 CLOSEOUT SUBMITTALS

- A. Maintenance data.
- B. Manufacturer's Warranty: Executed copy of manufacturer's warranty.

1.11 DELIVERY, STORAGE, AND HANDLING

- A. Protect products of metal panel system during shipping, handling, and storage to prevent staining, denting, deterioration of components, or other damage. Protect panels and trim bundles during shipping. Protect painted surfaces with a protective covering before shipping.
 - 1. Deliver, unload, store, and erect metal panels and accessory items without misshaping panels or exposing panels to surface damage from weather or construction operations.
 - 2. Store in accordance with Manufacturer's written instructions. Provide wood collars for stacking and handling in the field.
 - 3. Shield foam insulated metal panels from direct sunlight until installation.

1.12 WARRANTY

- A. Special Manufacturer's Warranty: Submit Manufacturer's two (2) year limited warranty providing panels to be free from defects in materials and workmanship, beginning from the date of substantial completion excluding coil coatings (paint finishes) that are covered under a separate warranty.
- B. The installation contractor shall issue a separate warranty against defects in installed materials and workmanship, beginning from the date of substantial completion of the installation.
- C. Special Panel Finish Warranty: Submit Manufacturer's limited warranty on the exterior paint finish for adhesion to the metal substrate and limited warranty on the exterior paint finish for chalk and fade.
 - 1. Fluoropolymer Two-Coat System:
 - a. Color fading in excess of 5 or 10 for copper, silver metallic and bright red; Hunter units per ASTM D 2244.
 - b. Chalking in excess of 6 for copper, silver metallic and bright red or 8 rating per ASTM D 4214.
 - c. Failure of adhesion, peeling, checking, or cracking.
 - 2. Modified Silicone-Polyester Two-Coat System:
 - a. Color fading in excess of [5] or [7] for crimson red; Hunter units per ASTM D 2244.
 - b. Chalking in excess of [7] for crimson red or [8] rating per ASTM D 4214.
 - c. Failure of adhesion, peeling, checking, or cracking.

PART 2 - PRODUCTS

2.1 MANUFACTURER

- A. Basis of Design Manufacturer: Metl-Span, a Nucor company; Lewisville, Texas Tel: 972.221.6656; Email: info@metlspan.com; Web: metlspan.com
 - 1. Provide basis of design product, or comparable product approved by Architect prior to bid.

2.2 PERFORMANCE REQUIREMENTS

- A. General: Provide metal panel system meeting performance requirements as determined by application of specified tests by a qualified testing facility on manufacturer's standard assemblies.
- B. Structural Performance: Provide metal panel assemblies capable of withstanding the effects of indicated loads and stresses within limits and under conditions indicated, as determined by ASTM E 72 or ASTM E 1592 applied in accordance with ICC AC 04, Section 4, Panel Load Test Option or Section 5, Panel Analysis Option:
 - 1. Wind Loads: Determine loads based on uniform pressure, importance factor, exposure category, and basic wind speed indicated on drawings.
 - a. Roof Panel Wind Uplift Testing: Certify capacity of metal panels by testing of proposed assembly per ASTM E 72 or ASTM E 1592.
 - 2. Roof Panel Snow Loads: As indicated on drawings.
 - 3. Deflection Limits: Withstand inward and outward wind-load design pressures in accordance with applicable building code with maximum deflection of 1/240 of the span with no evidence of failure.
- C. Fire Performance Characteristics: Provide metal panel systems with the following fire-test characteristics determined by indicated test standard as applied by UL or other testing and inspection agency acceptable to authorities having jurisdiction.
 - 1. Surface-Burning Characteristics: Provide metal panel systems with the following characteristics when tested per ASTM E 84. The core shall have:
 - a. Flame spread index: 25 or less.
 - b. Smoke developed index: 450 or less.
 - 2. Fire Performance of Insulated Roof: Class 1 roof and wall panel per ANSI/FM 4880.
- D. Roof Panel Air Infiltration, ASTM E 1680: Maximum 0.023 cfm/sq. ft. (0.115 L/s per sq. m) at static-air-pressure difference of 12 lbf/sq. ft. (575 Pa).
- E. Roof Panel Water Penetration Static Pressure, ASTM E 1646: No uncontrolled water penetration at a static pressure of 20 lbf/sq. ft. (958 Pa).
- F. Test procedure for susceptibility to leakage of discontinuous roof systems protocol TAS 114: Water applied to a depth of 6" above the lowest section of roof profile. No water infiltration observed during the seven-day test period.
- G. Thermal Movements: Allow for thermal movements from variations in both ambient and internal temperatures. Accommodate movement of support structure caused by thermal expansion and contraction. Allow for deflection and design for thermal stresses caused by temperature differences from one side of the panel to the other.
- H. Thermal Performance: When tested in accordance with ASTM C 518, Measurement of Steady State thermal Transmission, the panels shall provide a k factor of 0.114 btu/sf/hr/deg F at a 35° F (1.67° C) mean temperature.

2.3 INSULATED METAL ROOF PANELS

- A. Standing Seam, Foamed-Insulation-Core Metal Roof Panels: Structural metal panels consisting of an exterior standing seam with an interior tongue and groove joint, coupled with a vapor seal in the standing seam, and provides superior resistance to air and moisture intrusion. Attached with concealed fasteners to the structure.
 - 1. Basis of Design: Metl-Span, CFR Insulated Metal Panel.
 - 2. G-90 Galvanized Coated Steel: ASTM A 653 or Aluminum-Zinc Alloy-Coated Steel: ASTM A 792/A 792M, structural quality, Grade 50, Coating Class AZ50 (Grade 340, Coating Class AZM150), prepainted by the coil-coating process per ASTM A 755/A 755M.
 - 3. Exterior Face Sheet: Gauge thickness required to meet loads indicated on drawings, with stucco embossed surface.
 - 1) Finish: Fluoropolymer two-coat metallic color system.
 - 2) Color: As selected by Architect from manufacturer's standard colors.
 - 4. Interior Face Sheet: Gauge thickness required to meet loads indicated on drawings, with stucco embossed surface Mesa profile.
 - 1) Finish: Fluoropolymer two-coat system.
 - 2) Color: As selected by Architect from manufacturer's standard colors.
 - 5. Endlaps: Provide panels with factory endlaps, notching, swedging and backer plates; where panel lengths permit.
 - 6. Low Eave Treatment: Provide cutback for trim/gutter installation; where panel lengths permit.
 - 7. Panel Width: 42 inches (1067 mm).
 - 6. Panel Thickness: 6 inch (152 mm).
 - 7. Insulating Core: Polyurethane with zero ozone depletion potential blowing agent
 - a. Closed Cell Content: 90% or more as determined by ASTM D 6226
 - b. Compressive Strength: As required to meet structural performance requirements and with a minimum of 22 psi as determined by ASTM D 1621
 - c. Shear Strength: As required to meet structural performance requirements and with a minimum of 36 psi as determined by ASTM C 273
 - d. Tensile Strength: As required to meet structural performance requirements and with a minimum of 41 psi ASTM D 1623
 - e. Minimum Density: 2.0 pcf (32 kg/m3) as determined by ASTM D 1622
 - d. Thermal Resistance (R-Value): 52.5 deg. F * hr * sq. ft./Btu as determined by ASTM C 518 at 35 degrees Fahrenheit mean temperature.
 - 8. Heat Transfer Coefficient (U-factor): 0.022 Btu/hr * sq. ft. * deg. F as determined by ASTM C 1363 at 35 degrees Fahrenheit mean temperature. Tested specimen must include at least two engaged side joints.

2.4 METAL ROOF PANEL ACCESSORIES

- A. General: Provide complete metal panel assemblies incorporating trim, copings, fasciae, gutters and downspouts, and miscellaneous flashings. Provide required fasteners, closure strips, and sealants as indicated in manufacturer's written instructions.
- B. Flashing and Trim: Match material, thickness, and finish of metal panel face sheet.
- C. Panel Fasteners: Self-tapping screws and other acceptable fasteners recommended by metal panel manufacturer. Provide corrosion-resistant fasteners with heads matching color of metal panels by means of factory-applied coating, with weathertight resilient washers.
- D. Joint Sealers: Provide Tape Mastic Sealants and Concealed <u>Joint Sealants</u> per Section 07 92 00, "Joint Sealants".
- E. Roof Accessories: Approved by metal panel manufacturer. Refer to Section 07 72 00 "Roof Accessories" for requirements for curbs, equipment supports, roof hatches, heat and smoke vents, ventilators, and preformed flashing sleeves.
- F. Snow Guards: Compatible with standing seam roof and approved by metal panel manufacturer. Refer to Section 07 72 53 "Snow Guards" for requirements for snow guards attached to metal roof panels.
- G. Roof Curbs: Compatible with standing seam roof and approved by metal panel manufacture. Refer to Section 07 72 10 "Roof Curbs" for requirements for roof curbs attached to metal roof panels.

2.5 FABRICATION

- A. General: Provide factory fabricated and finished metal panels, trim, and accessories meeting performance requirements, indicated profiles, and structural requirements.
- B. Fabricate metal panel joints configured to accept sealant tape providing weathertight seal and preventing metal-to-metal contact and minimizing noise resulting from thermal movement.
- C. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's written instructions, approved shop drawings, and project drawings.

2.6 FINISHES

- A. Finishes, General: Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
- B. Exterior Face Sheet Coil-Coated Finish System
 - Silicone-Polyester Two-Coat System: 0.20 0.25 mil primer with 0.7 0.8 mil color coat.
 Basis of Design: Metl-Span, Silicone Polyester.
 - 2. Fluoropolymer Two-Coat System: 0.2 0.3 mil primer with 0.7 0.8 mil 70 percent PVDF fluoropolymer color coat.
 - a. Basis of Design: Metl-Span, Fluoropolymer.
- C. Interior Face Sheet Coil-Coated Finish System:
 - 1. Fluoropolymer Two-Coat System: 0.2-mil primer with 0.7 0.8 mil 70 percent PVDF fluoropolymer color coat
 - a. Basis of Design: Metl-Span, Fluoropolymer

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine metal panel system substrate with Installer present. Inspect for erection tolerances and other conditions that would adversely affect installation of metal panels.
 - 1. Inspect framing that will support insulated metal panels to determine if support components are installed as indicated on approved shop drawings and are within tolerances acceptable to metal panel manufacturer and installer. Confirm presence of acceptable framing members at recommended spacing to match installation requirements of metal panels.
 - 2. Panel Support Tolerances: Confirm that metal panel supports are within tolerances acceptable to metal panel manufacturer but not greater than the following:
 - a. 1/4 inch (6 mm) in 20 foot (6100 mm) in any direction.
 - b. 3/8 inch (9 mm) over any single roof plane.
 - c. At Purlin Spacing 7 feet (2133 mm) or less: 1/8 inches (3 mm), out only.
- B. Correct out-of-tolerance work and other deficient conditions prior to proceeding with insulated metal panel installation.

3.2 METAL PANEL INSTALLATION

- A. Standing Seamed, Concealed-Fastener Insulated Metal Panels: Install metal panel system in accordance with manufacturer's written instructions, approved shop drawings, and project drawings. Install metal panels in orientation, sizes, and locations indicated. Anchor panels and other components securely in place. Provide for thermal and structural movement.
- B. Attach panels to metal framing using clips, fasteners, and sealants recommended for application by metal panel manufacturer.
 - 1. Fasten metal panels to supports with fasteners at each location indicated on approved shop drawings, at spacing and with fasteners recommended by manufacturer.
 - 2. Cut panels in field where required using manufacturer's recommended methods.
 - 3. Provide weatherproof jacks for pipe and conduit penetrating metal panels.
 - 4. Dissimilar Materials: Where elements of metal panel system will come into contact with dissimilar materials, treat faces and edges in contact with dissimilar materials as recommended by metal panel manufacturer.
- C. Attach panel flashing trim pieces to supports using recommended fasteners and joint sealers.
- D. Joint Sealers: Install tape sealers and liquid sealants where indicated and where required for weatherproof performance of metal panel assemblies.
 - 1. Seal panel side and perimeter joints using joint sealers indicated in manufacturer's instructions.
 - 2. Seal roof panel joints utilizing tape sealer and vapor seal bead of non-curing butyl.
 - 3. Prepare joints and apply sealants per requirements of Division 07 Section "Joint Sealants."

3.3 ACCESSORY INSTALLATION

A. General: Install metal panel accessories with positive anchorage to building and weathertight mounting; provide for thermal expansion. Coordinate installation with flashings and other components.

- 1. Install components required for a complete metal panel assembly, including trim, copings, flashings, sealants, closure strips, and similar items.
- 2. Comply with details of assemblies utilized to establish compliance with performance requirements and manufacturer's written installation instructions.
- 3. Set units true to line and level as indicated. Install work with laps, joints, and seams that will be permanently weather resistant.

3.4 CLEANING AND PROTECTION

- A. Remove temporary protective films immediately in accordance with metal panel manufacturer's instructions. Clean finished surfaces as recommended by metal panel manufacturer.
- B. Replace damaged panels and accessories that cannot be repaired to the satisfaction of the Architect.

END OF SECTION 074113

SECTION 074213

INSULATED METAL WALL PANELS

PART 1 - GENERAL

1.1 SECTION INCLUDES

A. Foamed-insulation-core concealed fastener metal wall panels, with related metal trim and accessories.

1.2 RELATED REQUIREMENTS

- A. Division 13 Section "Metal Building Systems" for steel framing supporting metal panels.
- B. REFERENCES
- C. American Architectural Manufacturer's Association (AAMA): www.aamanet.org:
 - 1. AAMA 501.2 Quality Assurance and Diagnostic Water Leakage Field Check of Installed Storefronts, Curtain Walls, and Sloped Glazing Systems.
- D. American Society of Civil Engineers (ASCE): www.asce.org/codes-standards:
 - 1. ASCE 7 Minimum Design Loads for Buildings and Other Structures.
- E. ASTM International (ASTM): www.astm.org:
 - 1. ASTM A 653 Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
 - 2. ASTM A 755 Specification for Steel Sheet, Metallic Coated by the Hot-Dip Process and Prepainted by the Coil-Coating Process for Exterior Exposed Building Products.
 - 3. ASTM A 792 Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process.
 - 4. ASTM A 240 Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications
 - 5. ASTM C 518 Standard Test Method for Steady State Heat Flux Measurements and Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus.
 - 6. ASTM C 1363 Standard Test Method for Thermal Performance of Building Materials and Envelope Assemblies by Means of a Hot Box Apparatus
 - 7. ASTM D 1621 Compressive Properties of Rigid Cellular Plastics.

- 8. ASTM D 1622 Apparent Density of Rigid Cellular Plastics.
- 9. ASTM D 2244 Test Method for Calculation of Color Differences from Instrumentally Measured Color Coordinates.
- 10. ASTM D 4214 Test Methods for Evaluating Degree of Chalking of Exterior Paint Films.
- 11. ASTM D 6226 Standard Test Method for Open Cell Content of Rigid Cellular Plastics
- 12. ASTM E 72 Standard Test Methods of Conducting Strength Tests of Panels for Building Construction.
- 13. ASTM E 84 Test Methods for Surface Burning Characteristics of Building Materials.
- 14. ASTM E 283 Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen.
- 15. ASTM E 331 Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference.
- 16. ASTM E 1592 Standard Test Method for Structural Performance of Sheet Metal Roof and Siding Systems by Uniform Static Air Pressure Difference.
- F. National Fire Protection Association (NFPA)
 - 1. NFPA 259 Test Method for Potential Heat of Building Materials.
 - 2. NFPA 285 Evaluation of Fire Propagation Characteristics of Exterior Non-Load Bearing Wall Assemblies.
 - 3. NFPA 286 Fire Test of Evaluating Conditions of Wall and Ceiling Finish to Roof Fire Growth.
- G. Green Seal (GS) www.greenseal.org
 - 1. GS-11 Green Seal Standard for Paints and Coatings, Edition 3.2, October 26, 2015.

1.3 QUALITY ASSURANCE

- A. Manufacturer/Source: Provide metal panel assemblies and accessories from a single manufacturer approved under an accredited third-party quality control program
- B. Manufacturer Qualifications: Approved manufacturer listed in this Section with minimum ten years' experience in the manufacturing of similar products and successful use in similar applications.
 - 1. Approval of Comparable Products: Submit the following in accordance with project substitution requirements, within time allowed for substitution review:

- a. Product data, including certified independent test data indicating compliance with requirements.
- b. Samples of each component.
- c. Sample submittal from similar project.
- d. Project references: Minimum of five installations not less than five years old, with Owner and Architect contact information.
- e. Sample warranty.
- f. Certificate from an accredited third-party Quality Control Program.
- 2. Substitutions following award of contract are not allowed except as stipulated in Division 01 General Requirements
- 3. Approved manufacturers must meet separate requirements of Submittals Article.
- C. Installer Qualifications: Experienced Installer [certified by metal panel manufacturer] with minimum of five years' experience with successfully completed projects of a similar nature and scope.
 - 1. Installer's Field Supervisor: Experienced mechanic certified by metal panel manufacturer supervising work on site whenever work is underway.
- D. Buy American Compliance: Materials provided under work of this Section shall comply with the following requirements:
 - 1. Buy American Act of 1933 BAA-41 U.S.C §§ 10a 10d.
 - 2. Buy American provisions of Section 1605 of the American Recovery and Reinvestment Act of 2009 (ARRA)

1.4 ADMINISTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Prior to erection of framing, conduct preinstallation meeting at site attended by Owner, Architect, metal panel installer, metal panel manufacturer's technical representative, inspection agency and related trade contractors.
 - 1. Coordinate building framing in relation to metal panel system.
 - 2. Coordinate openings and penetrations of metal panel system.

1.5 ACTION SUBMITTALS

- A. Product Data: Manufacturer's data sheets for specified products.
- B. Shop Drawings: Show layouts of metal panels. Include details of each condition of installation, panel profiles, and attachment to building. Provide details at a minimum scale 1-1/2-inch per foot

of edge conditions, joints, fastener and sealant placement, flashings, openings, penetrations, and special details. Make distinctions between factory and field assembled work.

- 1. Include data indicating compliance with performance requirements.
- 2. Indicate points of supporting structure that must coordinate with metal panel system installation.
- 3. Include structural data indicating compliance with performance requirements and requirements of local authorities having jurisdiction.
- C. Samples for Initial Selection: For each exposed product specified including sealants. Provide representative color charts of manufacturer's full range of colors.
- D. Samples for Verification:
 - 1. Provide 12-inch- (305 mm) long section of each metal panel profile.
 - 2. Provide color chip verifying color selection.

1.6 INFORMATIONAL SUBMITTALS

- A. Product Test Results: Indicating compliance of products with requirements.
- B. Qualification Information: For Installer
- C. Accreditation Certificate: Indicating that manufacturer is accredited under an accredited third-party Quality Control Program, including IAS AC472 and based upon chapter 17 of the International Building Code (IBC).
- D. Buy American Certification: Manufacturers' letters of compliance acceptable to authorities having jurisdiction, indicating products comply with requirements.
- E. Warranty:
 - 1. Submit manufacturer's written two (2) year limited warranty providing panels to be free from defects in materials and workmanship, beginning from the date of substantial completion excluding coil coatings (paint finishes) that are covered under a separate warranty.
 - 2. The installation contractor shall issue a separate warranty against defects in installed materials and workmanship, beginning from the date of substantial completion of the installation.

1.7 CLOSEOUT SUBMITTALS

- A. Maintenance data.
- B. Manufacturer's Warranty: Executed copy of manufacturer's warranty.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Protect products of metal panel system during shipping, handling, and storage to prevent staining, denting, deterioration of components or other damage. Protect panels and trim bundles during shipping. Protect painted surfaces with a protective covering before shipping.
 - 1. Deliver, unload, store, and erect metal panels and accessory items without deforming panels or exposing panels to surface damage from weather or construction operations.
 - 2. Store in accordance with Manufacturer's written instructions.
 - 3. Shield foam insulated metal panels from direct sunlight until all components are installed.

1.9 WARRANTY

- A. Special Manufacturer's Warranty: Submit Manufacturer's two (2) year limited warranty providing panels to be free from defects in materials and workmanship, beginning from the date of substantial completion excluding coil coatings (paint finishes) that are covered under a separate warranty.
- B. The installation contractor shall issue a separate warranty against defects in installed materials and workmanship, beginning from the date of substantial completion of the installation.
- C. Special Panel Finish Warranty: Submit Manufacturer's limited warranty on the exterior paint finish for adhesion to the metal substrate and limited warranty on the exterior paint finish for chalk and fade.
 - 1. Fluoropolymer Two-Coat System:
 - a. Color fading in excess of 5 or 10 for copper, silver metallic and bright red; Hunter units per ASTM D 2244.
 - b. Chalking in excess of 6 for copper, silver metallic and bright red or 8 rating per ASTM D 4214.
 - c. Failure of adhesion, peeling, checking, or cracking.
 - 2. Modified Silicone-Polyester Two-Coat System:
 - a. Color fading in excess of 5 or 7 for crimson red; Hunter units per ASTM D 2244.
 - b. Chalking in excess of 7 for crimson red.
 - c. Failure of adhesion, peeling, checking, or cracking.

1.10 PRODUCTS

1.11 MANUFACTURER

- A. Basis of Design Manufacturer: Metl-Span, a Nucor company; Lewisville, Texas Tel: 972.221.6656; Email: info@metlspan.com; Web: metlspan.com.
- B. Provide basis of design product, or comparable product approved by Architect prior to bid.

1.12 PERFORMANCE REQUIREMENTS

- A. General: Provide metal panel system meeting performance requirements as determined by application of specified tests by a qualified testing facility on manufacturer's standard assemblies.
- B. Structural Performance: Provide metal panel assemblies capable of withstanding the effects of indicated loads and stresses within limits and under conditions indicated, as determined by ASTM E 72 or ASTM E 1592 applied in accordance with ICC AC 04, Section 4, Panel Load Test Option or Section 5, Panel Analysis Option:
 - 1. Wind Loads: Determine loads based on applicable building code, wind speed, importance factor, exposure category, and internal pressure coefficient indicated on drawings.
 - a. Wind Negative Pressure: Certify capacity of metal panels by testing of proposed assembly.
 - 2. Deflection Limits: Withstand inward and outward wind-load design pressures in accordance with applicable building code with maximum deflection of 1/240 of the span with no evidence of failure.
- C. Fire Performance Characteristics: Provide metal panel systems with the following fire-test characteristics determined by indicated test standard as applied by testing and inspection agency acceptable to authorities having jurisdiction.
 - 1. Surface-Burning Characteristics: The insulating core shall have been tested per ASTM E 84. The core shall have:
 - a. Flame spread index: 25 or less.
 - b. Smoke developed index: 450 or less.
 - 2. Room Test Performance: FM Global 4880: The panel assembly shall not support a self-propagating fire which reaches any limits of the 50' (15.24m) high corner test structure as evidenced by flaming or material damage of the ceiling of the assembly.
 - 3. Fire Propagation: The fire assembly shall meet the requirements of the standard for NFPA 285
 - 4. Fire Growth: The fire assembly shall meet the requirements of the standard for NFPA 286
 - 5. Potential Heat: Determined in accordance with NFPA 259
 - 6. IBC Chapter 26: Panel Performance under the above test methods, shall meet the requirements of IBC, Chapter on foam plastics.
- D. Air Infiltration, ASTM E 283:
 - 1. Maximum 0.0002 cfm/sq. ft. (0.001 L/s per sq. m) at static air pressure difference of 1.57 lbf/sq. ft. (75 Pa).
 - 2. Maximum 0.0009 cfm/sq. ft. (0.005 L/s per sq. m) at static-air-pressure difference of 6.24 lbf/sq. ft. (300 Pa).

3. Maximum 0.01 cfm/sq. ft. (0.050 L/s per sq. m) at static-air-pressure difference of 20 lbf/sq. ft. (958 Pa).

E. Water Penetration Static Pressure:

- 1. ASTM E 331: No uncontrolled water penetration at a static pressure of 20 lbf/sq. ft. (958 Pa).
- 2. ASTM E 331 Modified (2-hour duration): No uncontrolled water penetration at a static pressure of 6.24 lbf/sq. ft. (300 Pa).
- F. Thermal Movements: Allow for thermal movements from variations in both ambient and internal temperatures. Accommodate movement of support structure caused by thermal expansion and contraction. Allow for deflection and design for thermal stresses caused by temperature differences from one side of the panel to the other.
- G. Thermal Performance: When tested in accordance with ASTM C 518, Measurement of Steady State thermal Transmission, the panels shall provide a k factor of 0.114 btu/sf/hr/deg F at a 35° F (1.67° C) mean temperature.

1.13 INSULATED METAL WALL PANELS

- A. Concealed Fastener, Insulated Metal Wall Panels with foam core: Structural metal panels consisting of exterior metal sheet with five major tapered inverted ribs 1 by 1/4 inches (25.4 by 6.4 mm) with a mesa profile between the inverted ribs, and interior metal sheet with a Mesa or Light Mesa profile, with factory foamed-in-place polyurethane core in thermally-separated profile, with tongue-and-groove panel edges, attached to supports using concealed fasteners.
 - 1. Basis of Design: Metl-Span, CF Flute
 - 2. G-90 galvanized coated steel conforming to ASTM A 653 or AZ-50 aluminum-zinc alloy coated steel, conforming to ASTM A 792/A 792M, minimum grade 33, pre-painted by the coil-coating process per ASTM A 755/A 755M.
 - a. Exterior Face Sheet: gauge thickness as required to meet loads indicated on drawings, with stucco embossed surface.
 - 1. Finish: Fluoropolymer two-coat system.
 - 2. Color: As selected by Architect from manufacturer's standard colors.
 - b. Interior Face Sheet: gauge thickness as required to meet loads indicated on drawings, with stucco embossed surface and Mesa or Light Mesa profile.
 - 1. Finish: Fluoropolymer two-coat system.
 - 2. Color: As selected by Architect from manufacturer's standard colors.
 - 3. Panel Width: 42 inches (1067 mm)
 - 4. Panel Thickness: 3 inch (76 mm)
 - 5. Insulating Core: Polyurethane with zero ozone depletion potential blowing agent
 - a. Closed Cell Content: 90% or more as determined by ASTM D 6226

- b. Compressive Strength: As required to meet structural performance requirements and with a minimum of 22 psi as determined by ASTM D 1621
- c. Shear Strength: As required to meet structural performance requirements and with a minimum of 36 psi as determined by ASTM C 273
- d. Tensile Strength: As required to meet structural performance requirements and with a minimum of 41 psi ASTM D 1623
- e. Minimum Density: 2.0 pcf (32 kg/m3) as determined by ASTM D 1622
- f. Thermal Resistance R-Value: 26.2.
- 6. Heat Transfer Coefficient (U-factor): 0.039 Btu/hr * sq. ft. * deg. F as determined by ASTM C 1363 at 35 degrees Fahrenheit mean temperature. Tested specimen must include at least two engaged side joints.

1.14 METAL WALL PANEL ACCESSORIES

- A. General: Provide complete metal panel assemblies incorporating trim, copings, fasciae, gutters and downspouts, and miscellaneous flashings. Provide required fasteners, closure strips, and sealants as indicated in manufacturer's written instructions.
- B. Flashing and Trim: Match material, thickness, and finish of metal panels.
- C. Panel Clips: ASTM A 653/A 653M, G90 (Z180) hot-dip galvanized zinc coating, one-piece, configured for concealment in panel joints, and identical to clips utilized in tests demonstrating compliance with performance requirements.
- D. Panel Fasteners: Self-drilling or Self-tapping screws and other acceptable fasteners recommended by metal panel manufacturer. Where exposed fasteners cannot be avoided, supply corrosion-resistant fasteners with heads matching color of metal panels by means of factory-applied coating, with weathertight resilient washers.

E. Joint Sealers:

- 1. Sealants: Provide Tape Mastic Sealants, Non-skinning sealants, and Urethane Sealants in accordance with manufacturers standards
- 2. Vertical Joint Gasket: Manufacturers standard EPDM gasket. Color: Black Or custom color.

1.15 FABRICATION

- A. General: Provide factory fabricated and finished metal panels, trim, and accessories meeting performance requirements, indicated profiles, and structural requirements.
- B. Fabricate metal panel joints configured to accept sealant providing weathertight seal.

C. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's written instructions, approved shop drawings, and project drawings.

1.16 FINISHES

- A. Finishes, General: Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturer's written instructions.
- B. Exterior Face Sheet Coil-Coated Finish System
 - 1. Silicone-Polyester Two-Coat System: 0.20 0.25 mil primer with 0.7 0.8 mil color coat.
 - a. Basis of Design: Metl-Span, Silicone Polyester.
 - 2. Fluoropolymer Two-Coat System: 0.2-0.3 mil primer with 0.7-0.8 mil 70 percent PVDF fluoropolymer color coat, meeting solar reflectance index requirements.
 - a. Basis of Design: Metl-Span, Fluoropolymer.
- C. Interior Face Sheet Coil-Coated Finish System
 - 1. Fluoropolymer Two-Coat System: 0.2-mil primer with 0.7 0.8 mil 70 percent PVDF fluoropolymer color coat
 - a. Basis of Design: Metl-Span, Fluoropolymer

PART 2 - EXECUTION

2.1 EXAMINATION

- A. Examine metal panel system substrate with Installer present. Inspect for erection tolerances and other conditions that would adversely affect installation of metal panels.
 - 1. Inspect framing that will support insulated metal panels to determine if support components are installed as indicated on approved shop drawings and are within tolerances acceptable to metal panel manufacturer and installer. Confirm presence of acceptable framing members at recommended spacing to match installation requirements of metal panels.
 - 2. Panel Support Tolerances: Confirm that metal panel supports are within tolerances acceptable to metal panel manufacturer but not greater than the following:
 - a. 1/4 inch (6 mm) in 20 foot (6100 mm) in any direction.
 - b. 3/8 inch (9 mm) over any single wall plane.
 - c. Girt Spacing 8 feet (2438 mm) or more: 1/4 inch (6 mm) out only.
 - d. Girt Spacing Less Than 8 feet (2438 mm): 1/8 inch (3 mm) out only.

- e. CF Architectural girt spacing less than 4 feet (1219 mm): 1/16 inch (1.5 mm) inch out only.
- B. Correct out-of-tolerance work and other deficient conditions prior to proceeding with insulated metal panel installation.

2.2 METAL PANEL INSTALLATION

- A. Concealed-Fastener Insulated Metal Panels with foam core: Install metal panel system in accordance with manufacturer's written instructions, approved shop drawings, and project drawings. Install metal panels in orientation, sizes, and locations indicated. Anchor panels and other components securely in place. Provide for thermal and structural movement.
- B. Attach panels to metal framing using screws, fasteners, sealants, and adhesives recommended for application by metal panel manufacturer.
 - 1. Fasten metal panels to supports with fasteners at each location indicated on approved shop drawings, at spacing and with fasteners recommended by manufacturer.
 - 2. Cut panels in field where required using manufacturer's recommended methods.
 - 3. Provide weatherproof jacks for pipe and conduit penetrating metal panels.
 - 4. Dissimilar Materials: Where elements of metal panel system will come into contact with dissimilar materials, treat faces and edges in contact with dissimilar materials as recommended by metal panel manufacturer
- C. Attach panel flashing trim pieces to supports using recommended fasteners and joint sealers
- D. Joint Sealers: Install sealants where indicated and where required for weatherproof performance of metal panel assemblies
 - 1. Seal panel base assembly, openings, panel head joints, and perimeter joints using sealants indicated in manufacturer's instructions
 - 2. Seal wall panel joints; apply continuously without gaps in accordance with manufacturer's written instructions, approved shop drawings, and project drawings
 - 3. Prepare joints and apply sealants per requirements of Division 07 Section.

2.3 ACCESSORY INSTALLATION

- A. General: Install metal panel accessories with positive anchorage to building and weather tight mounting; provide for thermal expansion. Coordinate installation with flashings and other components.
 - 1. Install components required for a complete metal panel assembly, including trim, copings, flashings, sealants, closure strips, and similar items.

- 2. Comply with details of assemblies utilized to establish compliance with performance requirements and manufacturer's written installation instructions.
- 3. Set units true to line and level as indicated. Install work with laps, joints, and seams that will be permanently weather resistant.

2.4 FIELD QUALITY CONTROL

2.5 CLEANING AND PROTECTION

- A. Remove temporary protective films immediately in accordance with metal panel manufacturer's instructions. Clean finished surfaces as recommended by metal panel manufacturer.
- B. Replace damaged panels and accessories that cannot be repaired to the satisfaction of the Architect.

END OF SECTION 074213

SECTION 077253

SNOW GUARDS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Rail-type, seam-mounted snow guards.

1.3 ACTION SUBMITTALS

- A. Product Data: Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for snow guards.
- B. Shop Drawings: Include roof plans showing layouts and attachment details of snow guards.
 - 1. Include details of rail-type snow guards.
 - 2. Include calculation of number and location of snow guards based on snow load, roof slope, roof type, components, spacings, and finish.

1.4 INFORMATIONAL SUBMITTALS

A. Product Test Reports: For each type of snow guard, for tests performed by manufacturer and witnessed by a qualified testing agency.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Performance Requirements: Provide snow guards that withstand exposure to weather and resist thermally induced movement without failure, rattling, or fastener disengagement due to defective manufacture, fabrication, installation, or other defects in construction.
 - 1. Temperature Change: 120 deg F.

B. Structural Performance:

1. Snow Loads: As indicated on Drawings.

2.2 RAIL-TYPE SNOW GUARDS

- A. Seam-Mounted, Rail-Type Snow Guards:
 - 1. Acceptable manufactures:
 - a. Berger
 - b. Alpine
 - c. Or engineer approved equal.
 - 2. Description: Snow guard rails fabricated from metal pipes, bars, or extrusions, anchored to brackets and equipped with one rail.
 - 3. Material and Finish: Aluminum; mill.
 - 4. Material and Finish: Stainless steel; mill.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances, snow guard attachment, and other conditions affecting performance of the Work.
 - 1. Verify compatibility with and suitability of substrates including compatibility with existing finishes or primers.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean and prepare substrates for bonding snow guards.
- B. Prime substrates according to snow guard manufacturer's written instructions.

3.3 INSTALLATION

- A. Install snow guards according to manufacturer's written instructions.
- B. Attachment for Standing-Seam Metal Roofing:
 - 1. Do not use fasteners that will penetrate metal roofing, or fastening methods that void metal roofing finish warranty.
 - 2. Seam-Mounted, Rail-Type Snow Guards: Stainless-steel clamps attached to vertical ribs of standing-seam metal roof panels.

END OF SECTION 077253

SECTION 133419

METAL BUILDING SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

- 1. Structural-steel framing.
- 2. Metal roof panels.
- 3. Metal wall panels.
- 4. Accessories.

B. Related Requirements:

- 1. Section 074116 "Insulated Metal Roof Panels"
- 2. Section 074213.19 "Insulated Metal Wall Panels"
- 3. Section 077253 "Snow Guards"

1.2 DEFINITIONS

A. Terminology Standard: See MBMA's "Metal Building Systems Manual" for definitions of terms for metal building system construction not otherwise defined in this Section or in standards referenced by this Section.

1.3 COORDINATION

- A. Coordinate sizes and locations of concrete foundations and casting of anchor-rod inserts into foundation walls and footings. Anchor rod installation, concrete, reinforcement, and formwork requirements are specified in Section 033000 "Cast-in-Place Concrete."
- B. Coordinate metal panel assemblies with rain drainage work, flashing, trim, and construction of supports and other adjoining work to provide a leakproof, secure, and noncorrosive installation.

1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project Site.
 - 1. Review methods and procedures related to metal building systems including, but not limited to, the following:
 - a. Condition of foundations and other preparatory work performed by other trades.
 - b. Structural load limitations.

- c. Construction schedule. Verify availability of materials and erector's personnel, equipment, and facilities needed to make progress and avoid delays.
- d. Required tests, inspections, and certifications.
- e. Unfavorable weather and forecasted weather conditions and impact on construction schedule.
- 2. Review methods and procedures related to metal roof panel assemblies including, but not limited to, the following:
 - a. Compliance with requirements for purlin and rafter conditions, including flatness and attachment to structural members.
 - b. Structural limitations of purlins and rafters during and after roofing.
 - c. Flashings, special roof details, roof drainage, roof penetrations, equipment curbs, and condition of other construction that will affect metal roof panels.
 - d. Temporary protection requirements for metal roof panel assembly during and after installation.
 - e. Roof observation and repair after metal roof panel installation.
- 3. Review methods and procedures related to metal wall panel assemblies including, but not limited to, the following:
 - a. Compliance with requirements for support conditions, including alignment between and attachment to structural members.
 - b. Structural limitations of girts and columns during and after wall panel installation.
 - c. Flashings, special siding details, wall penetrations, openings, and condition of other construction that will affect metal wall panels.
 - d. Temporary protection requirements for metal wall panel assembly during and after installation.
 - e. Wall observation and repair after metal wall panel installation.

1.5 ACTION SUBMITTALS

- A. Product Data: For each type of metal building system component.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for the following:
 - a. Metal roof panels.
 - b. Metal wall panels.
- B. Shop Drawings: Indicate components by others. Include full building plan, elevations, sections, details and the following:
 - 1. Anchor-Rod Plans: Submit anchor-rod plans and templates before foundation work begins. Include location, diameter, and minimum required projection of anchor rods required to attach metal building to foundation. Indicate column reactions at each location.
 - 2. Structural-Framing Drawings: Show complete fabrication of primary and secondary framing; include provisions for openings. Indicate welds and bolted connections, distinguishing between shop and field applications. Include transverse cross-sections.

- 3. Metal Roof and Wall Panel Layout Drawings: Show layouts of panels including methods of support. Include details of edge conditions, joints, panel profiles, corners, anchorages, clip spacing, trim, flashings, closures, and special details. Distinguish between factory- and field-assembled work; show locations of exposed fasteners.
 - a. Show wall-mounted items including personnel doors, vehicular doors, windows, and louvers.
- 4. Accessory Drawings: Include details of the following items, at a scale of not less than 1-1/2 inches per 12 inches (1:8)
 - a. Flashing and trim.
 - b. Gutters.
 - c. Downspouts.
- C. Door Schedule: For doors and frames. Use same designations indicated on Drawings. Include details of reinforcement.
- D. Delegated Design Submittals: For metal building systems.
 - 1. Include analysis data indicating compliance with performance requirements and design data signed and sealed by the qualified professional engineer responsible for their preparation, licensed in the State of New York.

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For manufacturer.
- B. Welding certificates.
- C. Letter of Design Certification: Signed and sealed by a qualified professional engineer, licensed in the State of New York. Include the following:
 - 1. Name and location of Project.
 - 2. Order number.
 - 3. Name of manufacturer.
 - 4. Name of Contractor.
 - 5. Building dimensions including width, length, height, and roof slope.
 - 6. Indicate compliance with AISC standards for hot-rolled steel and AISI standards for cold-rolled steel, including edition dates of each standard.
 - 7. Governing building code and year of edition.
 - 8. Design Loads: Include dead load, roof live load, collateral loads, roof snow load, deflection, wind loads/speeds and exposure, seismic design category or effective peak velocity-related acceleration/peak acceleration, and auxiliary loads (cranes).
 - 9. Load Combinations: Indicate that loads were applied acting simultaneously with concentrated loads, according to governing building code.
 - 10. Building-Use Category: Indicate category of building use and its effect on load importance factors.
- D. Material Test Reports: For each of the following products:

- 1. Structural steel including chemical and physical properties.
- 2. Bolts, nuts, and washers including mechanical properties and chemical analysis.
- 3. Tension-control, high-strength, bolt-nut-washer assemblies.
- 4. Shop primers.
- 5. Nonshrink grout.
- E. Source quality-control reports.
- F. Sample Warranties: For special warranties.

1.7 CLOSEOUT SUBMITTALS

A. Maintenance Data: For metal panel finishes to include in maintenance manuals.

1.8 QUALITY ASSURANCE

- A. Manufacturer Qualifications: A qualified manufacturer.
 - 1. Accreditation: Manufacturer's facility accredited according to IAS AC472, "Accreditation Criteria for Inspection Programs for Manufacturers of Metal Building Systems."
 - 2. Engineering Responsibility: Preparation of comprehensive engineering analysis and Shop Drawings by a professional engineer who is legally qualified to practice in jurisdiction where Project is located.
- B. Welding Qualifications: Qualify procedures and personnel according to the following:
 - 1. AWS D1.1/D1.1M, "Structural Welding Code Steel."
 - 2. AWS D1.3, "Structural Welding Code Sheet Steel."

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Deliver components, sheets, panels, and other manufactured items so as not to be damaged or deformed. Package metal panels for protection during transportation and handling.
- B. Unload and store metal panels in a manner to prevent bending, warping, twisting, and surface damage.
- C. Stack metal panels horizontally on platforms or pallets, covered with suitable weathertight and ventilated covering. Store metal panels to ensure dryness, with positive slope for drainage of water. Do not store metal panels in contact with other materials that might cause staining, denting, or other surface damage.

1.10 WARRANTY

A. Special Warranty on Metal Panel Finishes: Manufacturer agrees to repair finish or replace metal panels that show evidence of deterioration of factory-applied finishes within specified warranty period.

- 1. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:
 - a. Color fading more than 5 Hunter units when tested according to ASTM D2244.
 - b. Chalking in excess of a No. 8 rating when tested according to ASTM D4214.
 - c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.
- 2. Finish Warranty Period: 25 years from date of Substantial Completion.
- B. Special Weathertightness Warranty for Standing-Seam Metal Roof Panels: Manufacturer agrees to repair or replace standing-seam metal roof panel assemblies that leak or otherwise fail to remain weathertight within specified warranty period.
 - 1. Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain metal building system components, including primary and secondary framing and metal panel assemblies, from single source from single manufacturer.

2.2 SYSTEM DESCRIPTION

- A. Provide a complete, integrated set of mutually dependent components and assemblies that form a metal building system capable of withstanding structural and other loads, thermally induced movement, and exposure to weather without failure or infiltration of water into building interior.
- B. Primary-Frame Type:
 - 1. Rigid Modular: Solid-member, structural-framing system with interior columns.
- C. End-Wall Framing:
 - 1. Manufacturer's standard, for buildings not required to be expandable, consisting of primary frame, capable of supporting one-half of a bay design load, and end-wall columns or load-bearing end-wall and corner columns and rafters.
- D. Secondary-Frame Type: Manufacturer's standard purlins and joists and exterior-framed (bypass) girts at eave ends. Manufacturer's standard purlins and joists flush framed girts at gable ends.
- E. Eave Height: As indicated by nominal height on Drawings.
- F. Bay Spacing: As indicated on Drawings.
- G. Roof Slope: 2 inches per 12 inches (1:6)
- H. Roof System: Manufacturer's standard standing-seam insulated metal panel.

- 1. Liner Panels: None.
- I. Exterior Wall System: Manufacturer's standard foamed-insulation-core metal wall panels.
 - 1. Liner Panels: None.

2.3 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design metal building system.
- B. Structural Performance: Metal building systems to withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated according to procedures in MBMA's "Metal Building Systems Manual."
 - 1. Design Loads: As indicated on Drawings.
 - 2. Deflection and Drift Limits:
 - a. No greater than the following:
 - 1) Purlins and Rafters: Vertical deflection of 1/240 from imposed snow load and 1/180 total of the span.
 - 2) Girts: Horizontal deflection of 1/240 of the span.
 - 3) Metal Roof Panels: Vertical deflection of 1/240 from imposed snow load and 1/180 total of the span.
 - 4) Metal Wall Panels: Horizontal deflection of 1/240 total of the span.
 - 5) Design secondary-framing system to accommodate deflection of primary
 - 6) Lateral Drift: Maximum of 1/400 of the building height.
- C. Seismic Performance: Metal building system to withstand the effects of earthquake motions determined according to 2020 New York Building Code.
- D. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 - 1. Temperature Change: 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.
- E. Structural Performance for Metal Roof and Wall Panels: Provide metal panel systems capable of withstanding the effects of the following loads, based on testing according to ASTM E1592:
 - 1. Wind Loads: As indicated on Drawings.
- F. Air Infiltration for Metal Roof Panels: Air leakage of not more than 0.06 cfm/sq. ft. (0.3 L/s per sq. m) when tested according to ASTM E1680 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 6.24 lbf/sq. ft. (300 Pa).

- G. Water Penetration for Metal Roof Panels: No water penetration when tested according to ASTM E1646 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 6.24 lbf/sq. ft. (300 Pa).
- H. Water Penetration for Metal Wall Panels: No water penetration when tested according to ASTM E331 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 6.24 lbf/sq. ft. (300 Pa).
- I. Wind-Uplift Resistance: Provide metal roof panel assemblies that comply with UL 580 for wind-uplift-resistance class indicated.
 - 1. Uplift Rating: UL 90.
- J. Thermal Performance for Opaque Elements: Provide the following maximum U-factors and minimum R-values when tested according to ASTM C1363 or ASTM C518:
 - 1. Roof:
 - a. U-Factor: 0.035.
 - b. R-Value: 52.5
 - 2. Walls:
 - a. U-Factor: 0.052.
 - b. R-Value: 26.2

2.4 STRUCTURAL-STEEL FRAMING

- A. Structural Steel: Comply with AISC 360, "Specification for Structural Steel Buildings."
- B. Bolted Connections: Comply with RCSC's "Specification for Structural Joints Using High-Strength Bolts."
- C. Cold-Formed Steel: Comply with AISI's "North American Specification for the Design of Cold-Formed Steel Structural Members" for design requirements and allowable stresses.
- D. Primary Framing: Manufacturer's standard primary-framing system, designed to withstand required loads and specified requirements. Primary framing includes transverse and lean-to frames; rafters, rake, and canopy beams; sidewall, intermediate, end-wall, and corner columns; and wind bracing.
 - 1. General: Provide frames with attachment plates, bearing plates, and splice members. Factory drill for field-bolted assembly. Provide frame span and spacing indicated.
 - 2. Rigid Modular Frames: I-shaped frame sections fabricated from shop-welded, built-up steel plates or structural-steel shapes. Provide interior columns fabricated from round steel pipes or tubes, or shop-welded, built-up steel plates.
 - 3. Frame Configuration: Single gable.
 - 4. Exterior Column: Tapered.

- 5. Rafter: Tapered.
- E. End-Wall Framing: Manufacturer's standard primary end-wall framing fabricated for field-bolted assembly to comply with the following:
 - 1. End-Wall Rafters: C-shaped, cold-formed, structural-steel sheet; or I-shaped sections fabricated from shop-welded, built-up steel plates or structural-steel shapes.
- F. Secondary Framing: Manufacturer's standard secondary framing, including purlins, girts, eave struts, flange bracing, base members, gable angles, clips, headers, jambs, and other miscellaneous structural members. Unless otherwise indicated, fabricate framing from either cold-formed, structural-steel sheet or roll-formed, metallic-coated steel sheet, prepainted with coil coating, to comply with the following:
 - 1. Purlins:
 - a. C- or Z-shaped sections; fabricated from built-up steel plates, steel sheet, or structural-steel shapes; minimum 2-1/2-inch- (64-mm-) wide flanges.
 - 1) Depth: As needed to comply with system performance requirements. 12 gauge minimum.
 - 2. Girts: C- or Z-shaped sections; fabricated from built-up steel plates, steel sheet, or structural-steel shapes. Form ends of Z-sections with stiffening lips angled 40 to 50 degrees from flange, with minimum 2-1/2-inch- (64-mm-) wide flanges.
 - a. Depth: 8 Inches. 14 gauge minimum.
 - 3. Eave Struts: Unequal-flange, C-shaped sections; fabricated from built-up steel plates, steel sheet, or structural-steel shapes; to provide adequate backup for metal panels.
 - 4. Flange Bracing: Minimum 2-by-2-by-1/8-inch (51-by-51-by-3-mm) structural-steel angles or 1-inch- (25-mm-) diameter, cold-formed structural tubing to stiffen primary-frame flanges.
 - 5. Sag Bracing: Minimum 1-by-1-by-1/8-inch (25-by-25-by-3-mm) structural-steel angles.
 - 6. Base or Sill Angles: Manufacturer's standard base angle, minimum 3-by-2-inch (76-by-51-mm), fabricated from zinc-coated (galvanized) steel sheet.
 - 7. Purlin and Girt Clips: Manufacturer's standard clips fabricated from steel sheet. Provide galvanized clips where clips are connected to galvanized framing members.
 - 8. Framing for Openings: Channel shapes; fabricated from cold-formed, structural-steel sheet or structural-steel shapes. Frame head and jamb of door openings and head, jamb, and sill of other openings.
 - 9. Miscellaneous Structural Members: Manufacturer's standard sections fabricated from cold-formed, structural-steel sheet; built-up steel plates; or zinc-coated (galvanized) steel sheet; designed to withstand required loads.
- G. Bracing: Provide adjustable wind bracing as follows:
 - 1. Rigid Portal Frames: Fabricated from shop-welded, built-up steel plates or structural-steel shapes to match primary framing; of size required to withstand design loads.

H. Anchor Rods: Headed anchor rods as indicated in Anchor Rod Plan for attachment of metal building to foundation.

I. Materials:

- 1. W-Shapes: ASTM A992/A992M; ASTM A572/A572M, Grade 50 or 55 (345 or 380); or ASTM A529/A529M, Grade 50 or 55 (345 or 380).
- 2. Channels, Angles, M-Shapes, and S-Shapes: ASTM A36/A36M; ASTM A572/A572M, Grade 50 or 55 (345 or 380); or ASTM A529/A529M, Grade 50 or 55 (345 or 380).
- 3. Plate and Bar: ASTM A36/A36M; ASTM A572/A572M, Grade 50 or 55 (345 or 380); or ASTM A529/A529M, Grade 50 or 55 (345 or 380).
- 4. Steel Pipe: ASTM A53/A53M, Type E or S, Grade B.
- 5. Cold-Formed Hollow Structural Sections: ASTM A500, Grade B or C, structural tubing.
- Structural-Steel Sheet: Hot-rolled, ASTM A1011/A1011M, Structural Steel (SS), Grades 30 through 55 (205 through 380), or High-Strength Low-Alloy Steel (HSLAS) or High-Strength Low-Alloy Steel with Improved Formability (HSLAS-F), Grades 45 through 70 (310 through 480); or cold-rolled, ASTM A1008/A1008M, Structural Steel (SS), Grades 25 through 80 (170 through 550), or HSLAS, Grades 45 through 70 (310 through 480).
- 7. Metallic-Coated Steel Sheet: ASTM A653/A653M, SS, Grades 33 through 80 (230 through 550), or HSLAS or HSLAS-F, Grades 50 through 80 (340 through 550); with G60 (Z180) coating designation; mill phosphatized.
- 8. Metallic-Coated Steel Sheet Prepainted with Coil Coating: Steel sheet, metallic coated by the hot-dip process and prepainted by the coil-coating process to comply with ASTM A755/A755M.
 - a. Zinc-Coated (Galvanized) Steel Sheet: ASTM A653/A653M, SS, Grades 33 through 80 (230 through 550), or HSLAS or HSLAS-F, Grades 50 through 80 (340 through 550); with G90 (Z275) coating designation.
 - b. Aluminum-Zinc Alloy-Coated Steel Sheet: ASTM A792/A792M, SS, Grade 50 or 80 (340 or 550); with Class AZ50 (AZM150) coating.
- 9. Non-High-Strength Bolts, Nuts, and Washers: ASTM A307, Grade A, carbon-steel, hex-head bolts; ASTM A563 (ASTM A563M) carbon-steel hex nuts; and ASTM F844 plain (flat) steel washers.
 - a. Finish: Plain.
- 10. High-Strength Bolts, Nuts, and Washers, Grade A325 (Grade A325M): ASTM F3125/F3125M, Type 1, heavy-hex steel structural bolts; ASTM A563, Grade DH, (ASTM A563M, Class 10S) heavy-hex carbon-steel nuts; and ASTM F436/F436M, Type 1, hardened carbon-steel washers.
 - a. Finish: Plain.
- 11. High-Strength Bolts, Nuts, and Washers, Grade A490 (Grade A490M): ASTM F3125/F3125M, Type 1, heavy-hex steel structural bolts or Grade F2280 tension-control, bolt-nut-washer assemblies with splined ends; ASTM A563, Grade DH, (ASTM A563M, Class 10S) heavy-hex carbon-steel nuts; and ASTM F436/F436M, Type 1, hardened carbon-steel washers; all with plain finish.

- 12. Tension-Control, High-Strength Bolt-Nut-Washer Assemblies: ASTM F3125/F3125M, Grade F1852, Type 1, heavy-hex or round head assemblies consisting of steel structural bolts with splined ends; ASTM A563, Grade DH, (ASTM A563M, Class 10S) heavy-hex carbon-steel nuts; and ASTM F436/F436M, Type 1 hardened carbon-steel washers.
 - a. Finish: Plain
- 13. Headed Anchor Rods: ASTM F1554, Grade 36.
 - a. Configuration: Straight.
 - b. Nuts: ASTM A563 (ASTM A563M) heavy-hex carbon steel.
 - c. Plate Washers: ASTM A36/A36M carbon steel.
 - d. Washers: ASTM F436 (ASTM F436M) hardened carbon steel.
 - e. Finish: Hot-dip zinc coating, ASTM F2329, Class C.
- J. Finish: Factory primed. Apply specified primer immediately after cleaning and pretreating.
 - 1. Clean and prepare in accordance with SSPC-SP2.
 - 2. Coat with manufacturer's standard primer. Apply primer to primary and secondary framing to a minimum dry film thickness of 1 mil (0.025 mm).
 - a. Prime secondary framing formed from uncoated steel sheet to a minimum dry film thickness of 0.5 mil (0.013 mm) on each side.

2.5 METAL ROOF PANELS

A. Refer to Section 074116 "Insulated Metal Roof Panels"

2.6 METAL WALL PANELS

A. Refer to Section 074213.19 "Insulated Metal Wall Panels"

2.7 METAL SOFFIT PANELS

- A. General: Provide factory-formed metal soffit panels designed to be installed by lapping and interconnecting side edges of adjacent panels and mechanically attaching through panel to supports using concealed fasteners and factory-applied sealant in side laps. Include accessories required for weathertight installation.
- B. Metal Soffit Panels: Match material of metal wall panels.
 - 1. Finish: Match finish and color of metal wall panels.

2.8 ACCESSORIES

A. General: Provide accessories as standard with metal building system manufacturer and as specified. Fabricate and finish accessories at the factory to greatest extent possible, by

manufacturer's standard procedures and processes. Comply with indicated profiles and with dimensional and structural requirements.

- 1. Form exposed sheet metal accessories that are without excessive oil-canning, buckling, and tool marks and that are true to line and levels indicated, with exposed edges folded back to form hems.
- B. Roof Panel Accessories: Provide components required for a complete metal roof panel assembly including copings, fasciae, corner units, ridge closures, clips, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal roof panels unless otherwise indicated.
 - 1. Closures: Provide closures at eaves and ridges, fabricated of same material as metal roof panels.
 - 2. Clips: Manufacturer's standard, formed from stainless steel sheet, designed to withstand negative-load requirements.
 - 3. Backing Plates: Provide metal backing plates at panel end splices, fabricated from material recommended by manufacturer.
 - 4. Closure Strips: Closed-cell, expanded, cellular, rubber or crosslinked, polyolefin-foam or closed-cell laminated polyethylene; minimum 1-inch- (25-mm-) thick, flexible closure strips; cut or premolded to match metal roof panel profile. Provide closure strips where indicated or necessary to ensure weathertight construction.
- C. Wall Panel Accessories: Provide components required for a complete metal wall panel assembly including copings, fasciae, mullions, sills, corner units, clips, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal wall panels unless otherwise indicated.
 - 1. Closures: Provide closures at eaves and rakes, fabricated of same material as metal wall panels.
 - 2. Backing Plates: Provide metal backing plates at panel end splices, fabricated from material recommended by manufacturer.
 - 3. Closure Strips: Closed-cell, expanded, cellular, rubber or crosslinked, polyolefin-foam or closed-cell laminated polyethylene; minimum 1-inch- (25-mm-) thick, flexible closure strips; cut or premolded to match metal wall panel profile. Provide closure strips where indicated or necessary to ensure weathertight construction.
- D. Flashing and Trim: Zinc-coated (galvanized) or aluminum-zinc alloy-coated steel sheet, 0.018-inch (0.46-mm) nominal uncoated steel thickness, prepainted with coil coating; finished to match adjacent metal panels.
 - 1. Provide flashing and trim as required to seal against weather and to provide finished appearance. Locations include, but are not limited to, eaves, rakes, corners, bases, framed openings, ridges, fasciae, and fillers.
- E. Gutters: Metl Span or approved equal and rack trim, end caps, corners, etc. Detailed in accordance with manufacturer's specifications and installation guidelines.
- F. Downspouts: Zinc-coated (galvanized) or aluminum-zinc alloy-coated steel sheet, 0.018-inch (0.46-mm) nominal uncoated steel thickness, prepainted with coil coating; finished to match

metal wall panels. Fabricate in minimum 10-foot- (3-m-) long sections, complete with formed elbows and offsets.

- 1. Mounting Straps: Fabricated from same material and finish as gutters.
- G. Pipe Flashing: Premolded, EPDM pipe collar with flexible aluminum ring bonded to base.

H. Materials:

- 1. Fasteners: Self-tapping screws, bolts, nuts, self-locking rivets and bolts, end-welded studs, and other suitable fasteners designed to withstand design loads. Provide fasteners with heads matching color of materials being fastened by means of plastic caps or factory-applied coating.
- 2. Fasteners for Metal Roof Panels:
 - a. Refer to Secion 074116 "Insulated Metal Roof Panels"
- 3. Fasteners for Metal Wall Panels:
 - a. Refer to Section 074213.19 "Insulated Metal Wall Panels"
- 4. Fasteners for Flashing and Trim: Blind fasteners or self-drilling screws with hex washer head.
- 5. Blind Fasteners: High-strength aluminum or stainless steel rivets.
- 6. Corrosion-Resistant Coating: Cold-applied asphalt mastic, compounded for 15-mil (0.4-mm) dry film thickness per coat. Provide inert-type noncorrosive compound free of asbestos fibers, sulfur components, and other deleterious impurities.
- 7. Nonmetallic, Shrinkage-Resistant Grout: ASTM C1107/C1107M, factory-packaged, nonmetallic aggregate grout, noncorrosive, nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.
- 8. Metal Panel Sealants:
 - a. Sealant Tape: Pressure-sensitive, 100 percent solids, gray polyisobutylene-compound sealant tape with release-paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape of manufacturer's standard size.
 - b. Joint Sealant: ASTM C920; one part elastomeric polyurethane or polysulfide; of type, grade, class, and use classifications required to seal joints in metal panels and remain weathertight; and as recommended by metal building system manufacturer.

2.9 FABRICATION

- A. General: Design components and field connections required for erection to permit easy assembly.
 - 1. Mark each piece and part of the assembly to correspond with previously prepared erection drawings, diagrams, and instruction manuals.
 - 2. Fabricate structural framing to produce clean, smooth cuts and bends. Punch holes of proper size, shape, and location. Members to be free of cracks, tears, and ruptures.

- B. Tolerances: Comply with MBMA's "Metal Building Systems Manual" for fabrication and erection tolerances.
- C. Primary Framing: Shop fabricate framing components to indicated size and section, with baseplates, bearing plates, stiffeners, and other items required for erection welded into place. Cut, form, punch, drill, and weld framing for bolted field assembly.
 - 1. Make shop connections by welding or by using high-strength bolts.
 - 2. Join flanges to webs of built-up members by a continuous, submerged arc-welding process.
 - 3. Brace compression flange of primary framing with steel angles or cold-formed structural tubing between frame web and purlin web or girt web, so flange compressive strength is within allowable limits for any combination of loadings.
 - 4. Weld clips to frames for attaching secondary framing if applicable, or punch for bolts.
 - 5. Shop Priming: Prepare surfaces for shop priming according to SSPC-SP 2. Shop prime primary framing with specified primer after fabrication.
- D. Secondary Framing: Shop fabricate framing components to indicated size and section by roll forming or break forming, with baseplates, bearing plates, stiffeners, and other plates required for erection welded into place. Cut, form, punch, drill, and weld secondary framing for bolted field connections to primary framing.
 - 1. Make shop connections by welding or by using non-high-strength bolts.
 - 2. Shop Priming: Prepare uncoated surfaces for shop priming according to SSPC-SP 2. Shop prime uncoated secondary framing with specified primer after fabrication.
- E. Metal Panels: Fabricate and finish metal panels at the factory to greatest extent possible, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements. Comply with indicated profiles and with dimensional and structural requirements.
 - 1. Provide panel profile, including major ribs and intermediate stiffening ribs, if any, for full length of metal panel.

2.10 SOURCE QUALITY CONTROL

- A. Special Inspection: Owner will engage a qualified special inspector to perform source quality control inspections and to submit reports.
 - 1. Accredited Manufacturers: Special inspections will not be required if fabrication is performed by an IAS AC472-accredited manufacturer approved by authorities having jurisdiction to perform such Work without special inspection.
 - a. After fabrication, submit copy of certificate of compliance to authorities having jurisdiction, certifying that Work was performed according to Contract requirements.

PART 3 - EXECUTION (Not Used)

END OF SECTION 133419